

| | | | | |
|---------------------|----------------|---------------------------|--------------|-----------|
| FAP RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 331 | 3-2, 8X-1, 4-2 | SALINE | 233 | 7 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |

SUMMARY OF QUANTITIES
US 45 - IL 13 RELOCATION - CONTRACT 5

| | | COUNTY: | | SALINE | |
|---------------------|--|-------------------------|----------------|-------------------|-------------------|
| | | LOCATION: | | URBAN | |
| | | CONSTRUCTION TYPE CODE: | | 1000-2A | Y031-1F |
| | | FUNDING: | | FED 80% STATE 20% | FED 80% STATE 20% |
| CODE NUMBER | ITEM DESCRIPTION | UNIT | TOTAL QUANTITY | ROAD FOUR LANE | TRAFFIC SIGNAL |
| 60224005 | MANHOLES TYPE A, 6' DIA TYPE 8 GRATE | EACH | 1 | 1 | |
| 60236200 | INLETS, TYPE A, TYPE 8 GRATE | EACH | 13 | 13 | |
| 60240225 | INLETS, TYPE B, TYPE 4 FRAME AND GRATE | EACH | 1 | 1 | |
| 60243500 | INLETS, SPECIAL, TYPE 3, 6' | EACH | 95 | 95 | |
| 60255500 | MANHOLES TO BE ADJUSTED | EACH | 8 | 8 | |
| 60263200 | INLETS TO BE RECONSTRUCTED WITH NEW TYPE 4 FRAME AND GRATE | EACH | 8 | 8 | |
| 60265700 | VALVE VAULTS TO BE ADJUSTED | EACH | 3 | 3 | |
| 60266500 | VALVE VAULTS TO BE REMOVED | EACH | 2 | 2 | |
| 60500040 | REMOVING MANHOLES | EACH | 3 | 3 | |
| 60500060 | REMOVING INLETS | EACH | 27 | 27 | |
| 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 | FOOT | 17,785 | 17,785 | |
| 60608600 | COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 | FOOT | 87 | 87 | |
| 60610400 | COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24 | FOOT | 130 | 130 | |
| 60618300 | CONCRETE MEDIAN SURFACE, 4 INCH | SQ FT | 29,794 | 29,794 | |
| 60620300 | CONCRETE MEDIAN, TYPE SB-6.24 (SPECIAL) | SQ FT | 9,317 | 9,317 | |
| 60622320 | CONCRETE MEDIAN, TYPE SM4-24 | SQ FT | 1,307 | 1,307 | |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 51 | 51 | |
| 66600105 | FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS | EACH | 85 | 85 | |
| 66900105 | UNDERGROUND STORAGE TANKS REMOVAL | EACH | 1 | 1 | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | |
| 70101830 | TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21 | L SUM | 1 | 1 | |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1 | 1 | |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1 | 1 | |
| 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L SUM | 1 | 1 | |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DA | 600 | 600 | |
| 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 16 | 16 | |
| * 72000100 | SIGN PANEL, TYPE 1 | SQ FT | 102 | | 102 |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 1,950 | 1,950 | |
| 70300520 | PAVEMENT MARKING TAPE - TYPE III, 4" | FOOT | 10,300 | 10,300 | |
| X 70322752 | WORK ZONE PAVEMENT MARKING REMOVAL | FOOT | 15,200 | 15,200 | |
| 78008200 | POLYUREA PAVEMENT MARKING TYPE 1 - LETTERS & SYMBOLS | SQ FT | 692 | 692 | |
| 78008210 | POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4" | FOOT | 6,569 | 6,569 | |
| 78008230 | POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6" | FOOT | 5,365 | 5,365 | |
| * 78008240 | POLYUREA PAVEMENT MARKING TYPE 1 - LINE 8" | FOOT | 512 | 512 | |
| 78008250 | POLYUREA PAVEMENT MARKING TYPE 1 - LINE 12" | FOOT | 1,376 | 1,376 | |
| 78008270 | POLYUREA PAVEMENT MARKING TYPE 1 - LINE 24" | FOOT | 371 | 371 | |
| 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 271 | 271 | |

* SPECIALTY ITEMS

Rev. SUMMARY OF QUANTITIES

US DB
 DRAWN BY
 CHECKED BY

| |
|--|
| M:\PROJECTS\PROJ3526\ROADWAY\COMMON\ASB\SUMMARY SHEETS.DGN |
| REV: 01/08 |
| DATE: 01/08 |