

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	3-2, 8X-1, 4-2	SALINE	233	27
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STORM SEWERS & END SECTIONS

LOCATION STA TO STA	STORM SEWERS, CLASS A, TYPE 2								P.R.C. FLARED END SECTION	P.R.C. FLARED END SECTION	P.R.C. FLARED END SECTION	P.R.C. FLARED END SECTION	P.R.C. FLARED END SECTION	TRENCH BACKFILL
	12 INCH FEET	15 INCH FEET	18 INCH FEET	24 INCH FEET	30 INCH FEET	36 INCH FEET	42 INCH FEET	48 INCH FEET	12 INCH EACH	21 INCH EACH	24 INCH EACH	30 INCH EACH	36 INCH EACH	CU.YD.
STA 1039+90 RT TO STA 1041+20 RT	124													96.2
STA 1041+20 RT TO STA 1041+20 RT	8													
STA 1044+70 RT TO STA 1046+85 RT	209													22.8
STA 1046+85 RT TO STA 1049+00 RT			209											21.9
STA 1049+00 RT TO STA 1051+15 RT			209											29.9
STA 1051+15 RT TO STA 1052+04 RT			83											20.3
STA 1052+04 RT TO STA 1052+04 RT				30										7.9
STA 1052+04 RT TO STA 1052+04 RT						22								
STA 1052+04 RT													1	
STA 1052+70 RT												1		
STA 1052+70 RT TO STA 1052+70 RT					16									
STA 1052+70 RT TO STA 1053+70 RT			94											16.9
STA 1052+70 RT TO STA 1052+70 LT							72							47.7
STA 1053+70 RT TO STA 1055+75 RT			199											33.4
STA 1055+75 RT TO STA 1057+36 RT			155											24.0
STA 1057+36 RT TO STA 1059+02 RT			159											24.6
STA 1059+02 RT TO STA 1060+59 RT	151													23.0
STA 1060+59 RT TO STA 1062+03 RT	138													19.6
STA 1068+56 RT TO STA 1070+00 RT	138													16.8
STA 1070+00 RT TO STA 1071+23 RT	117													13.1
STA 1071+23 RT TO STA 1071+45 RT				17										1.2
STA 1071+23 RT TO STA 1071+23 RT	8													
STA 1071+45 RT TO STA 1071+89 RT				41										2.9
SUBTOTALS	1270	147	1217	387	16	189	72	0	0	1	0	1	2	807.7
GRANGER STREET														
STA 8+15 RT TO STA 8+57 RT			36											5.6
STA 8+57 RT TO STA 8+90 RT			27											4.5
STA 8+90 RT TO STA 8+90 RT				54										
STA 8+90 RT											1			
STA 10+79 RT TO STA 10+79 RT					52									
STA 14+94 RT TO STA 14+94 RT	7													
SUBTOTALS	7	0	63	54	52	0	0	0	0	0	1	0	0	10.1
GRANGER STREET														
STA 8+72 LT TO STA 8+89 LT	15													1.5
STA 8+89 LT TO STA 8+90 RT	35													4.3
STA 10+82 LT												1		
STA 10+82 LT TO STA 10+79 LT					38									
STA 10+79 LT TO STA 10+79 RT					46									36.6
STA 12+19 LT									1					
STA 12+19 LT TO STA 12+19 LT	22													
STA 12+19 LT TO STA 11+83 RT	46													2.9
STA 12+19 LT TO STA 12+51 RT	43													2.2
STA 14+94 LT									1					
STA 14+94 LT TO STA 14+94 LT	30													
STA 14+94 LT TO STA 14+94 RT	29													3.2
SUBTOTALS	220	0	0	0	84	0	0	0	2	0	0	1	0	50.8
ILL. 34 -- MAIN STREET														
STA 1668+44 RT TO STA 1669+10 RT						60								37.1
STA 1669+10 RT TO STA 1669+63 RT								47						29.8
STA 1669+63 RT TO STA 1669+61 RT			16											8.4
STA 1669+61 RT TO STA 1669+87 RT			22											7.9
STA 1669+63 RT TO STA 1670+12 RT								46						24.8
STA 1669+87 RT TO STA 1669+94 RT			4											
STA 1670+12 RT TO STA 1670+68 RT								50						29.4
STA 1670+68 RT TO STA 1671+50 RT								77						57.8
STA 1671+50 RT TO STA 1671+50 RT				75										22.3
STA 1671+50 RT TO STA 1672+94 RT								140						21.8
STA 1672+94 RT TO STA 1672+94 RT								6						15.5
STA 1672+94 RT TO STA 1672+71 RT						23								9.1
STA 1672+94 RT TO STA 1673+79 RT						80								9.6
STA 1673+79 RT TO STA 1674+33 RT			48											10.2
STA 1038+25 RT TO STA 1672+71 RT						40								

DRAWN BY JS
CHECKED BY DB

PROJECT: PROJ3526/ROADWAY/COMMON
SHEET: 27 OF 27
DATE: 10/13/2006