

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	*	WAYNE & WHITE	15	10
STA. 448+99		TO STA. 61+90		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

* (104,105)RS-4,(108)RS-3

PAVEMENT SCHEDULE

LOCATION STATION TO STATION	LENGTH (FOR INFORMATION ONLY) FEET	HOT-MIX ASPHALT BINDER COURSE TONS	HOT-MIX ASPHALT SURFACE COURSE TONS	PRIME COAT	AGGREGATE TONS	SHOULDERS		HOT-MIX ASPHALT SURFACE REMOVAL 3/4" SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2" SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL 2 1/4" SQ YD
				BITUMINOUS MATERIALS GAL		AGGREGATE TYPE B TONS	HOT-MIX ASPHALT TONS			
STA 448+99 TO STA 470+06	2107.00	255.65	511.30	1096	18.3	81.4	22.4		6264.7	
STA 470+06 TO STA 509+00	3893.40	472.40	944.80	2025	33.7	122.9				11247.6
STA 509+00 TO STA 559+04.13	4998.03	606.43	1212.86	2599	43.3	213.5			14438.8	
STA 568+70.71 TO STA 598+32	2961.29	359.30	718.61	1540	25.7	126.5			8554.8	
STA 599+20 TO STA 614+69	1549.00	187.95	375.89	805	13.4	66.2			4474.9	
STA 614+69 TO STA 614+97	28.00	6.79	13.58	15	0.2			80.9		
STA 614+97 TO STA 654+28.8	3931.80	477.06	954.12	2045	34.1	167.9			11358.5	
STA 655+27.2 TO STA 688+74	3328.80	403.89	807.79	1731	28.8	142.2			9616.5	
STA 688+74 TO STA 696+27	753.00	91.36	182.73	392	6.5	14.3				2175.3
STA 696+27 TO STA 704+47	803.90	97.54	195.08	418	7.0	34.3			2322.4	
STA 704+47 TO STA 709+76.5	703.00	85.30	170.59	366	6.1		78.7		2655.8	
STA 709+76.5 TO STA 718+38.5	862.00	104.59	209.18	448	7.5	18.4	48.3		2873.3	
STA 718+38.5 TO STA 808+02	8890.70	1078.74	2157.48	4623	77.1	379.7		92.4	25684.2	
STA 808+88 TO STA 872+93.3	6739.70	817.75	1635.50	3505	58.4	287.8			19470.2	
STA 872+93.3 TO STA 880+17	723.00	87.72	175.45	376	6.3		81.0		2731.4	
STA 880+17 TO STA 882+90	273.00	33.12	66.25	142	2.4	5.8	15.3		910.0	
STA 882+90 TO STA 931+87	4897.00	594.17	1188.34	2546	42.4	209.1			14146.9	
STA 931+87 TO STA 932+19	32.00	7.77	15.54	17	0.3					
STA 932+19 TO STA 954+28	2209.00	268.03	536.05	1149	19.1	94.3			6381.6	
STA 954+28 TO STA 954+76	48.00	11.65	23.30	25	0.4			138.7		
STA 954+76 TO STA 18+41	8044.50	976.07	1952.13	4183	69.7	343.6			23239.7	
STA 18+41 TO STA 7+87	2628.30	318.90	637.80	1367	22.8	7.6				7592.9
STA 9+43 TO STA 22+53	1289.20	156.42	312.85	670	11.2		144.4			4870.6
STA 22+53 TO STA 61+28	3875.00	470.17	940.33	2015	33.6	165.5			11194.4	
STA 61+28 TO STA 61+90	62.00	14.00	27.00	58	1.0	2.4				320.0
TOTALS		7957	15939	34154	569	2484	390	312	166319	26207

PATCHING SCHEDULE

STATION TO STATION	MP TO MP	PATCH DEPTH	TY 1 (SQ YD)	TY 2 (SQ YD)	TY 3 (SQ YD)	TY 4 (SQ YD)
STA 448+99 TO STA 470+06	MP 0.0 TO MP 0.4	19"	28	45	20	27
STA 470+06 TO STA 688+74	MP 0.4 TO MP 4.5	13"	51	575		27
STA 688+74 TO STA 696+27	MP 4.5 TO MP 4.7	19"		6		
STA 696+27 TO STA 61+0	MP 4.7 TO MP 12.7	17"	47	1554	60	174
TOTALS			126	2180	80	228

PLOT DATE = 10/19/2006
 FILE NAME = c:\pav\pav\p98206.dwg
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = rcooper

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. DATE DRAWN BY CHECKED BY

SCHEDULES OF QUANTITIES