


80% FEDERAL
20% STATE

80% FEDERAL
20% STATE

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | |
|-----------------------|--|-------|------------------|------------------------|------------------|
| CODE NO | ITEM | UNIT | | 0013 SN 051-0022 | 0013 SN 051-0023 |
| 51200957 | FURNISHING METAL SHELL PILES 12" X 0.250" | FOOT | 1500 | 750 | 750 |
| 51202305 | DRIVING PILES | FOOT | 1500 | 750 | 750 |
| 51203200 | TEST PILE METAL SHELLS | EACH | 4 | 2 | 2 |
| 51500100 | NAME PLATES | EACH | 2 | 1 | 1 |
| 52200010 | TEMPORARY SHEET PILING | SO FT | 474 | 237 | 237 |
| 58600101 | GRANULAR BACKFILL FOR STRUCTURES | CU YD | 170 | 85 | 85 |
| 59100100 | GEOCOMPOSITE WALL DRAIN | SO YD | 108 | 54 | 54 |
| 60146304 | PIPE UNDERDRAINS FOR STRUCTURES 4" | FOOT | 244 | 122 | 122 |
| * 63000001 | STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS | FOOT | 1088 | 538 | 550 |
| * 63100045 | TRAFFIC BARRIER TERMINAL, TYPE 2 | EACH | 2 | 1 | 1 |
| * 63100070 | TRAFFIC BARRIER TERMINAL, TYPE 5 | EACH | 2 | 1 | 1 |
| * 63100085 | TRAFFIC BARRIER TERMINAL, TYPE 6 | EACH | 4 | 2 | 2 |
| * 63100167 | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT | EACH | 4 | 2 | 2 |

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | |
|-----------------------|---|--------|------------------|------------------------|------------------|
| CODE NO | ITEM | UNIT | | 0013 SN 051-0022 | 0013 SN 051-0023 |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 896 | 448 | 448 |
| 64200116 | SHOULDER RUMBLE STRIPS, 16 INCH | FOOT | 2386 | 1205 | 1181 |
| 66700305 | PERMANENT SURVEY MARKERS, TYPE II | EACH | 2 | 1 | 1 |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 10 | 5 | 5 |
| 67100100 | MOBILIZATION | L SUM | 1 | 0.5 | 0.5 |
| 70100207 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 | EACH | 2 | 1 | 1 |
| 70100800 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 | L SUM | 1 | 0.5 | 0.5 |
| 70107007 | PAVEMENT MARKING BLACKOUT TAPE, 7" | FOOT | 2164 | 1079 | 1085 |
| 70107025 | CHANGEABLE MESSAGE SIGN | CAL DA | 28 | 14 | 14 |
| 70300100 | SHORT TERM PAVEMENT MARKING | FOOT | 70 | 35 | 35 |
| 70300150 | SHORT TERM PAVEMENT MARKING REMOVAL | SO FT | 1297 | 647 | 650 |
| 70300241 | TEMPORARY PAVEMENT MARKING - LINE 6"- PAINT | FOOT | 3382 | 1703 | 1679 |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 825 | 412.5 | 412.5 |



* SPECIALTY ITEM

⚠️ REVISED 1-4-2024

MODEL: Default
FILE NAME: p:\w\p\paw\benfley.com\p\p\p\DOT\Documents\DOT_Offices\District 2\Projects\74A09\CADD\Drawings\74A09-SP-S00.dgn

| | | |
|------------------------------|------------|-----------|
| USER NAME = jessica.hille | DESIGNED - | REVISED - |
| PLOT SCALE = 100.0000' / in. | DRAWN - | REVISED - |
| PLOT DATE = 10/6/2023 | CHECKED - | REVISED - |
| | DATE - | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF
QUANTITIES

SCALE: SHEET 2 OF 3 SHEETS STA. TO STA.

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------------|---------------|--------------------|--------------|-----------|
| 327 | (51-24HB-1)BR | LAWRENCE | 87 | 4 |
| | | CONTRACT NO. 74A09 | | |
| ILLINOIS FED. AID PROJECT | | | | |