

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				ROADWAY 0006 RURAL
44213000	PATCHING REINFORCEMENT	SQ YD	1302	1302
44213200	SAW CUTS	FOOT	4646	4646
44213204	TIE BARS 3/4"	EACH	147	147
67100100	MOBILIZATION	L SUM	1	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	320	320
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	380	380
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	127	127
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	2363	2363
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	92	92
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	92	92
X4420581	CLASS A PATCHES, TYPE I, 13 INCH (SPECIAL)	SQ YD	42	42
X4420583	CLASS A PATCHES, TYPE II, 13 INCH (SPECIAL)	SQ YD	547	547



CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				ROADWAY 0006 RURAL
X4420585	CLASS A PATCHES, TYPE III, 13 INCH (SPECIAL)	SQ YD	228	228
X4420587	CLASS A PATCHES, TYPE IV, 13 INCH (SPECIAL)	SQ YD	485	485
Ø Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	500	500

Ø 0042

* SPECIALTY ITEM

△ REVISED 1-2-2024

REV. - MS

MODEL: INCDLNAME\$
FILE NAME: \$FILES

USER NAME = \$USERS	DESIGNED - _____	REVISED - _____
	DRAWN - _____	REVISED - _____
PLOT SCALE = \$\$SCALE\$	CHECKED - _____	REVISED - _____
PLOT DATE = \$DATES	DATE - _____	REVISED - _____

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: 1"=50' SHEET 1 OF 1 SHEETS STA. + TO STA. +

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	61-(1,1-1,1-2,2,3,3-1,4,5,5-1,6)PP	MARION	10	3
CONTRACT NO. 76T25				

ILLINOIS | FED. AID PROJECT

MODEL: Corridors 12.20.23 [Sheet]
 FILE NAME: c:\pwworking\robert.hughes@illinois.gov\0892515\0816725-shr-schedule.dgn

CLASS A PATCHING SCHEDULE												
NB/SB	DL/PL	MM	LENGTH	WIDTH	CLASS A PATCHES, TYPE I, 13 INCH (SPECIAL)	CLASS A PATCHES, TYPE II, 13 INCH (SPECIAL)	CLASS A PATCHES, TYPE III, 13 INCH (SPECIAL)	CLASS A PATCHES, TYPE IV, 13 INCH (SPECIAL)	PATCHING REINFORCEMENT	TIE BARS 3/4", 32" LONG	TIE BARS 3/4", 24" LONG	SAW CUTS
			(FT)	(FT)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(EACH)	(EACH)
NB	DL	132.0	6	6	4.00				4.00	12.0		24
NB	DL	133.0	14	6		9.33			9.33	12.0		40
NB	DL	133.1	60	12				80.00	80.00	24.0	20.0	216
NB	DL	133.1	12	12			16.00		16.00	24.0		48
NB	DL	133.5	10	12		13.33			13.33	24.0		44
SB	DL	133.8	25	12				33.33	33.33	24.0	9.0	98
SB	DL	132.4	20	6		13.33			13.33	12.0		52
SB	DL	132.4	15	6		10.00			10.00	12.0		42
SB	DL	132.3	15	12			20.00		20.00	24.0		54
SB	DL	132.3	30	12				40.00	40.00	24.0	10.0	120
SB	PL	132.3	50	6				33.33	33.33	12.0	17.0	142
SB	PL	132.3	15	6		10.00			10.00	12.0		42
SB	DL	132.1	12	6		8.00			8.00	12.0		36
SB	DL	132.0	12	6		8.00			8.00	12.0		36
SB	DL	131.9	10	6		6.67			6.67	12.0		32
SB	DL	131.9	8	12		10.67			10.67	24.0		40
SB	DL	131.8	20	6		13.33			13.33	12.0		52
SB	DL	131.5	15	6		10.00			10.00	12.0		42
SB	DL	131.1	6	6	4.00				4.00	12.0		24
SB	PL	130.4	15	6		10.00			10.00	12.0		42
SB	PL	130.4	15	6		10.00			10.00	12.0		42
SB	DL	130.3	6	12		8.00			8.00	24.0		36
SB	DL	130.3	10	6		6.67			6.67	12.0		32
SB	DL	127.2	20	6		13.33			13.33	12.0		52
SB	DL	125.6	6	6	4.00				4.00	12.0		24
SB	DL	125.1	10	6		6.67			6.67	12.0		32
SB	DL	125.1	10	6		6.67			6.67	12.0		32
SB	DL	124.6	15	12			20.00		20.00	24.0		54
SB	DL	124.6	10	12		13.33			13.33	24.0		44
SB	DL	124.0	15	12			20.00		20.00	24.0		54
SB	PL	114.6	12	6		8.00			8.00	12.0		36
SB	DL	113.3	6	6	4.00				4.00	12.0		24
SB	DL	111.0	12	12			16.00		16.00	24.0		48
SB	DL	111.0	8	12		10.67			10.67	24.0		40
MEASURED TOTALS:					32.0	420.7	175.3	373.3	1001.3	1188.0	113.0	3574.0
30% CONTINGENCY:					9.6	126.2	52.6	112.0	300.4	356.4	33.9	1072.2
TOTAL:					42	547	228	485	1302	1701		4646

4646



1 REVISION 1-2-2024

USER NAME = Robert.Hughes	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 0.16666633' / in.	CHECKED -	REVISED -
PLOT DATE = 12/20/2023	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE: 1"=50'	SHEET 2	OF 4 SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	61-1,1-1,1-2,2,3,3-1,4,5,5-1,6)PP	MARION	10	6
CONTRACT NO. 76T25				
ILLINOIS FED. AID PROJECT				