



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 8, 2024

SUBJECT: Route FAU 8591/FAS792 & FAS 1793 (Green Street Road and Odin Road)
Section 20-00144-00-SP
Marion County
Contract No. 97820
Item 123
January 19, 2024 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Page 6 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

DETOUR SIGNING: This work shall consist of furnishing, erecting, maintaining, covering, uncovering, and removing the detour signing as shown in the plans for the temporary closure of CH 9 for the widening of SN 061-3221.

The materials used shall be in accordance with Section/Article 1090, 1091, 1006.29, and 1007.05 of the Standard Specifications.

The Contractor shall furnish and erect new detour signs at locations indicated in the plans and as directed by the Engineer. The signs shall be post mounted. Where it is possible, signs may be attached to existing posts or poles.

The signs are to be in place and uncovered prior to any road closure. When a detour is not in use, the detour signing shall be completely covered.

The signs and posts shall be removed when detours are no longer required. The Contractor shall return the area around the signs to its previous condition, at the Contractor's expense. This may include seeding.

This work will be measured for payment on a lump sum basis and shall include furnishing, erecting and maintaining detour route signs at locations indicated in the plans. This work will be paid for at the contract unit price per lump sum for DETOUR SIGNING.

STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS): This work shall consist of furnishing and erecting radial guardrail on 9' posts in accordance with Section 630 of the Standard Specifications, as well as Highway Standard 630001-12 the details in the plans, and as directed by the Engineer.

All radial guardrail shall have a radius of 15' to the rail face. Each piece of guardrail shall have a uniform arc length of 12.5'. The last piece of radial guardrail shall be terminated with a standard end section as shown in Highway Standard 630001-12.



This work will be measured for payment on a per FOOT basis and shall include all labor, materials, and equipment necessary to perform the work as described herein. This work shall be paid for at the Contract unit price per FOOT for STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS).