

| | | | | |
|-----------------------|--------------|----------|-----------------|-----------|
| F.A.R. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 348 | 0108.2.A-1-2 | COOK | 14 | 3 |
| FED. ROAD DIST. NO. 1 | | ILLINOIS | HIGHWAY PROJECT | |

MCHD CLAIM #713941

| SUMMARY OF QUANTITIES | | | CONSTRUCTION TYPE CODE | | | | | | SUMMARY OF QUANTITIES | | | CONSTRUCTION TYPE CODE | | | | | | |
|-----------------------|---|--------|------------------------|--------------------------|--|--|--|--|-----------------------|---|-------|------------------------|--------------------------|--|--|--|--|--|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | URBAN 100% STATE SFTY-2A | | | | | CODE NO | ITEM | UNIT | TOTAL QUANTITIES | URBAN 100% STATE SFTY-2A | | | | | |
| 50102400 | CONCRETE REMOVAL | CU YD | 34.1 | 34.1 | | | | | X0321781 | MECHANICAL SPLICE | EACH | 280 | 280 | | | | | |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 34.1 | 34.1 | | | | | X0322467 | TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE | SO FT | 48 | 48 | | | | | |
| 50300260 | BRIDGE DECK GROOVING | SO YD | 57 | 57 | | | | | X7011015 | TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS) | L SUM | 1 | 1 | | | | | |
| 50300300 | PROTECTIVE COAT | SO YD | 114 | 114 | | | | | Z0003600 | BEAM STRAIGHTENING | L SUM | 1 | 1 | | | | | |
| 50500405 | FURNISHING AND ERECTING STRUCTURAL STEEL | POUND | 20300 | 20300 | | | | | Z0030240 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2 | EACH | 1 | 1 | | | | | |
| 50500505 | STUD SHEAR CONNECTORS | EACH | 392 | 392 | | | | | Z0047300 | PROTECTIVE SHIELD | SO YD | 155 | 155 | | | | | |
| 50501110 | STRUCTURAL STEEL REMOVAL | POUND | 19640 | 19640 | | | | | Z0073300 | TEMPORARY SHORING AND CRIBBING | L SUM | 1 | 1 | | | | | |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 6740 | 6740 | | | | | | | | | | | | | | |
| 50900905 | REMOVING AND RE-ERECTING EXISTING RAILING | FOOT | 74 | 74 | | | | | | | | | | | | | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 1 | 1 | | | | | | | | | | | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | | | | | | | | | | | |
| 70102630 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701601 | L SUM | 1 | 1 | | | | | | | | | | | | | | |
| 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L SUM | 1 | 1 | | | | | | | | | | | | | | |
| 70300210 | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS | SO FT | 38 | 38 | | | | | | | | | | | | | | |
| 70300520 | PAVEMENT MARKING TAPE, TYPE III 4" | FOOT | 1500 | 1500 | | | | | | | | | | | | | | |
| 70300540 | PAVEMENT MARKING TAPE, TYPE III 6" | FOOT | 200 | 200 | | | | | | | | | | | | | | |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 110 | 110 | | | | | | | | | | | | | | |
| 78003110 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4" | FOOT | 850 | 850 | | | | | | | | | | | | | | |
| 78003150 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12" | FOOT | 120 | 120 | | | | | | | | | | | | | | |

© SFTY-3N

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 10/27/2005

10/27/2005 12:00:00 PM C:\PROJECTS\60A6Q\1027005\SFTY-3N.DWG