

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
368	2005-0761	COOK	12	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	URBAN 100% STATE SFTY-2A	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT							
44001000	BITUMINOUS CONCRETE SURFACE REMOVAL	SQ YD	10.9	10.9					
50102400	CONCRETE REMOVAL	CU YD	1.8	1.8					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	16.6	16.6					
50300300	PROTECTIVE COAT	SQ YD	66.3	66.3					
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	806	806					
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1130	1130					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2020	2020					
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	67.6	67.6					
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	272	272					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2					
67100100	MOBILIZATION	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	240	240					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	110	110					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	200	200					
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	806	806					
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48	48					
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	11.4	11.4					
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	7	7					
Δ 20030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1					
Δ 20030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	SFTY-2A	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT							

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

REV.

Δ SFTY-34  
\* SPECIALTY ITEMS