

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	*	COOK	631	6
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* (2425 & 2626) R-2		CONTRACT NO. 62111		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	1-80 **	RAILROAD, BURNHAM, 175TH ST., BERNICE **	BRIDGE ** 016-2791	BRIDGE ** 016-2792	RETAINING WALLS **	SURVEILLANCE **	LANSING ****	Y000 LANSING ****	SIDEWALK ***
				J000-2A 5591	I000-2A 1183	X271-2A	X281-2A	Y007	Y032-IF	I000-2A	3	SFTY-1B
M2080150	TRENCH BACKFILL	CU M	6777									
M2090410	SAND BACKFILL	CU M	1196	1196								
M2101000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ M	76043	76043								
M2113150	TOPSOIL FURNISH AND PLACE, 150MM	SQ M	3934		3934							
M2113300	TOPSOIL FURNISH AND PLACE, 300MM	SQ M	817		817							
M2114100	COMPOST FURNISH AND PLACE, 100MM	SQ M	817		817							
M2500210	SEEDING, CLASS 2A	HA	0.12	0.06	0.06							
M2500400	NITROGEN FERTILIZER NUTRIENT	KG	70		70							
M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	70		70							
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	70		70							
M2510115	MULCH, METHOD 2	HA	0.12		0.12							
M2510630	EROSION CONTROL BLANKET	SQ M	2552	1025	1527							
M2520110	SODDING, SALT TOLERANT	SQ M	3519		3519							
M2520200	SUPPLEMENTAL WATERING	UNIT	36		36							
M2800200	EARTH EXCAVATION FOR EROSION CONTROL	CU M	2071	2035	36							
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	47	14	33							
M2810105	STONE RIPRAP, CLASS A3	SQ M	15		15							
M2820100	FILTER FABRIC	SQ M	15		15							
M3111100	SUB-BASE GRANULAR MATERIAL, TYPE B 100MM	SQ M	3076	3076								
M3111300	SUB-BASE GRANULAR MATERIAL, TYPE B 300MM	SQ M	76043	76043								
M3120150	STABILIZED SUB-BASE 150MM	SQ M	77581	77581								
M3511150	AGGREGATE BASE COURSE, TYPE B 150MM	SQ M	11599	10490						1109		
M4060200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	32.2	6.9	25.3							
M4060895	CONSTRUCTING TEST STRIP	EACH	3	1	2							
M4202255	PORTLAND CEMENT CONCRETE PAVEMENT 250MM (JOINTED)	SQ M	2343	2343								
M4205050	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ M	1694			842	852					
M4205200	PROTECTIVE COAT	SQ M	1079		1079							
M4210360	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 360MM	SQ M	52576	52576								
M4214360	PAVEMENT REINFORCEMENT 360MM	SQ M	52576	52576								
M4217088	LUG SYSTEM COMPLETE 8.8 METER	EACH	1	1								
M4217108	LUG SYSTEM COMPLETE 10.8 METER	EACH	1	1								
M4217144	LUG SYSTEM COMPLETE 14.4 METER	EACH	5	5								
M4230150	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 150MM	SQ M	547		547							
M4240125	PORTLAND CEMENT CONCRETE SIDEWALK 125MM	SQ M	822		665							157
M4402000	PAVEMENT REMOVAL	SQ M	37587	29380	8207							
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	495		495							
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	1056		1056							
M4402050	SIDEWALK REMOVAL	SQ M	757		757							

*SPECIALTY ITEMS
 **90% FEDERAL
 10% STATE
 ***50% STATE
 50% VILLAGE OF LANSING
 ****100% VILLAGE OF LANSING
 *****100% CITY OF CHICAGO
 HEIGHTS
 **90% FEDERAL
 5% STATE
 5% VILLAGE OF LANSING

STANKIRJ
 9-14-2005, 13:48:33
 I:\2005\138833
 1:\DOCUMENT\193750\CIVIL\ADON\SORTQ02A.DGN
 3233 34 35 36 37 3839 40 41 4243 44 45 46 47 4849 50 51 52 53 54 55 56 57 5859 60 61 62 63
 \S0176102A.DGN, \V89900102A.DGN, \S0176102A.DGN

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. ROUTE 80/94 (KINGERY EXPRESSWAY)
 EB & WB INSIDE LANES (MAINLINE) CONSTRUCTION
 COOK COUNTY

**SUMMARY OF QUANTITIES
 II**

SCALE: NONE
 DATE: 9/13/05

DRAWN BY: SNM
 CHECKED BY: KC

TENG
 TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 CHICAGO, ILLINOIS

Rev.