

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-2	COOK/LAKE	1207	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62114		INDOT DES. NO. 0100987		

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	LIGHTING-	SURVEIL-	SIGNING	ROADWAY	LIGHTING	SURVEIL-	SIGNING	VILLAGE			
				ILLINOIS	ILLINOIS	LANCE ILLINOIS	ILLINOIS	INDIANA	INDIANA	LANCE INDIANA	INDIANA	OF LANSING			
				CONSTRUCTION TYPE CODE											
				J000-2A	Y030-1E	Y032-1F	Y002-1C	J000-2A	Y030-1E	Y032-1F	Y002-1C	Y060			
M4230200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 200MM	SQ M	1019	1019	0	0	0	0	0	0	0	0			
M4243000	PORTLAND CEMENT CONCRETE SIDEWALK, SPECIAL	SQ M	3.82	3.82	0	0	0	0	0	0	0	0			
M4401000	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ M	485	485	0	0	0	0	0	0	0	0			
M4402000	PAVEMENT REMOVAL	SQ M	83633	36900	0	0	0	46508	0	0	0	225			
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	37	37	0	0	0	0	0	0	0	0			
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	1036.7	9.5	0	0	0	967.2	0	0	0	60			
M4402050	SIDEWALK REMOVAL	SQ M	252	18	0	0	0	234	0	0	0	0			
M4402060	APPROACH SLAB REMOVAL	SQ M	2321	0	0	0	0	2321	0	0	0	0			
M4402280	CONCRETE BARRIER REMOVAL	METER	1405	733	0	0	0	672	0	0	0	0			
M4402530	PAVED SHOULDER REMOVAL	SQ M	19434	6412	0	0	0	13022	0	0	0	0			
M4402540	PAVEMENT BREAKING	SQ M	8416	8416	0	0	0	0	0	0	0	0			
M4428420	CLASS D PATCHES, TYPE IV, 200MM	SQ M	99	38	0	0	0	61	0	0	0	0			
M4428450	CLASS D PATCHES, TYPE IV, 350MM	SQ M	415	82	0	0	0	333	0	0	0	0			
M4830360	PORTLAND CEMENT CONCRETE SHOULDERS - 360MM	SQ M	15836	15836	0	0	0	0	0	0	0	0			
M5010240	CONCRETE REMOVAL	CU M	429.7	0	0	0	0	429.7	0	0	0	0			
M5020100	STRUCTURE EXCAVATION	CU M	536	536	0	0	0	0	0	0	0	0			
M542C212	REINFORCED CONCRETE PIPE TEE, 300MM PIPE WITH 300MM RISER	EACH	1	1	0	0	0	0	0	0	0	0			
M542C228	REINFORCED CONCRETE PIPE TEE, 600MM PIPE WITH 300MM RISER	EACH	1	1	0	0	0	0	0	0	0	0			
M542C236	REINFORCED CONCRETE PIPE TEE, 750MM PIPE WITH 300MM RISER	EACH	2	2	0	0	0	0	0	0	0	0			
M542C252	REINFORCED CONCRETE PIPE TEE, 1200MM PIPE WITH 300MM RISER	EACH	6	6	0	0	0	0	0	0	0	0			
M542C348	REINFORCED CONCRETE PIPE TEE, 1200MM PIPE WITH 375MM RISER	EACH	1	1	0	0	0	0	0	0	0	0			
M5502840	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 300MM	METER	554.8	487.2	0	0	0	67.6	0	0	0	0			
M5502850	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 375MM	METER	28.4	28.4	0	0	0	0	0	0	0	0			
M5502860	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 450MM	METER	199.1	199.1	0	0	0	0	0	0	0	0			
M5502880	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 600MM	METER	279.8	279.8	0	0	0	0	0	0	0	0			
M5502900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 750MM	METER	638.5	638.5	0	0	0	0	0	0	0	0			
M5502920	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 900MM	METER	149.4	149.4	0	0	0	0	0	0	0	0			
M5502990	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS I 1950MM	METER	88.2	88.2	0	0	0	0	0	0	0	0			
M5503050	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 300MM	METER	62.9	62.9	0	0	0	0	0	0	0	0			
M5503060	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 375MM	METER	77.4	77.4	0	0	0	0	0	0	0	0			
M5503111	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 750MM	METER	122.8	122.8	0	0	0	0	0	0	0	0			
M5503150	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 1200MM	METER	340	340	0	0	0	0	0	0	0	0			
M5503190	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS II, 1800MM	METER	117.2	117.2	0	0	0	0	0	0	0	0			

- SPECIALTY ITEMS
- • 100% STATE
- • • 100% INDIANA
- • • • 100% VILLAGE OF LANSING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41

SUMMARY OF QUANTITIES

SCALE _____ DATE 07/05

DRAWN BY ACE/CAD
CHECKED BY TAE

AMERICAN
CONSULTING ENGINEERS

Rev. 12-5-05