

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-2	COOK/LAKE	1207	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62114		INDOT DES. NO. 0100987		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE										
				RETAINING WALLS ILLINOIS	NOISE WALLS ILLINOIS	MINOR STRUCTURES ILLINOIS	RETAINING WALLS INDIANA	NOISE WALLS INDIANA	MINOR STRUCTURES INDIANA	BRIDGE OVER HOHMAN	BRIDGE OVER LITTLE CALUMET	BRIDGE OVER HARRISON	VILLAGE OF LANSING	
	<i>URBAN</i>			Y007	Y220	Y007	Y007	Y220	Y007	X281-2A	X071-2A	X271-2A		
50300440	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	63	0	0	0	0	0	0	0	63	0	0	
50300450	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	42	0	0	0	0	0	0	0	42	0	0	
50500305	ERECTING STRUCTURAL STEEL	L SUM	1	0	0	0	0	0	0	0	.79	.21	0	
60248000	JUNCTION CHAMBER, NO. 1	EACH	1	0	0	0	0	0	0	0	0	0	1	
60248100	JUNCTION CHAMBER, NO. 2	EACH	1	0	0	0	0	0	0	0	0	0	1	
60248200	JUNCTION CHAMBER, NO. 3	EACH	4	0	0	4	0	0	0	0	0	0	0	
60248300	JUNCTION CHAMBER, NO. 4	EACH	2	0	0	2	0	0	0	0	0	0	0	
60248400	JUNCTION CHAMBER, NO. 5	EACH	2	0	0	2	0	0	0	0	0	0	0	
M3111010	SUB-BASE GRANULAR MATERIAL, TYPE B	M TON	408.5	408.5	0	0	0	0	0	0	0	0	0	
M5020100	STRUCTURE EXCAVATION	CU M	535.1	535.1	0	0	0	0	0	0	0	0	0	
M5030350	CONCRETE STRUCTURES	CU M	279.48	269	0	10.48	0	0	0	0	0	0	0	
M5030380	RUSTICATION FINISH	SQ M	4598	148	0	0	4450	0	0	0	0	0	0	
M5030450	PROTECTIVE COAT	SQ M	92.7	92.7	0	0	0	0	0	0	0	0	0	
M5041219	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 1219MM	METER	1272	0	0	0	0	0	0	1272	0	0	0	
M5080105	REINFORCEMENT BARS	KG	490	0	0	490	0	0	0	0	0	0	0	
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	18390	18390	0	0	0	0	0	0	0	0	0	
M5910100	GEOCOMPOSITE WALL DRAIN	SQ M	4328	138	0	0	4190	0	0	0	0	0	0	
M6011105	PIPE UNDERDRAINS FOR STRUCTURES 150MM	METER	52.5	52.5	0	0	0	0	0	0	0	0	0	
MX030128	REMOVAL OF EXISTING NOISE ABATEMENT WALL	SQ M	8798	0	0	0	0	8798	0	0	0	0	0	
MX030257	ERECTING FLOATING BEARINGS, GUIDED EXPANSION 1250KN	EACH	21	0	0	0	0	0	0	0	21	0	0	
MX030355	NOISE ABATEMENT WALL, GROUND MOUNTED	SQ M	1213	0	1213	0	0	0	0	0	0	0	0	
MX030356	NOISE ABATEMENT WALL, STRUCTURE MOUNTED	SQ M	11169	0	11169	0	0	0	0	0	0	0	0	
MX030511	EXCAVATION FOUNDATION, UNCLASSIFIED (INDIANA)	CU M	21085	0	0	0	16071	0	0	1876	2671	467	0	
MX030512	EXCAVATION WET (INDIANA)	CU M	498	0	0	0	0	0	0	0	498	0	0	
MX030513	EXCAVATION DRY (INDIANA)	CU M	1362	0	0	0	0	0	0	0	1362	0	0	
MX030514	STRUCTURE BACKFILL (INDIANA)	CU M	22373.7	0	0	0	15321.5	0	5160.2	623	473	796	0	
MX030515	RIPRAP REVETMENT (INDIANA)	SQ M	4314	0	0	0	0	0	0	0	4314	0	0	
MX030516	TEST PILE, 356MM (INDIANA)	EACH	22	0	0	0	16	0	0	4	0	2	0	
MX030517	PILE, CONCRETE, STEEL SHELL ENCASED, 6.35MM, 356MM (INDIANA)	METER	3331.5	0	0	0	18973	0	0	3324	9483	1531.5	0	
MX030518	CONCRETE, A, SUBSTRUCTURE (INDIANA)	CU M	11141.8	0	0	0	7322.8	0	0	940	2761.1	117.9	0	
MX030519	CONCRETE, C, SUPERSRUCTURE (INDIANA)	CU M	3255.9	0	0	0	0	0	0	938.1	1716.2	601.6	0	
MX030520	REINFORCING BARS, EPOXY COATED (INDIANA)	KG	1,177,220	0	0	0	506,010	0	0	174,000	423,230	73,980	0	
MX030521	PIPE, UNDERDRAIN, PERFORATED, 1.63MM, 150MM (INDIANA)	METER	1248	0	0	0	1248	0	0	0	0	0	0	

- SPECIALTY ITEMS
- • 100% STATE
- • • 100% INDIANA
- • • • 100% VILLAGE OF LANSING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41
SUMMARY OF QUANTITIES

SCALE: DATE 07/05

DRAWN BY ACE/CAD
CHECKED BY TAE

AMERICAN
CONSULTING ENGINEERS

Rev.