

SCHEDULE OF QUANTITIES

ALL DIMENSIONS IN METERS EXCEPT PAVEMENT ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-2	COOK/LAKE	1207	29
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62114		INDOT DES. NO. 0100987		

PORTLAND CEMENT CONCRETE SHOULDERS - 360MM

STATION	WIDTH(m)	STATION	WIDTH(m)	SQ METER
ILLINOIS				
WESTBOUND OUTSIDE SHOULDER				
7+090.000	3.000	7+228.678	3.000	416.0
7+228.678	3.000	7+300.652	4.900	284.3
7+300.652	4.900	7+330.701	7.300	183.3
7+330.701	7.300	7+342.041	7.517	84.0
7+342.041	3.216	7+361.215	3.600	65.3
7+361.215	3.600	7+950.000	3.600	2,119.6
WESTBOUND EMERGENCY ACCESS				
7+342.041	3.800	7+361.242	3.800	73.0
7+361.242	3.800	7+379.000	4.155	70.6
EASTBOUND OUTSIDE SHOULDER				
6+814.721	3.600	7+400.281	3.600	2,108.0
7+400.281	8.080	7+499.547	3.600	579.7
7+499.547	3.600	7+950.000	3.600	1,621.6
EASTBOUND EMERGENCY ACCESS				
7+386.161	4.000	7+400.281	4.000	56.5
WESTBOUND INSIDE SHOULDER				
6+814.721	3.600	7+950.000	3.600	4,087.0
EASTBOUND INSIDE SHOULDER				
6+814.721	3.600	7+950.000	3.600	4,087.0
TOTAL =				15,836

CONCRETE REMOVAL

STATION	CUT/FILL(m ²)	STATION	CUT/FILL(m ²)	CU Meter
INDIANA				
REINFORCED SHOULDERS WITH CONCRETE BARRIER				
SHOULDER: 3.0 M WIDE X 0.30 M THICK				
CONCRETE BARRIER: 0.384 SQ M				
20+620.659	1.284	20+448.434	1.284	221.10
30+103.442	1.284	30+222.172	1.284	152.40
REINFORCED SHOULDERS WITH CONCRETE BARRIER				
SHOULDER: 1.7 M WIDE X 0.30 M THICK				
CONCRETE BARRIER: 0.384 SQ M				
30+297.546	0.894	30+329.127	0.894	28.20
SPECIAL BARRIER WALL				
CONCRETE BARRIER: 0.659 SQ M				
30+222.172	0.659	30+264.639	0.659	28.00
TOTAL =				429.7

STORM SEWER REMOVAL 200MM

STATION	OFFSET(m)	STATION	OFFSET(m)	METERS
ILLINOIS				
6+903.867	13.48 LT	6+908.870	13.48 LT	5.00
6+949.240	13.48 LT	6+954.247	13.48 LT	5.00
6+993.441	13.48 LT	6+998.227	13.48 LT	4.80
7+029.145	13.56 LT	7+034.063	13.56 LT	4.90
7+074.120	13.54 LT	7+078.677	13.54 LT	4.60
7+026.310	27.64 RT	7+041.820	21.01 RT	16.90
7+128.578	13.64 LT	7+132.943	13.64 LT	4.40
7+169.156	13.83 LT	7+173.317	13.83 LT	4.20
7+218.860	13.89 LT	7+222.770	13.89 LT	3.90
7+254.984	13.78 LT	7+265.186	13.78 LT	10.20
TOTAL =				63.9

STORM SEWER REMOVAL 300MM

STATION	OFFSET(m)	STATION	OFFSET(m)	METERS
ILLINOIS				
6+846.411	0.27 LT	6+890.349	0.95 RT	44.00
6+891.601	0.50 LT	6+905.230	14.88 LT	19.80
6+938.301	0.76 LT	6+950.440	14.88 LT	18.60
6+984.164	0.64 LT	6+994.560	14.88 LT	17.60
7+028.883	0.55 LT	7+029.170	14.88 LT	14.30
7+073.992	1.11 RT	7+074.190	14.88 LT	16.00
7+121.190	0.86 LT	7+129.350	14.88 LT	16.20
7+150.001	28.61 LT	7+150.000	18.00 LT	10.60
7+165.913	0.64 LT	7+173.970	14.88 LT	16.40
7+200.000	28.38 LT	7+250.000	29.24 LT	50.00
7+250.000	29.24 LT	7+300.000	30.57 LT	50.00
7+257.318	0.67 LT	7+267.767	17.77 LT	20.00
7+300.000	30.57 LT	7+303.897	17.69 LT	13.40
7+300.000	30.57 LT	7+350.000	32.98 LT	50.10
7+303.215	0.66 LT	7+314.008	17.67 LT	20.20
7+348.814	0.78 LT	7+361.516	17.58 LT	21.10
7+393.926	0.85 LT	7+406.428	17.67 LT	21.00
7+400.000	27.60 LT	7+450.000	26.60 LT	50.00
7+439.730	0.77 LT	7+450.433	18.69 LT	20.90
7+430.025	23.46 RT	7+470.749	1.60 RT	46.20
7+450.000	26.60 LT	7+464.481	26.18 LT	14.50
7+464.481	26.18 LT	7+464.393	19.23 LT	7.00
7+470.680	0.56 LT	7+482.632	20.09 LT	22.90
7+516.090	0.31 LT	7+528.387	23.04 LT	25.90
7+528.343	23.00 LT	7+536.500	30.50 LT	11.10
7+540.000	23.08 RT	7+557.136	21.40 RT	17.20
7+558.662	21.17 RT	7+561.890	1.40 RT	20.00
7+613.502	1.70 RT	7+623.284	1.78 RT	9.80
7+623.284	1.78 RT	7+635.000	1.83 RT	11.70
7+624.916	0.79 LT	7+632.466	21.17 LT	21.70
7+624.864	21.41 LT	7+625.000	25.70 LT	4.30
7+659.828	2.00 RT	7+669.844	2.00 RT	10.00
7+669.844	2.00 RT	7+679.861	2.00 RT	10.00
7+672.513	1.63 LT	7+682.961	20.41 LT	21.50
7+703.498	2.43 RT	7+713.521	2.61 RT	10.00
7+713.521	2.61 RT	7+723.542	2.74 RT	10.00
7+717.936	1.91 LT	7+733.210	21.40 LT	24.80
7+750.438	3.21 RT	7+760.463	3.46 RT	10.00
7+760.463	3.46 RT	7+770.488	3.70 RT	10.00
7+763.808	1.65 LT	7+775.780	24.01 RT	25.40
7+795.001	4.07 RT	7+806.052	4.22 RT	11.10
7+806.052	4.22 RT	7+816.083	4.35 RT	10.00
7+808.312	1.22 LT	7+815.369	21.73 LT	21.70
7+843.799	4.66 RT	7+854.120	4.58 RT	10.30
7+848.759	22.81 RT	7+861.559	21.33 LT	46.00
7+854.120	4.58 RT	7+863.871	4.56 RT	9.80
7+890.200	4.25 RT	7+899.400	4.08 RT	9.20
7+899.400	4.08 RT	7+909.476	3.83 RT	10.10
7+900.257	0.26 RT	7+952.831	0.74 LT	52.60
7+924.426	9.05 LT	7+939.791	25.19 LT	22.30
7+928.438	3.34 RT	7+938.505	3.15 RT	10.10
7+938.511	0.81 LT	7+939.542	25.53 LT	24.70
TEMPORARY DRAINAGE ***** 6.25				
TOTAL =				1,078.4

STORM SEWER REMOVAL 300MM

STATION	OFFSET(m)	STATION	OFFSET(m)	METERS
INDIANA				
7+966.037	53.04 LT	7+982.625	23.73 RT	78.50
7+981.809	7.62 LT	7+988.248	17.70 RT	26.10
8+023.561	3.77 RT	8+033.856	3.83 RT	10.30
8+110.000	3.79 RT	8+117.088	3.79 RT	7.10
8+117.088	3.79 RT	8+127.092	3.84 RT	10.00
8+253.953	21.68 LT	8+260.093	0.50 LT	22.10
8+260.000	0.50 LT	8+267.000	22.02 RT	23.60
8+259.152	3.74 LT	8+269.150	3.75 LT	10.00
8+326.215	3.64 LT	8+336.214	3.64 LT	10.00
8+336.214	3.64 LT	8+346.215	3.64 LT	10.00
8+400.873	3.76 LT	8+410.878	3.75 LT	10.00
8+404.458	22.83 LT	8+412.014	0.79 LT	23.30
8+412.330	0.50 RT	8+417.504	15.65 RT	16.00
8+661.182	1.00 RT	8+671.057	0.96 RT	9.90
8+671.057	0.96 RT	8+681.171	1.03 RT	10.10
8+728.790	20.64 LT	8+733.937	0.71 LT	20.60
8+733.937	0.71 LT	8+740.610	25.96 RT	27.50
8+828.585	3.04 RT	8+838.560	3.08 RT	10.00
8+838.560	3.08 RT	8+848.555	3.00 RT	10.00
8+838.473	15.21 LT	8+838.633	0.87 LT	14.30
8+838.523	0.85 RT	8+839.015	32.87 RT	32.00
8+912.301	18.71 LT	8+915.114	0.89 LT	18.00
8+915.135	0.83 RT	8+920.973	32.59 RT	32.30
8+915.333	2.94 RT	8+925.319	3.08 RT	10.00
8+965.725	1.44 LT	9+021.094	0.85 LT	55.40
8+976.360	29.69 LT	9+021.781	29.82 LT	45.40
9+010.789	2.93 RT	9+020.768	3.42 RT	10.00
9+020.768	3.42 RT	9+030.758	2.94 RT	10.00
9+021.021	0.83 RT	9+083.629	0.69 RT	62.60
9+021.781	29.82 LT	9+022.272	17.63 LT	12.20
9+073.262	2.85 RT	9+083.247	2.88 RT	10.00
9+083.247	2.88 RT	9+093.232	2.86 RT	10.00
9+081.581	17.34 RT	9+081.496	31.11 RT	13.80
9+083.540	0.65 RT	9+159.092	0.65 RT	75.60
9+140.082	34.15 RT	9+183.692	35.66 RT	43.60
9+146.182	22.33 LT	9+144.504	32.87 LT	10.70
9+148.923	2.78 RT	9+158.908	2.79 RT	10.00
9+158.908	2.79 RT	9+168.893	2.78 RT	10.00
9+158.982	1.11 LT	9+184.512	1.12 LT	25.50
9+158.982	1.11 LT	9+180.112	36.79 LT	41.50
9+180.776	21.06 RT	9+183.692	35.66 RT	14.90
9+183.692	35.66 RT	9+282.325	34.22 RT	98.60
9+191.842	22.27 LT	9+237.484	22.57 LT	45.60
9+231.549	40.94 LT	9+237.492	22.24 LT	19.60
9+237.492	22.24 LT	9+283.106	22.18 LT	45.60
9+252.125	42.12 LT	9+252.124	46.02 LT	3.90
9+282.325	34.22 RT	9+283.590	22.49 RT	11.80
9+283.590	22.49 RT	9+316.167	22.57 RT	32.60
9+319.307	22.24 LT	9+342.217	21.98 LT	22.90
9+333.572	31.50 RT	9+333.476	39.73 RT	8.20
9+356.568	22.92 RT	9+369.067	22.89 RT	12.50
TEMPORARY DRAINAGE ***** 67.60				
TOTAL =				1,281.8

STORM SEWER REMOVAL 375MM

STATION	OFFSET(m)	STATION	OFFSET(m)	METERS
ILLINOIS				
6+863.961	7.69 LT	6+863.878	14.71 LT	7.00
7+026.313	27.64 RT	7+030.858	15.62 RT	12.90
7+348.153	25.48 LT	7+354.550	17.59 LT	10.20
7+349.710	23.97 RT	7+361.342	17.58 LT	43.10
7+558.000	22.78 LT	7+561.865	0.66 LT	22.40
7+594.214	22.65 LT	7+597.823	1.01 LT	21.90
7+597.875	1.39 RT	7+601.916	19.95 RT	19.00
TOTAL =				136.5

STORM SEWER REMOVAL 375MM

STATION	OFFSET(m)	STATION	OFFSET(m)	METERS
INDIANA				
8+335.309	19.08 RT	8+336.120	0.88 RT	18.20