

| | | | | |
|-----------------------|-------------|----------|-----------------|-----------|
| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 1313 | 0606.1 BR-2 | COOK | 10 | 3 |
| FED. ROAD DIST. NO. 1 | | ILLINOIS | HIGHWAY PROJECT | |

MCHD CLAIM # 712697

| SUMMARY OF QUANTITIES | | | CONSTRUCTION TYPE CODE | | | | | |
|-----------------------|---|------------------|------------------------|-------------------|---------|--|--|--|
| CODE NO | ITEM | UNIT | MCHD TOTAL QUANTITIES | SFTY-2A | | | | |
| | | | | URBAN 016-0825 | SFTY-3N | | | |
| 50102400 | CONCRETE REMOVAL | CU YD | 3.1 | 3.1 | | | | |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 3.1 | 3.1 | | | | |
| 50500405 | FURNISHING AND ERECTING STRUCTURAL STEEL | POUND | 11290 | 11290 | | | | |
| 50501110 | STRUCTURAL STEEL REMOVAL | POUND | 11290 | 11290 | | | | |
| 50501130 | STRUCTURAL STEEL REPAIR | POUND | 2550 | 2550 | | | | |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 120 | 120 | | | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 2 | 2 | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | |
| 70102625 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701606 | L SUM | 1 | 1 | | | | |
| 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L SUM | 1 | 1 | | | | |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 160 | 160 | | | | |
| X0322467 | TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE | SQ FT | 48 | 48 | | | | |
| X7011015 | TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS) | L SUM | 1 | 1 | | | | |
| Z0003600 | BEAM STRAIGHTENING | L SUM | 1 | 1 | | | | |
| Z0030240 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2 | EACH | 2 | | 2 | | | |
| Z0073300 | TEMPORARY SHORING AND CRIBBING | L SUM | 1 | 1 | | | | |
| Z0073351 | TEMPORARY SLAB SUPPORT SYSTEM | L SUM | 1 | 1 | | | | |
| 70102622 | TRAFFIC CONTROL AND PROTECTION STANDARD 701502 | L SUM | 1 | 1 | | | | |

① SFTY-3N

△ Rev. 1-3-06

Rev.

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES