

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1313	0606.1 BR-2	COOK	10	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

MCHD CLAIM # 712697

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	MCHD TOTAL QUANTITIES	SFTY-2A				
				URBAN				
				016-0825	SFTY-3N			
50102400	CONCRETE REMOVAL	CU YD	3.1	3.1				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3.1	3.1				
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	11290	11290				
50501110	STRUCTURAL STEEL REMOVAL	POUND	11290	11290				
50501130	STRUCTURAL STEEL REPAIR	POUND	2550	2550				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	120	120				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	160	160				
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48	48				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
Z0003600	BEAM STRAIGHTENING	L SUM	1	1				
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2		2			
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1	1				
Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	L SUM	1	1				
70102622	TRAFFIC CONTROL AND PROTECTION STANDARD 701502	L SUM	1	1				

① SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

REV.

10/27/2005 10:00:00 AM C:\Users\jg\Documents\100566.mxd