

SCHEDULE OF QUANTITIES

Z0030150 IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3

STATION	WIDTH(FT)	-	STATION	WIDTH(FT)	EACH
US ROUTE 20 (HDR SECTION)					
1726+15					1
1726+75					1
1886+00					1
1886+60					1
=====					TOTAL = 4

Z0030250 IMPACT ATTENUATORS (TEMPORARY) NON REDIRECTIVE, TEST LEVEL 3

STATION	WIDTH(FT)	-	STATION	WIDTH(FT)	EACH
US ROUTE 20 (HDR SECTION)					
EB	STAGE I CROSSOVER - STANDARD		701402		1
WB	STAGE I CROSSOVER - STANDARD		701403		1
=====					TOTAL = 2

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

STATION	WIDTH(FT)	-	STATION	WIDTH(FT)	EACH
US ROUTE 20 (HDR SECTION)					
1704+50	EB		STAGE II		1
1779+50	MEDIAN		PERMANENT ATTENUATOR		1
1853+58	EB		STAGE II		1
1846+23	EB	RT	STAGE III		1
1846+23	EB	LT	STAGE IV		1
=====					TOTAL = 5

64200105 SHOULDER RUMBLE STRIP

STATION	WIDTH(FT)	-	STATION	WIDTH(FT)	FOOT
US ROUTE 20 (V3 SECTION)					
1914+41.0	WB x 2		1982+00.0		13,518.0
1964+60.0	EB		1977+05.0		1,245.0
=====					SUB-TOTAL = 14,763.0

US ROUTE 20 (HDR SECTION)

STATION	WIDTH(FT)	-	STATION	WIDTH(FT)	EACH	
1697+00			1829+15	LT.	OUTSIDE	13215
1702+15			1842+10	LT.	INSIDE	13995
1702+50			1710+00	RT.	INSIDE	750
1796+50			1812+75	RT.	INSIDE	1625
1796+50			1812+75	RT.	OUTSIDE	1625
1832+33			1842+10	LT.	OUTSIDE	977
1844+49			1855+34	LT.	OUTSIDE	1085
1844+49			1904+41	LT.	INSIDE	5992
1848+15			1865+77	RT.	INSIDE	1762
1848+15			1855+07	RT.	OUTSIDE	692
1861+84			1904+41	LT.	OUTSIDE	4257
1858+54			1883+62	RT.	OUTSIDE	2508
=====					SUB-TOTAL = 48,483.0	
=====					TOTAL = 63,246.0	

Z0065745 SLOTTED DRAIN 12" WITH 2 1/2" SLOT

STATION	WIDTH(FT)	-	STATION	WIDTH(FT)	U.S.F.L.	D.S.F.L.	FOOT
RAMP CA (HDR SECTION)							
411+90.00			TO 412+95.45	LT	821.33	820.48	104
412+95.45			TO 414+91.00	LT	820.38	818.65	194
TOTAL RAMP CA							298

RAMP AD

304+00.00			TO 306+58.50	LT	822.04	820.17	257
TOTAL RAMP AD							257

RAMP BC

104+00.00			TO 106+47.00	LT	826.82	823.81	245
TOTAL RAMP BC							245

RAMP DB

213+05.00			TO 214+43.12	LT	826.03	823.43	136
214+43.12			TO 216+40.00	LT	823.33	819.25	196
TOTAL RAMP DB							332
=====					TOTAL =	1132	

Z0065752 SLOTTED DRAIN 12" WITH 6" SLOT

STATION	WIDTH(FT)	-	STATION	WIDTH(FT)	FOOT
US ROUTE 20 (V3 SECTION)					
CROSS OVER, SEE MEDIAN CROSS OVER SHEET FOR DETAILS					
=====					126.0
SUB-TOTAL =					126.0

US ROUTE 20 (HDR SECTION)

MEDIAN CROSS-OVER					126
=====					SUB-TOTAL = 126
=====					TOTAL = 252

Z0074100 TERMINATION OF DEADEND ROADS

STATION	WIDTH(FT)	-	STATION	WIDTH(FT)	EACH
SMOKEY HOLLOW CUL-DE-SAC (V3 SECTION)					
=====					1
=====					TOTAL = 1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

US ROUTE 20

SCALE: VERT. HORIZ.
DATE: 10/28/05

DRAWN BY: DTE
CHECKED BY: JAM