

CONTRACT 64577				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	*	STEPHENSON	290	41A
STA.		TO STA.		
FED. ROAD DIST. NO. 2		ILLINOIS	FED. AID PROJECT	
* 177-13,4,4-1-1				

LOCATION	ESTBOUND OR EASTBOUND	MEDIAN OR OUTSIDE	60107600 PIPE UNDERDRAINS 4" FOOT	60108100 PFE UNDERDRAINS 4" (SPECIAL) FOOT	60100060 CONC. HDWL. FOR PIPE DRAINS EACH	REMARKS
BEGIN STA.	END STA.					
232+00.00	237+00.00	OUT	500	34	1	
237+00.00	241+05.00	OUT	405	34	1	
TOTAL RAMP DB			3933	340	10	
TOTALS			45822	3648	116	

US ROUTE 20	WESTBOUND OR EASTBOUND	MEDIAN OR OUTSIDE	60107600 PIPE UNDERDRAINS 4" FOOT	60108100 PIPE UNDERDRAINS 4" (SPECIAL) FOOT	60100060 CONC. HDWL. FOR PIPE DRAINS EACH
1914+50.00 - 1942+50.00	WB	OUT	2800	164.5	7
1914+50.00 - 1942+50.00	WB	MEDIAN	2800	136.5	7
1942+50.00 - 1969+41.00	WB	OUT	2691	141	6
1969+41.00 - 1982+00.00	WB	OUT	1259	70.5	3
1969+41.00 - 1982+00.00	WB	MEDIAN	1259	58.5	3
1964+60.00 - 1969+50.00	EB	OUT	490	23.5	1
TOTAL US ROUTE 20			11299	595	27
V3 SUB-TOTALS			11299	595	27
TOTAL			57121	4243	143

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		PIPE UNDERDRAIN SCHEDULE US ROUTE 20

SCALE: VERT. N/A
HORIZ. N/A
DATE 10/28/05

DRAWN BY DTE
CHECKED BY JAM