

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	6M & TS	HENRY	257	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES URBAN

CODE NO.	ITEM	UNIT	TOTAL	80% FED	100%	80% FED	80% FED	50% STATE
			QUANTITY	20% STATE	CITY	15% STATE	20% STATE	50% CITY
				J000-2A	Y060	Y031-1F	Y079	SFTY-1B
X0323230	ISLAND SPECIAL	SQ YD	39	39				
X0323455	ADJUST MONITORING WELLS	EACH	2	2				
X0324886	CONDUIT INSTALLED, 1 1/4", NON-METALLIC	FOOT	7			7		
X0324887	CONDUIT INSTALLED, 2 1/2", NON-METALLIC	FOOT	123			123		
X0324888	CONDUIT INSTALLED, 4", NON-METALLIC	FOOT	254			254		
X0469600	CONNECTION TO EXISTING WATER MAIN	EACH	12	8	4			
X0712400	TEMPORARY PAVEMENT	SQ YD	375	375				
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	139	139				
X4066546	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N70	TON	567	567				
X4066740	LEVELING BINDER (HAND METHOD), SUPERPAVE N70	TON	15	15				
X4066910	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	485	485				
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1	1				
X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1			1		
X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	8			8		
X8801395	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5 SECTION, BRACKET MOUNT	EACH	2			2		
X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2			2		
XX022086	6" DIAMETER PIPE BOLLARD, CONCRETE FILLED	EACH	2			2		
XX022909	CLASS SI CONCRETE	CU YD	11.4	11.4				
XX030000	CLASS SI CONCRETE STEPS	CU YD	0.9	0.9				
XX03663	PEDESTRAIN SIGNAL HEAD, 1 FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8			8		
XX03823	BITUMINOUS SURFACE REMOVAL 2 3/4"	SQ YD	5222	5222				
XX04921	PEDESTRIAN PUSH-BUTTON SPECIAL	EACH	8			8		
XX04949	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE	TON	564	564				
XX05281	STEEL CASING PIPE 16" (BORED AND JACKED)	FOOT	241	180	61			
XX05742	DETECTABLE WARNING TILES	SQ FT	1118	1118				
XX146400	STORM SEWER REMOVAL	FOOT	2603	2603				
Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1				
Z0007602	BUILDING REMOVAL NO. 2	L SUM	1	1				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
Z0017100	DOWEL BARS	EACH	704	576	128			
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	1313	1313				
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
Z0049800	RELOCATE EXISTING SURVEY MARKERS	EACH	49	49				
Z0050900	REMOVE CONCRETE FOUNDATION	EACH	9	9				

* SPECIALTY ITEM

PLOT DATE = Thu Dec 27 11:46:24 2005
 PLOT SCALE = 50.0000 / IN.
 USER NAME = meg111