

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	6M & TS	HENRY	257	22
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES

60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID		
	LOCATION	EACH	
	DETOUR ROUTE-STAGE 1A (TEMPORARY)		
	IL 81 & LEXINGTON AVE. (NW QUAD)	1	
	TOTAL	1	

60266500	VALVE VAULTS TO BE REMOVED		
	LOCATION	EACH	
	IL 81 Sta. 1356+85 Lt & Rt	2	
	TOTAL	2	

60500040	REMOVING MANHOLES		
	LOCATION	EACH	
	IL 81		
	Sta. 1346+57.8Lt	1	
	Sta. 1347+70.7Rt	1	
	Sta. 1348+11.7Rt	1	
	Sta. 1348+29.1Rt	1	
	Sta. 1355+10.3Rt	1	
	Sta. 1356+81.2Lt (City Cost)	1	
	Sta. 1357+31.8Rt	1	
	Sta. 1357+36Lt	1	
	Sta. 1360+76.5Lt	1	
	IL 78		
	Sta. 366+09.4Lt	1	
	Sta. 367+03.3Rt	1	
	Sta. 369+55.9Rt	1	
	Sta. 371+73.5Rt	1	
	Sta. 374+01Lt	1	
	Sta. 374+09.8Lt	1	
	Sta. 374+94.4Rt	1	
	Sta. 377+47.4Lt	1	
	6th Street		
	Sta. 11+441Lt	1	
	TOTAL	18	

60500060	REMOVING INLETS		
	LOCATION	EACH	
	IL 81		
	Sta. 1347+69.8Lt	1	
	Sta. 1348+08Rt	1	
	Sta. 1348+08.9Lt	1	
	Sta. 1348+28.9Rt	1	
	Sta. 1348+31Lt	1	
	Sta. 1354+39.5Lt	1	
	Sta. 1354+47.5Rt	1	
	Sta. 1356+77.7Rt	1	
	Sta. 1356+78.7Lt	1	
	Sta. 1356+90.8Rt	1	
	Sta. 1357+21.7Rt	1	
	Sta. 1357+32.3Lt	1	
	Sta. 1360+76.1Lt	1	
	Sta. 1360+78.9Rt	1	
	Sta. 1360+95.9Rt	1	
	IL 78		
	Sta. 367+40.8Lt	1	
	Sta. 367+42.3Rt	1	
	Sta. 367+90.2Rt	1	
	Sta. 367+93.5Lt	1	
	Sta. 368+31.8Rt	1	
	Sta. 371+32.8Rt	1	
	Sta. 374+79.5Lt	1	
	Sta. 374+85.3Rt	1	
	Sta. 377+47.9Rt	1	
	TOTAL	24	

60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24		
	LOCATION	FOOT	
	IL 81 (W 6th St.) Lt Side		
	1345+50 to 1346+70Lt	120	
	1346+70Lt to 11+02 PARK ENTRANCE	78.8	
	11+02Rt to 1347+48.1Lt	108.6	
	1347+48.1Lt to 100+43.1Lt on LEXINGTON AVE	43.9	
	100+43.1 to 101+13.1 on LEXINGTON AVE	70.1	
	101+13Rt to 100+43.1Rt on LEXINGTON AVE	70.1	
	100+43.1 to 1348+35.4Lt on IL 81 (NE Return)	44.6	
	1348+35.4 to 1350+81.8Lt	246.3	
	1350+81.8 to 200+42.8Lt on MADISON AVE (NW Return)	44.2	
	200+43.2Rt to 1351+67.8Lt on IL 81 (NE Return)	44.6	
	1351+67.8 to 1354+25.3Lt	257.5	
	1354+25.3 to 300+43Lt on CHESTNUT ST (NW Return)	44.1	
	300+43 to 301+55Lt on CHESTNUT ST	112	
	301+55Rt to 300+43 on CHESTNUT ST	112	
	300+43Rt to 1355+11.3Lt on IL 81 (NE Return)	44	
	1355+11.3 to 1356+63.4Lt	152.1	
	1356+63.4 to 700+42.8Lt on TREMONT ST (NW Return)	43.8	
	700+42.8 to 700+93Lt on TREMONT ST	50.2	
	700+93Rt to 700+44.8 on TREMONT ST	48.2	
	700+44.8Rt to 1357+50.3Lt on IL 81 (NE Return)	45.1	
	1357+50.3 to 1359+46.3	196.3	
	1359+46.3Lt to 372+87.4Lt on IL 78 (NW Return)	183.7	
	IL 81 (W 6th St.) Rt Side		
	1345+50 to 1347+47.1Rt	197.1	
	1347+47.1 to 99+56.5Lt on LEXINGTON AVE (SW Return)	44.5	
	99+56.5 to 98+35Lt on LEXINGTON AVE	121.5	
	98+35Rt to 99+57.5Rt on LEXINGTON AVE	122.5	
	99+57.5 to 1348+34Rt on IL 81 (SE Return)	43.6	
	1348+34 to 1354+42Rt	608	
	1354+42 to 599+57Lt on CHESTNUT ST (SW Return)	44.1	
	599+57 to 599+13.4Lt on CHESTNUT ST	43.6	
	599+13.4Rt to 599+57Rt on CHESTNUT ST	43.6	
	599+57 to 1355+29Rt on IL 81 (SE Return)	44.1	
	1355+29 to 1356+62.3Rt	133.3	
	1356+62.3 to 699+56.8Lt on TREMONT ST (SW Return)	44.3	
	699+56.8 to 698+67Lt on TREMONT ST	89.8	
	698+67Rt to 699+56.7Rt on TREMONT ST	88.8	
	699+56.7 to 1357+50Rt on IL 81 (SE Return)	44.6	
	1357+50 to 1360+26Rt	276	
	1360+26Rt to 371+07.5Lt on IL 78 (SW Return)	74.2	
	IL 78 (N Main St.) Lt Side		
	365+35.4 to 366+70Lt	197.7	
	366+70 to 899+23.3Rt on 5th St (SW Return)	107.3	
	899+23.3 to 898+40Rt on 5th St	58.3	
	898+40Lt to 899+40.5Lt on 5th St	75.5	
	899+40.5 to 368+23.9Lt on IL 78 (SE Return)	59.2	
	368+23.9 to 370+06.7Lt	182.8	
	370+06.7 to 371+07.5Lt on IL 81 (SW Return)	101.4	
	Omission across IL 81		
	1359+35.3Lt to 373+3.7Lt on Red Apple Parking Lot	227	
	373+71.3Lt to 374+00.3Lt on Red Apple Parking Lot	50	
	372+87.4Lt to 375+52.4Lt	294.4	
	375+52.4 to 377+90Lt	240.6	
	IL 78 (N Main St.) Rt Side		
	365+35.4 to 371+06.1Rt	599.7	
	371+06.1 to 10+63.7Rt on 6th St (SE Return)	67.7	
	10+63.7 to 13+63Rt on 6th St	298.9	
	13+63 to 13+9Rt (SW Return Burr St)	32.7	
	13+74.5Lt to 13+46.9 (NW Return Burr St)	31.9	
	13+46.9 to 10+57.5Lt on 6th St	291.3	
	10+57.5Lt to 372+28Rt on IL 78 (NE Return)	58.1	
	372+28 to 376+87.3Rt	459.7	
	376+87.3 to 20+65.5Rt on 7th St (SE Return)	62.1	
	20+65.5Lt to 377+75.1Rt on IL 78 (NE Return)	51.3	
	377+75.1 to 377+80Rt	4.9	
	DETOUR ROUTE		
	Lexington Ave & 5th St		
	on 5th St to LEXINGTON AVE (NE Return)	128	
	TOTAL	7904.3	

66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED		
	LOCATION	FOOT	
	IL 81 Sta. 1348+23.5 to 1350+96.8	320	
	TOTAL	320	

66411900	TEMPORARY FENCE		
	LOCATION	FOOT	
	IL 78 Sta. 1348+24.5 to 1350+95.3	270.8	
	TOTAL	270.8	

66700305	PERMANENT SURVEY MARKERS, TYPE II		
	LOCATION	EACH	
	NW Quad, Lexington Ave & IL 81	1	
	NW Quad, IL 81 & IL 78	1	
	Along IL 78, determine in the field	1	
	TOTAL	3	

70300520	PAVEMENT MARKING TAPE TYPE III, 4'		
	LOCATION	FEET	
	Detour Rte. Stage I		
	Lexington (double yellow)	230	
	Lexington (double yellow)	200	
	Lexington (double yellow)	180	
	5th Street (skip slash)	277	
	5th Street (double yellow)	240	
	5th Street (double yellow)	90	
	Stage 3A		
	IL 81/6th Street		
	(white) Sta. 1343+90-1345+10	120	
	(white) Sta. 1345+10-1345+50	40	
	(white) Sta. 1345+50-1347+00	150	
	(white) Sta. 1343+90-1345+50	160	
	(white) Sta. 1345+50-1348+35	285	
	(white) Sta. 1348+35-1349+85	150	
	(white) Sta. 1347+00-1348+35	135	
	(white) Sta. 1348+35-1349+85	150	
	Stage 3		
	IL 81/6th street		
	(white) Sta. 1343+90-1345+90	200	
	(white) Sta. 1345+90-1348+35	245	
	(white) Sta. 1348+35-1349+90	155	
	TOTAL	3007.0	

70300570	PAVEMENT MARKING TAPE TYPE III, 24'		
	LOCATION	FEET	
	Detour Rte. Stage I (Stop Bars)		
	Lexington Ave. Sta. 99+55	12.5	
	Sta. 96+50	12.5	
	5th Street	16	
	Sta. 886+40	10.5	
	Sta. 367+46	9	
	Sta. 367+38		
	Stage 3A		
	IL 81/6th street		
	Sta. 1343+90	12	
	Sta. 1343+95	13	
	TOTAL	85.5	

PLOT DATE = Wed Oct 26 14:35:47 2005
 FILE NAME = c:\pno\pno\p216800\p216800.vp
 PLOT SCALE = 5000000 / 1 IN.
 USER NAME = mgajluj