

SUMMARY OF QUANTITIES

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
599	ROCK ISLAND	90	6
EXISTING CONDITIONS:			
* 42M-T-2R, 19BR-2M 42M-T-1			
CONTRACT 64641			

← 80% FED. — 20% STATE →

CODE NUMBER	ITEM	UNITS	TOTAL	I000-2A	X028-2A SN 081-1009	Y060 VILLAGE OF ANDALUSIA 100% Village	SN 081-1008 X028-2A 80 % FED 20 % STATE	SN 081-0076 SFTY-2A 80 % FED 20 % STATE
* 70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	535	225			310	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	14,025	13,408			617	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	48	44			4	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	16				16	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4				4	
78300500	PAINT PAVEMENT MARKING REMOVAL	SQ FT	120				120	
X0301335	WATER MAIN REMOVAL 8"	FOOT	367			367		
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	327					327
X0320887	POLYMER CONCRETE	CU FT	3.4				3.4	
X0322752	WORK ZONE PAVEMENT MARKING REMOVAL	FOOT	249	249				
X0323076	SILICONE JOINT SEALER, 1 3/4"	FOOT	47				47	
X0323330	PRECAST CONCRETE SUBSTRUCTURE	L SUM	1		0.5		0.5	
X0323557	BRIDGE JOINT SYSTEM EXPANSION 1"	FOOT	36				36	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	272		272			
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	123	103			20	
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	276	276				
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL- 19.0, N50	TON	259	259				
X4066735	LEVELING BINDER (HAND METHOD), SUPERPAVE N50	TON	3	3				
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	19	19				
X4073121	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 12"	SQ YD	2,399	2,399				
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	262				262	
X6063401	COMBINATION CONCRETE CURB AND GUTTER, TYPE M- 4.12	FOOT	667	667				
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1	1				
* XX003345	WATER MAIN ENCASEMENT	FOOT	20			20		
XX003516	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) - 8"	EACH	2			2		
XX004949	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE	TON	213	213				
XX004970	TEMPORARY PAVEMENT SUPERPAVE	SQ YD	1,318	1,318				
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	3,250	3,250				
* Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	2				2	
Z0002600	BAR SPLICERS	EACH	83		26			57
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.67			0.33	
+ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6	4			2	
+ Z0017300	DOWEL REPAIR	EACH	26	2			2	26
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LOAD 3	EACH	4					
Z0003700	BEARING PAD ADJUSTMENT	EACH	26					26
X0325133	THREE-SIDED PRECAST CONCRETE STRUCTURE, 32' X 6' -6"	FOOT	85		85			
Z0032700	KEYWAY REPAIR	FOOT	654					654

* SPECIALTY ITEM
+ SFTY-3N ITEM

09/09/2009
DATE TIME
JOB SHEET
REF.