

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
517	L-M-3	BOONE	68	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NUMBER	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE HS			
				80% FED 20% STATE I000-1A	90% FED 10% STATE J000-1A	90% FED 5% STATE 2.5% CITY 2.5% TWP Y031-1F	50% STATE 50% CITY SFTY 1-B
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	866			866	
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1156			1156	
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1564			1564	
* 87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	3908			3908	
* 87601200	PEDESTRIAN PUSH-BUTTON POST, GALVANIZED STEEL, TYPE II	EACH	1			1	
* 87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT.	EACH	1			1	
* 87702980	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 50 FT.	EACH	1			1	
* 87702990	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 54 FT.	EACH	2			2	
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3			3	
* 87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5			3.5	
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	58			58	
* 88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	10			10	
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	12			12	
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1960			1960	
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	6			6	
* B2002716	TREE, MALUS ADIRONDACK (ADIRONDACK CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	1	1			
X0301893	REMOVE AND REINSTALL CONCRETE HEADWALL FOR PIPE DRAIN	EACH	2		2		
X0322939	RELOCATE EXISTING FLARED END SECTION	EACH	2		2		
* X0324885	CONDUIT INSTALLED 1", NON-METALLIC	FOOT	1485			1485	
* X0324887	CONDUIT INSTALLED 2 1/2", NON-METALLIC	FOOT	105			105	
* X0324888	CONDUIT INSTALLED 4", NON-METALLIC	FOOT	363			363	
X3550410	BITUMINOUS BASE COURSE SUPERPAVE 7 1/2"	SQ YD	685	685			
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	268		268		
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	217	217			
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	145	145			
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1	1			
* X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6			6	
* X8801395	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4			4	
* X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4			4	
* X8810395	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	6			6	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1		
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	4057	866	3191		

* DESIGNATES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

SUMMARY OF QUANTITIES

PLOT DATE * Mon Dec 05 13:40:01 2005
FILE NAME * C:\p05\proj\64895\64895.dgn
USER NAME * cshen@ibv

① REVISED PER ADDENDUM 01/04/06

① REVISIONS 11-03-05 ② REVISIONS 11-21-05