

| F.A. RTE.           | SECTION | COUNTY                    | TOTAL SHEETS | SHEET NO. |
|---------------------|---------|---------------------------|--------------|-----------|
| 517                 | L-M-3   | BOONE                     | 68           | 3         |
| STA.                |         | TO STA.                   |              |           |
| FED. ROAD DIST. NO. |         | ILLINOIS FED. AID PROJECT |              |           |

| CODE NUMBER | PAY ITEM   | UNIT  | URBAN TOTAL QUANTITY | CONSTRUCTION TYPE CODE       |                              |  |                                |
|-------------|--|-------|----------------------|------------------------------|------------------------------|--|--------------------------------|
|             |  |       |                      | 80% FED 20% STATE<br>I000-1A | 90% FED 10% STATE<br>J000-1A | 90% FED 5% STATE 2.5% CITY 2.5% TWP<br>Y031-1F | 50% STATE 50% CITY<br>SFTY 1-B |
| 20100210    | TREE REMOVAL (OVER 15 UNITS DIAMETER)                                      | UNIT  | 20                   | 20                           |                              |  |                                |
| 20200100    | EARTH EXCAVATION   | CU YD | 2172                 |                              | 2172                         |  |                                |
| 20800150    | TRENCH BACKFILL  | CU YD | 38                   | 38                           |                              |  |                                |
| 25000910    | SEEDING, CLASS 1 (MODIFIED)  | ACRE  | 0.2                  | 0.2                          |                              |  |                                |
| 25001830    | SEEDING, CLASS 6 (MODIFIED)  | ACRE  | 1.0                  | 1.0                          |                              |  |                                |
| 25100120    | MULCH, METHOD 2  | TON   | 2.4                  | 2.4                          |                              |  |                                |
| 28000250    | TEMPORARY EROSION CONTROL SEEDING  | POUND | 120                  | 120                          |                              |  |                                |
| * 28000300  | TEMPORARY DITCH CHECKS   | EACH  | 6                    | 6                            |                              |  |                                |
| 28000500    | INLET AND PIPE PROTECTION  | EACH  | 5                    | 5                            |                              |  |                                |
| 31100910    | SUB-BASE GRANULAR MATERIAL, TYPE A 12"                                     | SQ YD | 2894                 |                              | 2894                         |  |                                |
| 35101100    | AGGREGATE BASE COURSE, TYPE A 12"  | SQ YD | 740                  | 740                          |                              |  |                                |
| 35102000    | AGGREGATE BASE COURSE TYPE B 8"  | SQ YD | 163                  | 163                          |                              |  |                                |
| 40600200    | BITUMINOUS MATERIALS (PRIME COAT)  | TON   | 1.5                  | 1.5                          |                              |  |                                |
| 40600300    | AGGREGATE (PRIME COAT)   | TON   | 5                    | 5                            |                              |  |                                |
| 40600980    | BITUMINOUS SURFACE REMOVAL - BUTT JOINT                                    | SQ YD | 566                  | 566                          |                              |  |                                |
| 42000501    | PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)                            | SQ YD | 2681                 |                              | 2681                         |  |                                |
| 42300300    | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH                         | SQ YD | 163                  | 163                          |                              |  |                                |
| 42400200    | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH                                   | SQ FT | 3003                 |                              |                              |  | 3003                           |
| 42400800    | DETECTABLE WARNINGS  | SQ FT | 296                  | 24                           | 272                          |  |                                |
| 44000100    | PAVEMENT REMOVAL   | SQ YD | 102                  | 102                          |                              |  |                                |
| 44000500    | COMBINATION CURB AND GUTTER REMOVAL  | FOOT  | 348                  | 348                          |                              |  |                                |
| 44001430    | BITUMINOUS SHOULDER REMOVAL  | SQ YD | 1055                 |                              | 1055                         |  |                                |
| 44003100    | MEDIAN REMOVAL   | SQ FT | 552                  |                              | 552                          |  |                                |
| 44201765    | CLASS D PATCHES, TYPE II, 10 INCH  | SQ YD | 23                   | 23                           |                              |  |                                |
| 48202400    | BITUMINOUS SHOULDERS SUPERPAVE 6"  | SQ YD | 2376                 |                              | 2376                         |  |                                |
| 50105220    | PIPE CULVERT REMOVAL   | FOOT  | 107                  | 107                          |                              |  |                                |
| 542A0229    | PIPE CULVERTS, CLASS A, TYPE 1 24"   | FOOT  | 13                   |                              | 13                           |  |                                |
| 542A8203    | PIPE CULVERTS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 18"                   | FOOT  | 64                   | 64                           |                              |  |                                |
| 542D5470    | PIPE CULVERTS, CLASS D, TYPE 1, EQUIVALENT ROUND-SIZE 15"                  | FOOT  | 50                   | 50                           |                              |  |                                |
| 54213657    | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"                        | EACH  | 1                    | 1                            |                              |  |                                |
| 54214290    | END SECTIONS, EQUIVALENT ROUND-SIZE 15"                                    | EACH  | 2                    | 2                            |                              |  |                                |
| 54214503    | PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 18" | EACH  | 2                    | 2                            |                              |  |                                |

\* DESIGNATES SPECIALTY ITEM

| REVISIONS |      |
|-----------|------|
| NAME      | DATE |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. DATE:      HORIZ. DATE:      DRAWN BY:      CHECKED BY:

PLOT DATE \* Mon Dec 05 13:46:43 2005  
 PLOT SCALE \* 1:2000 \* / IN.  
 USER NAME \* rshimberb

**SUMMARY OF QUANTITIES**