

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	21T	STEPHENSON	49	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

FIELD TILE 6"				REMARKS
FOOT	LOCATION			
22.0	LT Sta.	477+47.0 TO	477+66.4	From Inlet, Stand Pipe to Field Tile Junction Vault
22.0	TOTAL			

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)				REMARKS
UNIT	LOCATION	OFFSET (ft)		
6	RT	468+52.0		
6	TOTAL			

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)				REMARKS
UNIT	LOCATION	OFFSET (ft)		
16	RT	468+86.0		
16	RT	468+86.0		
32	TOTAL			

20200100 EARTH EXCAVATION				REMARKS
CU. YD.	LOCATION			
349.2	LT & RT Sta.	467+00.0 TO	469+21.0	
330.2	LT & RT Sta.	475+50.0 TO	479+00.0	
212.4	LT & RT Sta.	497+00.0 TO	500+50.0	
891.8	TOTAL			

20400800 FURNISHED EXCAVATION				REMARKS
CU. YD.	LOCATION			
86.8	LT & RT Sta.	467+00.0 TO	469+21.0	Staging
34.6	LT & RT Sta.	475+50.0 TO	479+00.0	Staging
52.7	LT & RT Sta.	497+00.0 TO	500+50.0	Staging
174.1	TOTAL			

20800150 TRENCH BACKFILL				REMARKS
CU. YD.	LOCATION			
13.3	Sta.	467+70.2		CULVERT
13.3	Sta.	477+43.7		CULVERT
15.9	Sta.	498+59.0		CULVERT
42.5	TOTAL			

25000310 SEEDING, CLASS 4				REMARKS
ACRE	LOCATION			
0.04	RT Sta.	467+00.0 TO	469+21.0	
0.05	RT Sta.	475+50.0 TO	479+00.0	
0.04	RT Sta.	496+31.6 TO	501+00.8	
0.13	TOTAL			

25000910 SEEDING, CLASS 1 (MODIFIED)				REMARKS
ACRE	LOCATION			
0.12	LT Sta.	467+00.0 TO	469+21.0	
0.24	LT Sta.	475+50.0 TO	479+00.0	
0.37	TOTAL			

25001830 SEEDING, CLASS 6 (MODIFIED)				REMARKS
ACRE	LOCATION			
0.11	RT Sta.	467+00.0 TO	469+21.0	
0.17	RT Sta.	475+50.0 TO	479+00.0	
0.11	LT Sta.	497+00.0 TO	500+50.0	
0.16	RT Sta.	497+00.0 TO	500+50.0	
0.55	TOTAL			

25100115 MULCH, METHOD 2				REMARKS
ACRE	LOCATION			
0.12	LT Sta.	467+00.0 TO	469+21.0	
0.24	LT Sta.	475+50.0 TO	479+00.0	
0.04	RT Sta.	467+00.0 TO	469+21.0	
0.05	RT Sta.	475+50.0 TO	479+00.0	
0.04	RT Sta.	496+31.6 TO	501+00.8	
0.11	RT Sta.	467+00.0 TO	469+21.0	
0.17	RT Sta.	475+50.0 TO	479+00.0	
0.11	LT Sta.	497+00.0 TO	500+50.0	
0.16	RT Sta.	497+00.0 TO	500+50.0	
1.05	TOTAL			

28000250 TEMPORARY EROSION CONTROL SEEDING				REMARKS
POUND	LOCATION			
365.0	Entire Job			
365.0	TOTAL			

28000300 TEMPORARY DITCH CHECKS				REMARKS
EACH	LOCATION			
1	LT	467+49.7		
1	RT	467+50.4		
1	RT	468+00.7		
1	LT	468+00.8		
1	RT	469+00.2		
1	RT	476+00.3		
1	LT	477+00.3		
1	RT	477+00.4		
1	LT	477+99.6		
1	RT	478+00.9		
1	RT	498+00.6		
1	RT	499+01.3		
1	RT	500+00.7		
13	TOTAL			

28000400 PERIMETER EROSION BARRIER				REMARKS
FOOT	LOCATION			
320.7	LT	496+95.6 TO	500+54.6	
320.7	TOTAL			

28100107 STONE RIPRAP, CLASS A4				REMARKS
SQ. YD.	LOCATION		DIMENSION	
14.4	LT	467+70.2		13' x 10'
14.4	RT	467+70.2		13' x 10'
11.1	LT	477+43.7		10' x 10'
11.1	RT	477+43.7		10' x 10'
15.0	LT	498+59.0		15' x 9'
15.0	RT	498+59.0		15' x 9'
81.1	TOTAL			

28200200 FILTER FABRIC				REMARKS
SQ. YD.	LOCATION		DIMENSION	
14.4	LT	467+70.2		13' x 10'
14.4	RT	467+70.2		13' x 10'
11.1	LT	477+43.7		10' x 10'
11.1	RT	477+43.7		10' x 10'
15.0	LT	498+59.0		15' x 9'
15.0	RT	498+59.0		15' x 9'
81.1	TOTAL			

35100100 AGGREGATE BASE COURSE, TYPE A				REMARKS
TON	LOCATION			
31.7	Sta.	467+70.2		Temporary run-around
42.5	Sta.	477+43.7		Temporary run-around
34.2	Sta.	498+59.0		Temporary run-around
108.4	TOTAL			

FILE NAME = #FILES  
 LEVELS = #LEVELS  
 PLOT SCALE = #PLOTS/SCALE  
 DATE = #DATE  
 OPERATOR = #OPERATOR  
 REF = #REF  
 REF = #REF