

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	21T	STEPHENSON	49	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# SCHEDULE OF QUANTITIES

**35101400 AGGREGATE BASE COURSE, TYPE B**

TON	LOCATION	THICKNESS (in)	REMARKS
20.7	Sta. 467+70.2	9.0	14 x 26 - Temporary under incidental bituminous patch
7.8	Sta. 467+70.2	4.7	10 x 26 - Between top of culvert and bottom of CL B patch
20.7	Sta. 477+43.7	9.0	14 x 26 - Temporary under incidental bituminous patch
2.0	Sta. 477+43.7	1.2	10 x 26 - Between top of culvert and bottom of CL B patch
17.2	Sta. 498+59.0	9.0	11.6 x 26 - Temporary under incidental bituminous patch
6.9	Sta. 498+59.0	5.5	7.6 x 26 - Between top of culvert and bottom of CL B patch
49.8	LT Sta. 468+56.6	8.0	CE
29.3	RT Sta. 468+56.5	8.0	MB
62.7	LT Sta. 497+94.7	8.0	FE
56.4	LT Sta. 500+00.6	8.0	FE
<b>273.4</b>	<b>TOTAL</b>		

**40600200 BITUMINOUS MATERIALS (PRIME COAT)**

TON	LOCATION	THICKNESS (in)	REMARKS
0.03	LT Sta. 467+70.2	4.0	14 x 13 - One Lane - Temporary patch
0.03	RT Sta. 467+70.2	4.0	14 x 13 - One Lane - Temporary patch
0.14	LT Sta. 468+56.6	2.0	CE
0.07	RT Sta. 468+56.5	2.0	MB
0.03	LT Sta. 477+43.7	4.0	14 x 13 - One Lane - Temporary patch
0.03	RT Sta. 477+43.7	4.0	14 x 13 - One Lane - Temporary patch
0.02	LT Sta. 498+59.0	4.0	11.6 x 13 - One Lane - Temporary patch
0.02	RT Sta. 498+59.0	4.0	11.6 x 13 - One Lane - Temporary patch
<b>0.38</b>	<b>TOTAL</b>		

**42001200 PAVEMENT FABRIC**

SQ. YD.	LOCATION	REMARKS
20.2	LT Sta. 467+70.2	14 x 13 - One Lane
20.2	RT Sta. 467+70.2	14 x 13 - One Lane
20.2	LT Sta. 477+43.7	14 x 13 - One Lane
20.2	RT Sta. 477+43.7	14 x 13 - One Lane
16.8	LT Sta. 498+59.0	11.6 x 13 - One Lane
16.8	RT Sta. 498+59.0	11.6 x 13 - One Lane
<b>114.4</b>	<b>TOTAL</b>	

**44000600 SIDEWALK REMOVAL**

SQ. FT.	LOCATION	REMARKS
26.5	LT Sta. 468+50.5	BY CE
<b>26.5</b>	<b>TOTAL</b>	

**44201013 CLASS B PATCHES, TYPE IV, 13 INCH**

SQ. YD.	LOCATION	REMARKS
20.2	LT Sta. 467+70.2	14 x 13 - One Lane
20.2	RT Sta. 467+70.2	14 x 13 - One Lane
20.2	LT Sta. 477+43.7	14 x 13 - One Lane
20.2	RT Sta. 477+43.7	14 x 13 - One Lane
16.8	LT Sta. 498+59.0	11.6 x 13 - One Lane
16.8	RT Sta. 498+59.0	11.6 x 13 - One Lane
<b>114.4</b>	<b>TOTAL</b>	

**44213200 SAW CUTS**

FOOT	LOCATION	REMARKS
53.0	LT Sta. 467+70.2	14 x 13 - One Lane
53.0	RT Sta. 467+70.2	14 x 13 - One Lane
53.0	LT Sta. 477+43.7	14 x 13 - One Lane
53.0	RT Sta. 477+43.7	14 x 13 - One Lane
50.6	LT Sta. 498+59.0	11.6 x 13 - One Lane
50.6	RT Sta. 498+59.0	11.6 x 13 - One Lane
3.5	LT Sta. 468+50.5	Sidewalk by CE
<b>316.7</b>	<b>TOTAL</b>	

**48101200 AGGREGATE SHOULDERS, TYPE B**

TON	LOCATION	THICKNESS (in)	REMARKS
21.1	LT Sta. 467+00.0 TO 468+31.9	6	
2.5	LT Sta. 468+81.5 TO 469+00.0	6	
16.3	RT Sta. 467+00.0 TO 468+21.7	6	
44.3	LT Sta. 475+90.6 TO 479+00.0	6	
53.3	RT Sta. 475+50.0 TO 479+00.0	6	
52.1	LT Sta. 497+00.0 TO 500+49.8	6	
53.3	RT Sta. 497+00.0 TO 500+50.1	6	
<b>242.8</b>	<b>TOTAL</b>		

**50100300 REMOVAL OF EXISTING STRUCTURES NO. 1**

EACH	LOCATION	REMARKS
1	Sta. 467+70.0	
<b>1</b>	<b>TOTAL</b>	

**50100400 REMOVAL OF EXISTING STRUCTURES NO. 2**

EACH	LOCATION	REMARKS
1	Sta. 477+44.0	
<b>1</b>	<b>TOTAL</b>	

**50100500 REMOVAL OF EXISTING STRUCTURES NO. 3**

EACH	LOCATION	REMARKS
1	Sta. 498+59.0	
<b>1</b>	<b>TOTAL</b>	

**54010502 PRECAST CONCRETE BOX CULVERT 5' X 2'**

FOOT	LOCATION	REMARKS
60.0	Sta. 467+70.2	
60.0	Sta. 477+43.7	
<b>120.0</b>	<b>TOTAL</b>	

**542A5485 PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"**

FOOT	LOCATION	REMARKS
60.0	Sta. 498+59.0	
<b>60.0</b>	<b>TOTAL</b>	

**542D0223 PIPE CULVERTS, CLASS D, TYPE 1 18"**

FOOT	LOCATION	REMARKS
42.0	Sta. 468+56.6	CE
<b>42.0</b>	<b>TOTAL</b>	

**5421D018 PIPE CULVERTS, CLASS D, TYPE 1 18" (TEMPORARY)**

FOOT	LOCATION	REMARKS
12.0	LT Sta. 467+70.2	
12.0	LT Sta. 477+43.7	
12.0	LT Sta. 498+59.0	
<b>36.0</b>	<b>TOTAL</b>	

**54213453 END SECTIONS 18"**

EACH	LOCATION	REMARKS
2	Sta. 468+56.6	CE
<b>2</b>	<b>TOTAL</b>	

**54214515 PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"**

EACH	LOCATION	REMARKS
2	Sta. 498+59.0	
<b>2</b>	<b>TOTAL</b>	

**61100500 EXPLORATION TRENCH 52" DEPTH**

FOOT	LOCATION	OFFSET (ft)	REMARKS
10.0	LT Sta. 477+66.4	58.9	Field tile junction vault
<b>10.0</b>	<b>TOTAL</b>		

**61133100 FIELD TILE JUNCTION VAULTS, 2' DIA.**

EACH	LOCATION	OFFSET (ft)	REMARKS
1	LT Sta. 477+66.4	58.9	Field tile junction vault
<b>1</b>	<b>TOTAL</b>		

FILE NAME = #FILES  
 LEVELS = #LEVELS  
 PLOT SCALE = #PLOT SCALES  
 DATE = P.P. 5/99 82 13/4/93 2005  
 OPERATOR = #OPERATOR  
 REF REF REF