

# GENERAL NOTES

ROUTE NO.	SEC.	COUNTY	TOTAL SHEETS	SHEET NO.
FAS 221 (IL 94)	(19B-1)M	Rock Island	29	5
FED ROAD DIST. NO.	ILLINOIS	PROJECT		

Contract #64B06

The applicable portions of Article 105.07 of the Standard Specification shall apply except for the following: The Contractor shall be responsible to locate the vertical depths of the underground utilities which may interfere with construction operations. This work will not be measured or paid for separately, but shall be considered as included in the unit bid price for the item of construction involved.

Per SB 699 (90 day utility relocation law), a notice will be sent to the utility companies instructing them to have their facilities relocated within 90 days. Estimated date relocation complete = Letting Date + 135 days.

CADD data will be available to Contractors and Consultants working on this project. This information will be provided upon request as MicroStation CADD files and Geopak coordinate geometry files ONLY. If data is required in other formats it will be your responsibility to make these conversions. If any discrepancy or inconsistency arises between the electronic data and the information on the hard copy, the information on the hard copy should be used. Contact the District's Project Engineer to request these files.

## COMMITMENTS

1. All work on this structure over Mill Creek, 1 mile south of IL 192, shall be performed from the existing deck and no work shall take place below the existing structure on the ground.
2. No fill shall be placed in or around Mill Creek.

Program #5  
(Arch. Size)  
Enlarge  
200%  
Enlarge 107%