

# SCHEDULE OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
221	(19B-1) M	ROCK ISLAND	29	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

20200100 **EARTH EXCAVATION**

CU YD	LOCATION		
18.00	IL 94 LT&RT	195+06	- 197+13
66.00	LT&RT	197+81	- 200+90
<u>84.00</u>	<b>TOTAL</b>		

20400800 **FURNISHED EXCAVATION**

CU YD	LOCATION		
154.00	IL 94 LT&RT	195+06	- 197+13
73.00	LT&RT	197+81	- 200+90
<u>227.00</u>	<b>TOTAL</b>		

28100807 **STONE DUMPED RIPRAP, CLASS A4**

TON	LOCATION		
63.00	IL 94 LT	197+81	- 198+25
<u>63.00</u>	<b>TOTAL</b>		

40600980 **BITUMINOUS SURFACE REMOVAL - BUTT JOINT**

SQ YD	LOCATION		
73	IL 94 LT&RT	195+63	- 195+88
85	LT&RT	198+22	- 198+47
<u>158</u>	<b>TOTAL</b>		

40600990 **TEMPORARY RAMP**

SQ YD	LOCATION		
14	IL 94 LT&RT	197+09	- 197+13
14	LT&RT	197+81	- 197+85
<u>28</u>	<b>TOTAL</b>		

48101200 **AGGREGATE SHOULDERS, TYPE B**

TONS	LOCATION		
42	IL 94 LT	195+06	- 197+13
1	RT	195+65	- 195+93
33	RT	196+63	- 197+13
72	LT	197+81	- 200+90
49	RT	197+81	- 199+92
<u>197</u>	<b>TOTAL</b>		

63000000 **STEEL PLATE BEAM GUARDRAIL, TYPE A**

FOOT	LOCATION		
62.5	IL 94 LT	196+17	- 196+79
62.5	RT	198+15	- 198+78
162.5	LT	198+15	- 199+78
<u>287.5</u>	<b>TOTAL</b>		

63000130 **STEEL PLATE BEAM GUARDRAIL, TYPE A (SPECIAL)**

FOOT	LOCATION		
25	IL 94 RT	196+65	- 196+79
<u>25</u>	<b>TOTAL</b>		

63100087 **TRAFFIC BARRIER TERMINAL, TYPE 6A**

EACH	LOCATION		
1	IL 94 RT	196+79	- 197+13
1	LT	196+79	- 197+13
1	RT	197+81	- 198+15
1	LT	197+81	- 198+15
<u>4</u>	<b>TOTAL</b>		

63100167 **TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)**

EACH	LOCATION		
1	IL 94 LT	195+67	- 196+17
1	RT	196+65	- 196+65 (SIDE ROAD)
1	RT	198+78	- 199+28
1	LT	199+78	- 200+28
<u>4</u>	<b>TOTAL</b>		

63200310 **GUARDRAIL REMOVAL**

FOOT	LOCATION		
51	IL 94 RT	196+67	- 197+13
140	LT	195+74	- 197+13
139	RT	197+82	- 199+21
240	LT	197+82	- 200+21
<u>570</u>	<b>TOTAL</b>		

63500105 **DELINEATORS**

EACH	LOCATION		
1	IL 94 LT	195+67	
1	RT	196+65	(SIDE ROAD)
1	RT	199+28	
1	LT	200+28	
<u>4</u>	<b>TOTAL</b>		

70300220 **TEMPORARY PAVEMENT MARKING - LINE 4"**

FOOT	LOCATION		
1446	IL 94 LT & RT	194+31	- 200+68 (STAGE 2)
1446	LT & RT	194+31	- 200+68 (STAGE 3)
<u>2892</u>	<b>TOTAL</b>		

70301000 **WORK ZONE PAVEMENT MARKING REMOVAL**

SQ FT	LOCATION		
482	IL 94 LT & RT	194+31	- 200+68 (STAGE 2)
482	LT & RT	194+31	- 200+68 (STAGE 3)
<u>964</u>	<b>TOTAL</b>		

70400100 **TEMPORARY CONCRETE BARRIER**

FOOT	LOCATION		
90	IL 94 LT	195+22	- 196+12 (STAGE 2)
270	LT	197+02	- 199+72 (STAGE 2)
90	RT	196+12	- 197+02 (STAGE 3)
<u>450</u>	<b>TOTAL</b>		

70400200 **RELOCATE TEMPORARY CONCRETE BARRIER**

FOOT	LOCATION		
90	IL 94 RT	195+22	- 196+12 (STAGE 3)
270	RT	197+02	- 199+72 (STAGE 3)
<u>360</u>	<b>TOTAL</b>		

78001110 **PAINT PAVEMENT MARKING - LINE 4" (TWO COATS)**

FOOT	LOCATION		
740	IL 94 LT	195+59	- 199+29 (EDGE LINE)
740	RT	195+59	- 199+29 (EDGE LINE)
624	STA	195+59	- 198+71 (SOLID YELLOW)
180	STA	195+59	- 199+29 (SKIP DASH)
<u>2284</u>	<b>TOTAL</b>		

78200410 **GUARDRAIL MARKERS, TYPE A**

EACH	LOCATION		
4	IL 94 LT	196+17	- 197+13
4	RT	196+65	- 197+13
4	LT	197+81	- 199+78
4	RT	197+81	- 198+78
<u>16</u>	<b>TOTAL</b>		

78201000 **TERMINAL MARKER - DIRECT APPLIED**

EACH	LOCATION		
1	IL 94 LT	195+67	
1	RT	196+65	
1	RT	199+28	
1	LT	200+28	
<u>4</u>	<b>TOTAL</b>		

78300500 **PAINT PAVEMENT MARKING REMOVAL**

SQ FT	LOCATION		
123	IL 94 LT	195+59	- 199+29 (EDGE LINE)
123	RT	195+59	- 199+29 (EDGE LINE)
104	STA	195+59	- 198+71 (SOLID YELLOW)
31	STA	195+59	- 199+29 (SKIP DASH)
<u>381</u>	<b>TOTAL</b>		

PLOT DATE = Wed Oct 26 11:26:42 2005  
 FILE NAME = c:\p\projects\2285896\2285896.dgn  
 USER NAME = j...  
 USER MAKE = ...

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE:	VERT. HORIZ.	DRAWN BY
DATE		CHECKED BY