

# SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	32-2HBR	GRUNDY	171	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 66412				

NO.	PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	IM	IM	BRI	IM		90% FED 10% ST
					90% FED 10% STATE GRUNDY CO.	90% FED 10% STATE	80% FED 20% STATE GRUNDY CO.	GRUNDY CO.		GRUNDY
					ROADWAY J000-2A	LASALLE 1000	SN 032-0114 BRIDGE X771-2A	LIGHTING Y030-IE	SAFETY SFTY-3N	SN 032-W001 RETAINING WALL Y007
* 185	83700300	LIGHT TOWER FOUNDATION, 48" DIAMETER	FOOT	30					30	
* 186	83700350	LIGHT TOWER FOUNDATION, 54" DIAMETER	FOOT	36					36	
* 187	84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	16					16	
* 188	84200705	LIGHTING FOUNDATION REMOVAL, PARTIAL	EACH	4					4	
* 189	84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1					1	
* 190	84500120	REMOVAL OF ELECTRIC INSTALLATION SERVICE	EACH	1					1	
* 191	84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1					1	
192	X0322936	REMOVE EXISTING FLARED END SECTION	EACH	4	4					
193	X3550300	BITUMINOUS BASE COURSE, SUPERPAVE 6"	TON	850	850					
194	X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C" N50	TON	415	19	396				
195	X4066538	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E" N90	TON	2429	2429					
196	X4066765	LEVELING BINDER (MACHINE METHOD) SUPERPAVE N50	TON	707	707					
197	X4066770	LEVELING BINDER (MACHINE METHOD) SUPERPAVE N70	TON	497	497					
198	X6013600	PIPE UNDERDRAINS 4" (MODIFIED)	FOOT	19542	19542					
199	X6013820	PIPE UNDERDRAIN OUTLET EXTENSION SPECIAL	EACH	9	9					
200	X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	39	39					
201	X6064201	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06	FOOT	2479	2479					
202	X6065701	CONCRETE MEDIAN, TYPE SM-4.06	SQ FT	2443	2443					
203	X8420220	REMOVE EXISTING HIGH MAST LIGHT TOWER	EACH	4					4	
204	XX005347	BITUMINOUS CONCRETE BINDER COURSE, IL 19.0 N50	TON	6,659	6,214	445				
205	XX005430	MAINTENANCE OF EXISTING HIGHWAY LIGHTING	L SUM	1					1	
* 206	XX005466	FURNISHING AND INSTALLING GUARDRAIL END SHOES	EACH	1	0	1				
207	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	48058	48058					
208	Z0002600	BAR SPLICERS	EACH	124		124				
* 209	Z0008230	DRILLED SHAFT IN SOIL 30"	FOOT	600		600				
210	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
211	Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	2					2	
212	Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2					2	
213	Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	9					9	
214	Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE), NARROW, TEST LEVEL 3	EACH	3					3	
215	Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1					1	
216	Z0047300	PROTECTIVE SHIELD	SQ YD	420		420				
217	Z0076600	TRAINEES	hour	2,000	2,000					
218	Z0001058	AGGREGATE SUBGRADE 18"	SQ YD	1528	1528					
219										
220	Z8500100	FABRIC FORMED CONCRETE REVETMENT MATS	SQ YD	300	300					
221	48300410	PCC SHOULDERS 9 1/2"	SQ YD	16,285	16,285					
222	50104650	SLOPE WALL REMOVAL	SQ YD	300	300					
223	63500120	DELINEATOR REMOVAL	EACH	154	154					
224	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	500	500					
225	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	348	348					
	XX004056	MECHANICALLY STABILIZED EARTH RETAINING WALLS	SQ FT	926						926
	60602800	CONCRETE GUTTER, TYPE B	FOOT	77						77
	81020900	CONDUIT PUSHED, 4" DIA, INTERMEDIATE METAL	FOOT	215				215		
	83035400	LIGHT POLE, STEEL, 45 FT. M.H., TENON MOUNT - TWIN	EACH	4				4		
	83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8"	EACH	4				4		
	83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	16				16		

REVISIONS  
1-06-2006

Louis Berger & Associates, Inc.  
100 Elm Street, Suite 300  
Manchester, NH 03101  
(603) 544-5200

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
I-80 (F.A.I. 80) AT  
SENECA ROAD (F.A.P. 623)  
GRUNDY COUNTY  
SUMMARY OF QUANTITIES

SCALE: VERT. DATE 10/14/05  
HORIZ. DRAWN BY NMR/TCH  
CHECKED BY DJL/CML

1/15/2006 V:\CHICAGO\DOT\1836\CAD\DWG\1836\_SUM\_QNTY\_05.dgn

\* SPECIALTY ITEMS      0 Y080