F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	32-2HBR	GRUNDY	171	19
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 66412

SCHEDULE OF QUANTITIES

POLYUREA TYPE 2 PAVEMENT MARKING

LOCATION	LINE 4" (WHITE) (FOOT) 78008310	LINE 4" (YELLOW) (FOOT) 78008310	LINE 6" (WHITE) (FOOT) 78008330	LINE 8" (WHITE) (FOOT) 78008340	LINE 12" (WHITE) (FOOT) 78008350	LINE 24" (WHITE) (FOOT) 78008370	LETTERS AND SYMBOLS (WHITE) (SQ. FT.) 78008300
F.A.P. 623 (SENECA ROAD)							
475+75.00 TO 36+11.55	6480	7050		520		100	50
RAMP A							
98+95.33 TO 118+26.40	2080	1165		1480	560		
RAMP B							
150+12.90 TO 177+82.37	2800	1120		1580			
RAMP C							
198+95.31 TO 221+43.25	2330	1430		1460	550		
RAMP D							
250+12.97 TO 279+30.07	2950	1260		1590			
F.A.I. 80							
800+52.68 TO 803+52.65, 44' LT	300						
837+83.83 TO 846+34.04, 44' RT	851						
837+80.55 TO 840+80.50, 44' RT	300						
791+36.73 TO 799+86.92, 44' LT	851						
791+36.34 TO 840+80.62	2500	4945	1850				
800+52.69 TO 846+32.92	2150	4580	1725				
TOTALS	45150		3575	6630	1110	100	50

TEMPORARY PAVEMENT MARKING AND REMOVAL

LOCATION	TEMPORARY PAVEMENT MARKING							SHORT TERM PAVEMENT MARKING	PAVEMENT MARKING REMOVAL
	LINE 4"		LINE 8"		LINE 12"	LINE 24"	SYMBOLS		
	WHITE	YELLOW	WHITE	YELLOW	WHITE	WHITE	WHITE		
	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	SQ. FT.	LIN. FT.	SQ. FT.
	70300220	70300220	70300250	70300250	70300260	70300280	70300210	70300100	78300100
F.A.P. 623 (SENECA ROAD)									
475+75.00 TO 36+11.55	6480	7050		520		100	50		5107
RAMP A									
98+95.33 TO 118+26.40	2080	1165		1480	560				2628
RAMP B									
150+12.90 TO 177+82.37	2800	1120		1580					2360
RAMP C									
198+95.31 TO 221+43.25	2330	1430		1460	550				2777
RAMP D									
250+12.97 TO 279+30.07	2950	1260		1590					2463
F.A.I. 80									
800+52.68 TO 803+52.65, 44' LT	300								100
837+83.83 TO 846+34.04, 44' RT	851								284
837+80.55 TO 840+80.50, 44' RT	300								100
791+36.73 TO 799+86.92, 44' LT	851							1332	284
791+36.34 TO 840+80.62	2500	4945	1850					1333	3407
800+52.69 TO 846+32.92	2150	4580	1725						3106
TOTALS	45150		3575	6630	1110	100	50	2665	22616

MEDIAN QUANTITIES

LOCATION	CORRUGATED MEDIAN (SQ. FT.) 60624600	ISLAND PAVEMENT (SPECIAL) (SQ. YD.) 60625800	CONCRETE MEDIAN, TYPE SM-4.06 (SQ. FT.) X6065701	CONCRETE MEDIAN, TYPE SM-6.06 (SQ. FT.) 60622400
F.A.P. 623 (SENECA ROAD)				
7+24.86 TO 9+38.01	809			
8+54.86 TO 14+36.29		7042		
15+27.44 TO 18+08.07			1359	
18+08.07 TO 18+48.49				200
20+51.49 TO 20+91.91				200
20+81.91 TO 23+17.44			1084	
24+08.58 TO 30+05.15		7267		
29+22.00 TO 31+35.15	811			
RAMP A				
118+50 (CORNER ISLAND)		175		
RAMP C				
221+20 (CORNER ISLAND)		91		
TOTALS	1620	14575	2443	400

COMBINATION CONCRETE CURB AND GUTTER

LOCATION	TYPE M-4.06 (FOOT) X6064201	TYPE M-4.24 (FOOT) X6063600
F.A.P. 623 (SENECA ROAD)		
8+54.86 TO 14+36.29	1181	
24+08.58 TO 30+05.15	1212	
RAMP A		
118+50 (CORNER ISLAND)	45	22
RAMP C		
221+20 (CORNER ISLAND)	41	17
TOTALS	2479	39

LOCATION	TEMP. RAMPS (SQ. YD.) 40600990
F.A.I. 80	14
791+36.34 LT	14
800+52.69 RT	14
840+80.62 LT	14
846+32.92 RT	
F.A.P 623 SENECA ROAD	13
36+61.55	
TOTAL	69

LOCATION	BITUMINOUS MATERIAL PRIME COAT (GAL.) 40600100
SENECA DRIVEWAY	
401+15.00 TO 403+09.18	275
TOTAL	275

REVISIONS	
NAME	DATE
MJ	12 6 05

ILLINOIS DEPARTMENT OF TRANSPORTATION

I-80 (F.A.I. 80) AT SENECA ROAD (F.A.P. 623) GRUNDY COUNTY

SCHEDULE OF QUANTITIES

SCALE: N.T.S. DRAWN BY NMR/BJG

DATE 10/14/05 CHECKED BY DJL/JPL