

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	32-2HR	GRUNDY	171	22
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO.		6642		

SCHEDULE OF QUANTITIES

LOCATION	(FIELD TILE REPLACEMENT)																
	STORM SEWERS PROTECTED CLASS A 8" (FOOT) 61101009	STORM SEWERS PROTECTED CLASS A 10" (FOOT) 61101011	STORM SEWERS PROTECTED CLASS A 12" (FOOT) 61101013	STORM SEWERS PROTECTED CLASS A 14" (FOOT) 61101016	STORM SEWERS SPECIAL 6" (FOOT) 61139990	STORM SEWERS SPECIAL 8" (FOOT) 61140000	STORM SEWERS SPECIAL 10" (FOOT) 61140100	STORM SEWERS SPECIAL 12" (FOOT) 61140200	STORM SEWERS SPECIAL 14" (FOOT) 61140300	FIELD TILE JUNCTION VAULTS 2' DIA. (EACH) 61133100	FIELD TILE JUNCTION VAULTS 3' DIA. (EACH) 61133200	EXPLORATION TRENCH 52" DEPTH (EACH) 61100500	MISC. CONCRETE (CU YD) 61100605	PIPE DRAIN 10" (FOOT) 60100935	PIPE DRAIN 12" (FOOT) 60100945	PIPE DRAIN 15" (FOOT) 60100955	PIPE DRAIN 18" (FOOT) 60100965
F.A.P. 623 (SENECA ROAD)																	
13+16.20, 77.7' RT.											1						
13+60.20, 77.7' RT TO 15+96.46, 132.0' RT			280														
15+96.46, 132.0' RT.											1						
15+96.46, 132.0' RT. TO 18+60.04, 123.1' RT.							264										
18+60.04, 183.1' RT											1						
20+33.35, 216.6' RT.											1						
20+33.35, 216.6' RT. TO 115+66.73, 76.2' RT							215										
RAMP A																	
115+66.73, 76.2' LT.											1						
115+66.73, 76.2' LT. TO 116+15.41, 63.9' RT			148														
116+15.41, 63.9' RT													1				
RAMP D																	
264+50 LT TO 267+00 LT												250					
FRONTAGE ROAD																	
304+02.55, 50.9' LT										1							
304+02.55, 50.9' LT TO 305+16.92, 38.5' LT							126										
304+26.25, 45.3' LT										1							
305+16.92, 38.5' LT										1							
306+72.05, 31.6' LT TO 305+16.92, 38.5' LT							165										
306+72.05, 31.6' LT										1							
306+31.80, 39.9' LT TO 305+26.25, 45.3' LT							115										
306+31.80, 39.9' LT										1							
312+50.00, 41.0' LT TO 306+31.80, 39.9' LT							620										
MISCELLANEOUS AREAS																	
AS NECESSARY	100	100	100	100	315	100	100	100	100	10	15	1000	6	40	40	40	40
TOTALS	100	100	528	100	1050	391	100	579	100	15	20	1250	7	40	40	40	40

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**I-80 (F.A.I. 80) AT
 SENECA ROAD (F.A.P. 623)
 GRUNDY COUNTY**
 SCHEDULE OF QUANTITIES

SCALE: N.T.S.
 DATE 10/14/05

DRAWN BY NMR/BJG
 CHECKED BY DJL/JPL