

SCHEDULE OF QUANTITIES

SCHEDULE FOR STANDARD SIGNS						
LOCATION	STANDARD NUMBER	SIGN PANEL		WOOD SIGN SUPPORT (FOOT)	SIGN PLACEMENT	
		TYPE 1	TYPE 2		HEIGHT ABOVE EDGE OF PAVEMENT	DISTANCE FROM EDGE OF PAVEMENT
		(SQ. FT.)	(SQ. FT.)			
F.A.P. 623 (SENECA ROAD)		72000100	72000200	73000100		
2+38, RT	W6-1-36	9.00		18	7'-0"	12'-0"
11+82, LT (IN MEDIAN)	W6-2-36	9.00		17	7'-0"	2' BACK OF CURB
14+13, LT (IN MEDIAN)	M3-4(B)-3015 M1-1-36 M5-1L-3018	3.13 9.00 3.75		18	11'-6" 8'-6" 7'-0"	2' BACK OF CURB
17+87, RT (IN MEDIAN)	R3-1100-2424	4.00		14	7'-0"	CENTERED IN MEDIAN
20+57, LT (IN MEDIAN)	R3-1100-2424	4.00		14	7'-0"	CENTERED IN MEDIAN
24+32, RT (IN MEDIAN)	M3-2(B)-3015 M1-1-36 M5-1L-3018	3.13 9.00 3.75		18	11'-6" 8'-6" 7'-0"	2' BACK OF CURB
26+79, RT (IN MEDIAN)	W6-2-36	9.00		17	7'-0"	2' BACK OF CURB
36+23, LT	W6-1-36	9.00		20	7'-0"	18'-0"
RAMP A						
118+24, LT	R1-1-36	9.00		15	5'-0"	12'-0"
118+53, LT (IN ISLAND)	R6-3-2418	3.00		SEE SIGN RELOCATION SCHEDULE	4'-0"	2' BACK OF CURB
RAMP C						
221+07, LT	R1-1-36	9.00		15	5'-0"	12'-0"
221+19, RT (IN ISLAND)	R6-3-2418	3.00		SEE SIGN RELOCATION SCHEDULE	4'-0"	2' BACK OF CURB
FRONTAGE ROAD						
300+31, LT	R1-1-30	6.25		14	5'-0"	6'-0"
TOTALS		106	0	180		

SCHEDULE FOR REMOVE SIGN PANEL ASSEMBLY TYPE A OR TYPE B				
LOCATION	TYPE OF SIGNS	SIGN SUPPORT REMOVAL (EACH)	QUANTITIES	
			TYPE A (EACH)	TYPE B (EACH)
F.A.P. 623 (SENECA ROAD)			72400100	72400200
5+97, LT	W14-3-486464	1		1
31+48, RT	W14-3-486464	1		1
TOTALS		2	0	2

* EXISTING LOCATIONS ON THE RAMPS ARE BASED ON PROPOSED RAMP STATIONING.

SHOULDER RUMBLE STRIPS 64200105	
LOCATION	(EACH)
F.A.P. 623 (SENECA ROAD)	
1+50 TO 2+50 LT	100
1+50 TO 13+03 RT	1153
3+40 TO 12+82 LT	942
14+71 TO 18+18 RT	347
14+59 TO 18+18 LT	359
20+82 TO 23+90 RT	308
20+82 TO 23+80 LT	298
25+80 TO 31+96 RT	616
25+80 TO 36+11 LT	1031
32+93 TO 36+11 RT	318
RAMP A	
99+00 TO 118+09 RT	1909
106+61 TO 117+55 LT	1094
RAMP B	
151+72 TO 162+02 LT	1030
151+22 TO 177+82 RT	2660
RAMP C	
198+97 TO 220+36 RT	2139
206+60 TO 220+73 LT	1413
RAMP D	
250+09 TO 279+26 RT	2917
251+72 TO 263+40 LT	1168
TOTALS	19802

WOVEN WIRE FENCE, 4' 66500105	
LOCATION	(FOOT)
F.A.I. 80	
LT. 793+81 TO LT. 817+99	2550
RT. 799+56 TO RT. 811+46	1192
LT. 820+38 TO LT. 843+48	2540
RT. 821+02 TO RT. 848+89	2900
F.A.P. 623 (SENECA ROAD)	
RT. 8+00 TO RT. 13+01	510
LT. 8+00 TO LT. 11+09	310
RT. 25+31 TO RT. 32+00	675
LT. 25+46 TO LT. 32+00	660
LOCKED GATE EBACC	
RT. 10+76 TO RT 18+70	842
TOTALS	12179

WOVEN WIRE FENCE GATES 4' x 24' DOUBLE 66502000	
LOCATION	(FOOT)
LOCKED GATE EBACC	
10+70.40 LT 0.8' TO RT 23.2'	1
LOCKED GATE WBACC	
158+36.50 LT 11.4' TO RT 12.6'	1
TOTALS	2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**I-80 (F.A.I. 80) AT
 SENECA ROAD (F.A.P. 623)
 GRUNDY COUNTY**
 SCHEDULE OF QUANTITIES

SCALE: N.T.S. DRAWN BY NMR/BJG
 DATE 10/14/05 CHECKED BY DJL/JPL