

FAP RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
697	17BR	FORD	40	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LOCATION	RRPM	RRPM (BRIDGE)	RRPM REMOVAL
	EACH	EACH	EACH
STA 922+00	1		1
STA 922+80		1	
STA 923+60		1	
STA 924+40		1	
<b>TOTALS</b>	<b>2</b>	<b>2</b>	<b>1</b>

LOCATION	DESCRIPTION	SHORT-TERM PAVEMENT MARKING	PAINT PAVEMENT MARKING - LINE	
		(2 APPLICATIONS)	4"	6"
		FOOT	FOOT	FOOT
STA 921+32 TO STA 925+18	SOLID WHITE EDGE LINE		772	
STA 921+32 TO STA 925+18	SKIP-DASH YELLOW CENTERLINE	80		100
<b>TOTALS</b>		<b>80</b>	<b>772</b>	<b>100</b>

LOCATION	PAVEMENT MARKING DESCRIPTION	WORK ZONE PAVEMENT MARKING REMOVAL
		SQ FT
CENTERLINE	SHORT-TERM	27
<b>TOTAL</b>		<b>27</b>

LOCATION	CONCRETE HEADWALL FOR PIPE DRAINS
	EACH
STRUCTURE NO. 027-0068 - NW CORNER	1
STRUCTURE NO. 027-0068 - SW CORNER	1
STRUCTURE NO. 027-0068 - NE CORNER	1
STRUCTURE NO. 027-0068 - SE CORNER	1
<b>TOTAL</b>	<b>4</b>

LOCATION	BRIDGE APPROACH PAVEMENT	PROTECTIVE COAT	CONNECTOR (FLEXIBLE)
	SQ YD	SQ YD	SQ YD
STRUCTURE NO. 027-0068 - WEST APPROACH	107	107	21.5
STRUCTURE NO. 027-0068 - EAST APPROACH	107	107	21.5
<b>TOTALS</b>	<b>214</b>	<b>214</b>	<b>43</b>

LOCATION	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	SPBGR, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 6A	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B	TERMINAL MARKER-DIRECT APPLIED	STEEL BRIDGE RAIL, TYPE SM
	EACH	FOOT	EACH	EACH	EACH	EACH	FOOT
STRUCTURE NO. 027-0068 - NORTHWEST	1	50.0	1	2			
STRUCTURE NO. 027-0068 - SOUTHWEST	1	87.5	1	2			
STRUCTURE NO. 027-0068 - NORTHEAST	1	87.5	1	2			
STRUCTURE NO. 027-0068 - SOUTHEAST	1	50.0	1	2			
STRUCTURE NO. 027-0068 - BRIDGE					2		280
<b>TOTALS</b>	<b>4</b>	<b>275.0</b>	<b>4</b>	<b>8</b>	<b>2</b>	<b>4</b>	<b>280</b>

LOCATION	REMOVE SIGN PANEL ASSEMBLY TYPE A
	EACH
STA 923+25, 28' RT	1
STA 924+49, 27' LT	1
<b>TOTAL</b>	<b>2</b>

LOCATION	FOOT
STA 922+00 TO BRIDGE, LEFT	101
STA 922-31 TO BRIDGE, RIGHT	101
BRIDGE TO STA 925+43, LEFT	101
BRIDGE TO STA 925+74, RIGHT	101
<b>TOTAL</b>	<b>404</b>

**ESCA**  
CONSULTANTS, INC.

DESIGNED BY:	MTD	6/05
DRAWN BY:	HAG	6/05
CHECKED BY:	MTD	6/05
APPROVED BY:	RDP	8/05

*SCHEDULES OF QUANTITIES*  
*FAP RTE 697 (IL 9)*  
*SECTION 17BR*  
*FORD COUNTY*