

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	(99, 100, 371)	LASALLE	9	3

# SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: Y007

CODE NO.	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITY
20400800	FURNISHED EXCAVATION	CU YD	40
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	20
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	185
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	37
44000600	SIDEWALK REMOVAL	SQ FT	185
50102400	CONCRETE REMOVAL	CU YD	1.4
50102500	CONCRETE REMOVAL (SPECIAL)	CU YD	5
50200100	STRUCTURE EXCAVATION	CU YD	37
50300255	CONCRETE STRUCTURES	CU YD	1.4
50800105	REINFORCEMENT BARS	POUND	142
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	77
51000205	PIPE HANDRAIL REMOVAL	FOOT	31
51205200	TEMPORARY SHEET PILING	SQ FT	408
54002060	EXPANSION BOLTS 3/4 INCH X 12 INCH	EACH	10
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	7
60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	37
64000110	SIGHT SCREEN (CHAIN LINK FENCE) 6'	FOOT	40
67100100	MOBILIZATION	L SUM	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
<del>X2010505</del>	<del>CLEARING SPECIAL</del>	<del>L SUM</del>	<del>1</del>
XX002909	CLASS SI CONCRETE	CU YD	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 FAP 68 ALT. (IL 23 ALT.)  
 SECTION: (99, 100, 371)  
 LASALLE COUNTY  
 STA. 569+78.5

DATE 09/12/2005 DRAWN BY RLW

△ REVISED 1/04/06

Date: 09/30/2005  
File: c:\projects\cm01n06\cm323\details.dgn