| CONTRACT NO. 68 | F.A.P. | SECTION | COUNTY | TOTAL SHEET | NO. 404 | PEORIA | 27 | 4

FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT

## SCHEDULE OF QUANTITIES

<u>MOBILIZATION</u>

ENTIRE PROJECT = 1.0 LSUM

T, C, & P, STANDARD 701201

QUEENWOOD JOBSITE = 1.0 LSUM

T. C. & P. STANDARD 701406

INDIAN CRK. JOBSITE = 1.0 LSUM

T. C. & P. STANDARD 701601

BARTONVILLE JOBSITE = 0.5 LSUM 122E JOBSITE = 0.5 LSUM

1.0 LSUM

BLAST CLEANING BRIDGE JOINT STEEL

BRIDGE JOBSITES

= 1078 FOOT

METALIZING BRIDGE JOINT STEEL

BRIDGE JOBSITES

= 972 FOOT

SILICONE JOINT SEALER

BRIDGE JOBSITES = 1078 FOOT

BRIDGE MEDIAN EPDM SPECIAL

BARTONVILLE JOBSITE

= 890 FOOT

BI TUMI NOUS REMOVAL (MI SCELLANEOUS)

IL. 122E BRIDGE JOBSITE = 8.0 SQ. YD.

BITUMINOUS MIXTURE FOR PATCHING

IL. 122E BRIDGE JOBSITE = 1.0 TON

BLAST CLEANING PPC BEAM ENDS

INDIAN CREEK BRIDGE JOBSITE = 48 FOOT

METALIZING PPC BEAM ENDS

INDIAN CREEK BRIDGE JOBSITE = 279 SQ. FT.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	iccinois oci mi metti	O. HIMIDI ON MITON
		COLIEDI	u
		SCHEDULE OF QUANTITIES	
		QUAITI	11160
		TOWERT.	
		SCALE: HORIZ.	DRAWN BY CEJ
1		DATE 01-13-2004	CHECKED BY