

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
836	118BR	CHAMPAIGN	29	3
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE X080-2A
20200100	EARTH EXCAVATION	CU YD	100	100
20400800	FURNISHED EXCAVATION	CU YD	30	30
25000210	SEEDING CLASS 2A	ACRE	0.50	0.50
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45	45
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45	45
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45	45
25100115	MULCH, METHOD 2	ACRE	0.5	0.5
25100630	EROSION CONTROL BLANKET	SQ YD	334	334
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	50	50
28000400	PERIMETER EROSION BARRIER	FOOT	80	80
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	25	25
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	41	41
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	174	174
44000030	BITUMINOUS SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	373	373
48101200	AGGREGATE SHOULDERS, TYPE B	TON	129	129
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1
50102400	CONCRETE REMOVAL	CU YD	3.4	3.4
50300225	CONCRETE STRUCTURES	CU YD	4.7	4.7
50300260	BRIDGE DECK GROOVING	SQ YD	249	249

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE X080-2A
50300300	PROTECTIVE COAT	SQ YD	273	273
X5030305	CONCRETE WEARING SURFACE 5"	SQ YD	266	266
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	2393	2393
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4550	4550
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	145	145
51500100	NAME PLATES	EACH	1	1
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	500.0	500.0
* 63000130	STEEL PLATE BEAM GUARD RAIL, TYPE A (SPECIAL)	FOOT	50.0	50.0
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE I, SPECIAL (TANGENT)	EACH	4	4
63200310	GUARDRAIL REMOVAL	FOOT	368	368
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1
* 78001110	PAINT PAVEMENT MARKING - LINE 4'	FOOT	597	597
* 78200400	GUARDRAIL REFLECTORS	EACH	13	13
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4
X0323557	BRIDGE JOINT SYSTEM (EXPANSION), 1'	FOOT	76.0	76.0
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C, N50	TON	66.0	66.0
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	22	22

* DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DRAWN BY MLO
CHECKED BY SJK

DATE 6/05