

80% FEDERAL
20% STATE

CODE NO.	ITEM	UNITS	80% FEDERAL 20% STATE		
			1000-2A	AD71-2A	TOTAL
54213450	END SECTIONS 15"	EACH	34	0	34
54213453	END SECTIONS 18"	EACH	12	0	12
54213459	END SECTIONS 24"	EACH	22	0	22
54213471	END SECTIONS 36"	EACH	4	0	4
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	0	2
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	0	1
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	4	0	4
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	2	0	2
54248510	CONCRETE COLLAR	CU YD	3.3	0	3.3
542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	84	0	84
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	858	0	858
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	301	0	301
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	701	0	701
542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	119	0	119
5422D015	PIPE CULVERTS, CLASS D, TYPE 2 15" (TEMPORARY)	FOOT	42	0	42
5422D018	PIPE CULVERTS, CLASS D, TYPE 2 18" (TEMPORARY)	FOOT	150	0	150
5423D060	PIPE CULVERTS, CLASS D, TYPE 3 60" (TEMPORARY)	FOOT	50	0	50
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	20	0	20
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	48	0	48
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	118	0	118
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	183	0	183
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	217	0	217
55101200	STORM SEWER REMOVAL 24"	FOOT	97	0	97
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4	0	4
60107600	PIPE UNDERDRAINS 4"	FOOT	1990	0	1990
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	52	0	52
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	0	1
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1	0	1
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1	0	1
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	0	1
60236600	INLETS, TYPE A, TYPE 9 FRAME AND GRATE	EACH	1	0	1
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	1	0	1
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1	0	1
60240303	INLETS, TYPE B, TYPE 9 FRAME AND GRATE	EACH	1	0	1
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	9.6	0	9.6
60600605	CONCRETE CURB, TYPE B	FOOT	120	0	120
60602500	CONCRETE GUTTER, TYPE A	FOOT	569.5	0	569.5
60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXIST PAVEMENT)	FOOT	301.4	0	301.4
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	400	0	400
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	0	4
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL, FLARED	EACH	4	0	4
63200310	GUARDRAIL REMOVAL	FOOT	1761	0	1761

* SPECIALTY ITEMS

80% FEDERAL
20% STATE

CODE NO.	ITEM	UNITS	80% FEDERAL 20% STATE		
			1000-2A	AD71-2A	TOTAL
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	86	0	86
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	7	0	7
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	0	24
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	24	0	24
67100100	* MOBILIZATION	L SUM	1	0	1
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	1	0	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	5	0	5
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	0	20
70106500	* TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	5	0	5
70106700	* TEMPORARY RUMBLE STRIP	EACH	30	0	30
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5725	0	5725
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	55066	0	55066
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2532	0	2532
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	3640	0	3640
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	2470	0	2470
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	46500	0	46500
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	211	0	211
* 78200410	* GUARDRAIL MARKERS, TYPE A	EACH	16	0	16
* 78200530	* BARRIER WALL MARKERS, TYPE C	EACH	364	0	364
* 78201000	* TERMINAL MARKER - DIRECT APPLIED	EACH	4	0	4
X0301280	* PLUG EXISTING DRAINS	EACH	0	82	82
X0321100	* GEOTEXTILE RETAINING WALL	SQ FT	133	0	133
X0322194	* POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ FT	0	30	30
X0322871	* MAINTENANCE OF EROSION CONTROL SYSTEM	LSUM	1	0	1
X0323236	* TEMPORARY INLET	EACH	3	0	3
X0323857	BRIDGE JOINT SYSTEM EXPANSION 1/4"	FOOT	0	75	75
X0323858	BRIDGE JOINT SYSTEM EXPANSION 1/2"	FOOT	0	36	36
X0636700	* CLEANING AND PAINTING BEARINGS	EACH	0	40	40
X3550400	* BITUMINOUS BASE COURSE, SUPERPAVE, 7"	SQ YD	4738	0	4738
X3550500	* BITUMINOUS BASE COURSE, SUPERPAVE, 8"	SQ YD	1771	0	1771
X4021000	* TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	6	0	6
X4066414	* BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	4222	0	4222
X4066765	* LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	1737	0	1737
X4073151	* BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 13 1/2"	SQ YD	4609	0	4609
X4080020	* INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TONS	235	0	235
X0500715	GRACK AND REMOVE EXISTING BEARINGS	EACH	30	0	30
X6050700	REMOVE INLET BOX	EACH	1	0	1
XX005128	6TRIP SEAL EXPANSION JOINT ASSEMBLY	FOOT	70	70	
Z0002600	BAR SPLICERS	EACH	0	54	54
Z0006110	* BRIDGE DECK MICROSILICA CONCRETE OVERLAY	SQ YD	0	2599	2599
Z0006202	BRIDGE DECK SCARIFICATION (3/4 INCH)	SQ YD	0	2599	2599

REV.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	5R, Y, RS-1	CLAY	242	6
STA. TO STA.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 74078				

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE: 10-21-05

DRAWN BY: UJ
CHECKED BY: MAR