

# PAVING SUMMARY

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	5R, Y, RS-1	CLAY	242	16
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STATION	PROCESSING LIME MODIFIED SOILS 12"	AGGREGATE (PRIME COAT)	BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS BASE COURSE, SUPERPAVE, 7"	BITUMINOUS BASE COURSE, SUPERPAVE, 8"	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 13 1/2"	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 6"	AGGREGATE SHOULDERS, TYPE B, 8"	BITUMINOUS SHOULDERS SUPERPAVE, 8"	BITUMINOUS MIXTURE COMPLETE
	SQ YD	TON	GALLON	SQ YD	SQ YD	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	TON
<i>U.S. 45</i>												
1143+50.00 to 1231+00.00		50.6	1895.8			2145.7	1067.7		948.4	7415.4	5833.3	
1231+00.00 to 1237+00.00		3.5	130.0			146.3	72.8			238.8	666.7	
1237+00.00 to 1246+50.00		5.5	205.8			231.6	115.3		386.7	733.6	633.3	
1246+50.00 to 1263+00.88	4952.6							4608.7		1798.8	1100.6	
1263+00.88 to 1276+97.11		8.4	313.3			340.7	169.4			1241.1	930.8	
1276+97.11 to 1277+47.11										44.4	33.3	
1284+82.78 to 1285+32.78										44.4	33.3	
1285+32.78 to 1311+50.00		15.4	577.9			638.2	311.5			2134.2	1656.5	
<i>Detour 1</i>												
01+31.00 to 01+70.98				100.3		11.0						
01+70.98 to 02+21.99				128.0		14.1						
02+21.99 to 04+05.96				461.6		50.8						
04+05.96 to 17+35.60				3397.2		373.5						45.1
17+35.60 to 19+19.56				461.6		50.8						7.0
19+19.56 to 19+70.58				128.0		14.1						
19+70.58 to 19+95.00				61.3		6.7						
<i>SIDERROADS</i>												
TOTAL FOR SIDERROADS						1771	198.4					
<i>At Traffic Barrier Terminals, Type 1, Special Flared (see next sheet for calculation)</i>												
GRAND TOTAL	4953	83	3123	4738	1771	4222	1737	4609	1335	13759	10888	52

AGGREGATE BASE COURSE, TYPE B		
Temporary Mailbox Turnouts		
<i>U.S. 45</i>		TON
1246+40.7	LT	16.7
1254+48.1	LT	22.6
SUB-TOTAL		39
Temporary Barrier		
<i>Detour 1</i>		TON
1248+50.00	to 1250+00.00	19.0
1249+00.00	to 1250+00.00	12.7
1252+75.00	to 1254+45.00	21.6
1255+00.00	to 1261+00.00	76.1
1260+00.00	to 1263+00.00	38.1
SUB-TOTAL		168
TOTAL		207

TEMPORARY ACCESS (PRIVATE ENTRANCE)		
<i>U.S. 45</i>		EACH
1246+40.7	LT	1
1252+50.0	LT	1
1252+50.0	RT	1
1254+48.1	LT	1
1254+50.3	LT	1
1252+50.0	RT	1
TOTAL		6

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<h2 style="margin: 0;">SCHEDULE OF QUANTITIES</h2> <p style="margin: 0;">SCALE: VERT. HORIZ. DATE: 10-21-05</p> <p style="margin: 0;">DRAWN BY: UJ CHECKED BY: MAR</p>