

PAGE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PARK ROADS	DIST. 8 WSC 2006-1	RANDOLPH	43	28
STA.	TO STA.			

CONTRACT NO. 76972

GENERAL LANDSCAPE PLAN NOTES

- ALL WORK UNDER THIS CONTRACT SHALL CONFORM TO ALL APPLICABLE SECTIONS OF THE STANDARD SPECIFICATIONS WITH PARTICULAR ATTENTION TO SECTION 253. PLANTING WOODY PLANTS, THE SUPPLEMENTAL SPECIFICATIONS AND THE FOLLOWING PLAN NOTES.
- CONTRACTOR SHALL VERIFY LOCATION AND DEPTH OF ALL UTILITIES PRIOR TO COMMENCEMENT OF WORK WITH LOCAL UTILITY COMPANIES AND/OR CONTRACTORS FROM OTHER PHASES OF WORK AT THE WORLD SHOOTING AND RECREATION COMPLEX. IF UTILITIES OR OTHER OBSTRUCTIONS ARE DISCOVERED WHICH CONFLICT WITH THE PLANTING PLAN, NOTIFY THE LANDSCAPE ARCHITECT (NED ENRIETTO, 618-435-8138) SO ADJUSTMENTS CAN BE MADE. DAMAGE TO ANY UTILITY AS A RESULT OF PLANTING OPERATIONS ARE THE RESPONSIBILITY OF THE CONTRACTOR.
- PROVIDE QUANTITY OF PLANT MATERIAL ON THE PLANT SUMMARY. CONTRACTOR IS RESPONSIBLE FOR INSTALLING ALL PLANTINGS AS SHOWN ON THE DRAWINGS.
- THE OWNERS REPRESENTATIVE HAS THE RIGHT TO INSPECT AND APPROVE OR REJECT ALL PLANT MATERIAL PRIOR TO INSTALLATION (NED ENRIETTO 618-435-8138).
- MEASUREMENTS, CALIPER, BRANCHING, GRADING QUALITY, BALLING AND BURLAPPING FOR ALL PLANT MATERIAL SHALL ADHERE TO THE THE AMERICAN STANDARD OF NURSERY STOCK, ANSIZ60-2004 AND THE AMERICAN NURSERY AND LANDSCAPE ASSOCIATION.
- DO NOT MAKE SUBSTITUTIONS. IF SPECIFIED LANDSCAPE MATERIAL IS NOT OBTAINABLE, SUBMIT PROOF OF NON-AVAILABILITY TO RE/LA, TOGETHER WITH PROPOSAL FOR USE OF EQUIVALENT MATERIAL. THE CONTRACTOR SHALL SUBMIT ALL REQUESTS TO THE LANDSCAPE ARCHITECT (NED ENRIETTO, 618-435-8138) FOR APPROVAL 30 DAYS PRIOR TO COMMENCING WORK.
- MAINTAIN OR PROVIDE POSITIVE DRAINAGE FLOW. DO NOT OBSTRUCT THE NATURAL OR ENGINEERED DRAINAGE FLOW PATTERNS. NOTIFY LANDSCAPE ARCHITECT (NED ENRIETTO, 618-435-8138) OF ANY DRAINAGE CONCERNS.
- CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO PROTECT EXISTING PAVED AREAS, SIDEWALKS, TURF GRASS AND EXISTING VEGETATION. ANY DAMAGE TO PAVEMENT, SHOULDERS OR RUTTING THESE AREAS SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AT THEIR EXPENSE. CONTRACTOR IS TO MAINTAIN WORK AREAS IN A NEAT AND ORDERLY MANNER.
- A PRE-PLANTING MEETING WILL BE HELD WITH DNR, DOT, CDB REPRESENTATIVES ON SITE. NUMEROUS CONTRACTORS WILL BE WORKING ON-SITE DURING THE CONSTRUCTION OF THIS PROJECT. LANDSCAPE CONTRACTOR MUST ATTEND WEEKLY ON-SITE COORDINATION MEETINGS, SCHEDULE WORK TO AVOID CONFLICTS AND COOPERATE WITH ALL CONTRACTORS.
- MAINTENANCE OF THE PLANTED AREAS THROUGH THE ACCEPTANCE PERIOD SHALL INCLUDE WATERING, PROTECTION FROM INSECTS, OTHER DISEASE, WEEDING AND PRUNING AS WELL AS REPLACEMENT OF ANY PLANTS WHICH APPEAR TO BE IN DISTRESS. TREE STAKES SHALL BE SECURE AT ALL TIMES. DEFECTIVE MATERIALS AS DETERMINED BY THE OWNER SHALL BE REPLACED IMMEDIATELY WITH SPECIMENS OF THE SAME SPECIES AND SIZE AS THE ORIGINAL.
- WEEDING AND WATERING OPERATIONS SHALL BE PERFORMED AS DIRECTED BY OWNERS REPRESENTATIVE DURING THE PERIOD OF ESTABLISHMENT IN ACCORDANCE WITH ARTICLES 253.14 AND 253.15 OF THE STANDARD SPECIFICATIONS.
- WHEN INSTALLATION HAS BEEN ACCOMPLISHED, SUBMIT TO THE OWNER'S REPRESENTATIVE A WRITTEN REQUEST FOR FINAL INSPECTION. NOTIFICATION OF ACCEPTANCE OF ALL WORK WILL BE MADE BY THE OWNER'S REPRESENTATIVE TO THE CONTRACTOR IN WRITING, EXCLUSIVE OF THE POSSIBLE REPLACEMENT OF PLANTS SUBJECT TO THE GUARANTEE.
- THE CONTRACTOR SHALL FURNISH SEEDING CLASS 1B TO ALL PLANTING ISLANDS LOCATED IN THE WEST SHOOTING LINE PARKING LOT, EVENTS CENTER PARKING LOT, PAVILION AREA PARKING LOT AND EAST SHOOTING LINE PARKING LOT.
- IDNR SHALL FURNISH THE TOPSOIL FOR ALL PLANTING ISLANDS LOCATED IN THE WEST SHOOTING LINE PARKING LOT, EVENTS CENTER PARKING LOT, PAVILION AREA PARKING LOT AND EAST SHOOTING LINE PARKING LOT. CONTACT GARY ILES (618-435-8183) TO COORDINATE THE SCHEDULE FOR THE COMPLETION OF THIS TASK.
- IDNR SHALL RE-GRADE THE OLD ROAD BED NEAR THE MAIN ENTRANCE. CONTACT GARY ILES (618-435-8183) TO COORDINATE THE SCHEDULE FOR COMPLETION OF THIS TASK.
- ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE TO BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOW TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 *ILLINOIS POWER CO.
 *EXXON MOBIL PIPELINE CO.
 *VERIZON NORTH, INC.
 (MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY *. NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.)

LIST OF STANDARDS

NONE

COMMITMENTS

NONE

ITEM NO	PAYITEM	UNIT	TOTAL QUANTITIES	PLAN CODE	COMMENTS
1	SEEDING, CLASS 1B	ACRE	2		
2	NITROGEN FERTILIZER NUTRIENT	POUND	180		
3	PHOSPHORUS FERTILIZER NUTRIENT	POUND	180		
4	POTASSIUM FERTILIZER NUTRIENT	POUND	180		
5	AGRICULTURAL GROUND LIMESTONE	TON	4		
6	MULCH, METHOD 2 (PARKING AREA ISLANDS, MAIN ENTRANCE, CAMPGROUND ENTRANCE)	ACRE	2		
7	SELECTIVE MOWING STAKES	EACH	385		
8	MOBILIZATION	L SUM	1		
9	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	151	AF 2.0"	
10	TREE, ACER RUBRUM (RED MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	122	AR 1.75"	
11	TREE, BETULA NIGRA (RIVER BIRCH), 8' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	41	BN 8'	
12	TREE, BETULA NIGRA (RIVER BIRCH), 10' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	28	BN 10'	
13	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	59	CO 1.5"	
14	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER, BALLED AND BURLAPPED	EACH	30	CO 2.0"	
15	TREE, FRAXINUS PENNSYLVANICA SUMMIT (SUMMIT GREEN ASH), 2" CALIPER, BALLED AND BURLAPPED	EACH	85	FP 2.0"	
16	TREE, LIQUIDAMBAR STYRACIFLUA (AMERICAN SWEETGUM), 2" CALIPER, BALLED AND BURLAPPED	EACH	40	LS 2.0"	
17	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	33	QB 1.5"	
18	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	65	QB 2.0"	
19	TREE, QUERCUS MACROCARPA (BUR OAK), CONTAINER GROWN, 3-GALLON	EACH	136	QM CONTAINER	
20	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	83	QM 2.0"	
21	TREE, QUERCUS PALUSTRIS (PIN OAK), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	144	QP 1.5"	
22	TREE, QUERCUS PALUSTRIS (PIN OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	81	QP 2.0"	
23	TREE, QUERCUS RUBRA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	69	QR 2.0"	
24	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 2" CALIPER, BALLED AND BURLAPPED	EACH	40	TD 2.0"	
25	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), CONTAINER GROWN, 3-GALLON	EACH	127	QB CONTAINER	
26	TREE, QUERCUS PALUSTRIS (PIN OAK), CONTAINER GROWN, 3-GALLON	EACH	221	QP CONTAINER	
27	TREE, QUERCUS RUBRA (RED OAK), CONTAINER GROWN, 3-GALLON	EACH	125	QR CONTAINER	
28	TREE, TAXODIUM DISTICHUM (BALD CYPRESS), CONTAINER GROWN, 3-GALLON	EACH	109	TD CONTAINER	
29	TREE, CRATAEGUS CRUSGALLI (THORN LESS COCKSPUR HAWTHORN), CONTAINER GROWN, 3-GALLON	EACH	90	CC CONTAINER	
30	TREE, CERCI CANADENSIS (EASTERN REDBUD), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	63	CD 6'	
31	TREE, CORNUS FLORIDA (FLOWERING DOGWOOD), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	22	CF 6'	
32	TREE, CRATAEGUS CRUSGALLI INERMIS (THORN LESS COCKSPUR HAWTHORN), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	80	CC 6'	
33	TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRABAPPLE), 8' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	94	MP 8'	
34	SHRUB, MYRICA PENNSYLVANICA (BAYBERRY), 3' HEIGHT, BALLED AND BURLAPPED	EACH	33	MB 3'	
35	SHRUB, VIBURNUM DENTATUM (ARROWWOOD VIBURNUM), 4' HEIGHT, BALLED AND BURLAPPED	EACH	70	VD 4'	
36	SHRUB, ARONIA ARBUTIFOLIA BRILLIANT ISSIMA (BRILLIANT RED CHOKEBERRY), 2'-HEIGHT, CONTAINER GROWN	EACH	28	AB CONTAINER	
37	SHRUB, CORNUS RACEMOSA (GREY DOGWOOD), CONTAINER GROWN, 3-GALLON	EACH	56	CR CONTAINER	
38	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	152	PS 6'	
39	EVERGREEN, JUNIPERUS VIRGINIANA (EASTERN RED CEDAR), CONTAINER GROWN, 3-GALLON	EACH	126	JV CONTAINER	
40	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), CONTAINER GROWN, 3-GALLON	EACH	40	PS CONTAINER	
41	HEMEROCALLIS 'HAPPY RETURNS' (1 GAL)	EACH	48	HH 6"	
42	EVERGREEN, JUNIPERUS HORIZONTALIS "PLUMOSA COMPACTA" (COMPACT ANDORRA JUNIPER), 24" SPREAD, BALLED AND BURLAPPED	EACH	35	JH CONTAINER	
43	SHRUB, COTONEASTER ADPRESSUS (CREEPING COTONEASTER), 30" WIDTH, BALLED AND BURLAPPED	EACH	12	CA 30"	
44	SHRUB, ITEA VIRGINICA (VIRGINIA SWEETSPIRE), CONTAINER GROWN, 3-GALLON	EACH	99	IT CONTAINER	
45	SHRUB, RHUS CAPALLINA (FLAMELEAF SUMAC), 3 GALLON, CONTAINER GROWN	EACH	30	RC CONTAINER	
46	TREE, ACER RUBRUM (RED MAPLE), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	110	AR 1.5"	
47	TREE, ACER RUBRUM (RED MAPLE), CONTAINER GROWN, 3-GALLON	EACH	376	AR CONTAINER	
48	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	81	AF 1.5"	
49	TREE, AMELANCHIER ARBOREA (DOWNY SERVICEBERRY), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	16	AA 6'	
50	TREE, BETULA NIGRA (RIVER BIRCH), CONTAINER GROWN, 3-GALLON	EACH	66	BN CONTAINER	MULTI-STEMMED
51	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), CONTAINER GROWN, 3-GALLON	EACH	44	CO CONTAINER	
52	TREE, FRAXINUS PENNSYLVANICA SUMMIT (SUMMIT GREEN ASH), CONTAINER GROWN, 3-GALLON	EACH	10	FP CONTAINER	
53	TREE, FRAXINUS PENNSYLVANICA SUMMIT (SUMMIT GREEN ASH), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	23	FP 1.5"	
54	TREE, LIQUIDAMBAR STYRACIFLUA (AMERICAN SWEETGUM), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	46	LS 1.5"	
55	TREE, LIQUIDAMBAR STYRACIFLUA (AMERICAN SWEETGUM), CONTAINER GROWN, 3-GALLON	EACH	70	LS CONTAINER	
56	TREE, QUERCUS IMBRICARIA (SHINGLE OAK), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	65	QI 1.5"	
57	TREE, QUERCUS IMBRICARIA (SHINGLE OAK), CONTAINER GROWN, 3-GALLON	EACH	62	QI CONTAINER	
58	TREE, QUERCUS RUBRA (RED OAK), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	57	QR 1.5"	
59	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	18	TD 1.5"	
60	PLANTING BED PREPARATION	SQ FT	5700		
61	ADDITIONAL TREE AND SHRUB WATERING	1000 GAL			

ILLINOIS DEPARTMENT OF TRANSPORTATION
**GENERAL NOTES
 &
 SCHEDULE OF QUANTITIES**
 PARK ROADS
 SECTION DIST. 8 WSC 2006-1
 RANDOLPH COUNTY

DRAWN BY: