

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	01-00236-00 BR	COOK	18	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 83817				

SCHEDULE OF REMOVAL				
LOCATION	SIDEWALK SQ. FT.	CC&B FOOT	CHAIN LINK FENCE FOOT	PAVEMENT REMOVAL SQ YD
<b>GARFIELD STREET</b>				
STA 10+29 TO STA 11+33	520			
STA 10+29 TO STA 10+79			50	
STA 9+92 TO STA 11+92		200		
STA 9+92 TO STA 11+92				216
<b>HARRISON STREET</b>				
STA 13+21 TO STA 14+41		115		
STA 13+90 TO STA 14+07		17		
STA 13+26 TO STA 14+41	575			
STA 13+90 TO STA 14+53	315			
STA 14+37 TO STA 14+55			18	
STA 14+06 TO STA 14+25			19	
STA 14+44 TO STA 14+49				12
<b>TOTAL</b>	1410	332	87	228

TREE REMOVAL SCHEDULE			
20100110			
LOCATION CENTERLINE	OFFSET	OFFSET DISTANCE (FT)	TREE REMOVAL (6 TO 15 UNITS DIAMETER)
<b>HARRISON AVE.</b>			
13+63	RT	15	12
<b>TOTAL</b>			12

EARTHWORK REMOVAL SCHEDULE	
20200100	
LOCATION	EARTH EXCAVATION (CY)
<b>GARFIELD AVE.</b>	
STA. 10+86.67 TO STA. 11+42.22	25
<b>HARRISON AVE.</b>	
STA. 14+00 TO STA. 14+47	11
STA. 14+44 TO STA. 14+47	4
<b>TOTAL</b>	40

PLOT DATE = 08/20/05  
 PLOT NAME = 08/20/05  
 PLOT SCALE = AS SHOWN  
 REFERENCE = 08/20/05

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		HOME AVE PEDESTRAIN BRIDGE IMPROVEMENT SCHEDULE OF QUANTITIES 1 OF 2

SCALE: NOT TO SCALE  
DATE: 09/06/05

DRAWN BY FG  
CHECKED BY SC