

CONTRACT NO. 83817

PIPE HANDRAIL SCHEDULE

LOCATION	OFFSET	SIDE	LENGTH (FT)
GARFIELD STREET			
10+74 To 11+44	24	N	69
11+04 TO 11+51	18	N	55
10+49 TO 11+44	33	N	50
10+96 TO 11+51	41	N	65
10+71 TO 10+84	29	N	13
10+96	24	N	10
HARRISON STREET			
14+05 TO 14+25	18	S	25
14+23 TO 14+37	13	S	18
TOTAL			305

DRAINAGE ITEMS SCHEDULE

LOCATION	MANHOLE TO BE ADJUSTED (EACH)	CATCH BASIN TO BE ADJUSTED (EACH)	VALVE VAULT TO BE ADJUSTED (EACH)	VALVE BOX TO BE ADJUSTED (EACH)	HAND HOLE TO BE ADJUSTED (EACH)
GARFIELD STREET					
11+84					
10+45		1			
10+58					
10+62	1				
10+54				1	
			1		
			1		1
TOTAL	1	1	2	1	1

SIDEWALK SCHEDULE

LOCATION	PCC SIDEWALK 5" (SQ. FT.)	PCC SIDEWALK 5" SPECIAL (SQ. FT.)
GARFIELD STREET		
9+92 TO 11+06	800	
10+84 TO 11+51		793
HARRISON STREET		
13+32 TO 14+15	568	
14+15 TO 14+37		153
13+96 TO 14+37	275	
TOTAL	1643	946

SEEDING AND SODDING SCHEDULE

LOCATION	SODDING (SQ. YD.)	EUONYMUS ALATA COMPACTA(EACH)	NITROGEN FERTILIZER NUTRIENT(POUND)	PHOSPHORUS FERTILIZER NUTRIENT(POUND)	POTASSIUM FERTILIZER NUTRIENT(POUND)
GARFIELD STREET					
9+92 TO 11+92	200		9	9	9
10+94 TO 11+53		26			
HARRISON STREET					
14+38 TO 14+55	21		1	1	1
TOTAL	221	26	10	10	10

CONCRETE CURB AND GUTTER SCHEDULE

LOCATION	CONCRETE CURB TYPE B. (FT)	CCC & G TYPE B6.12(MODIFIED)(FT.)
GARFIELD STREET		
9+92 TO 11+89		210
HARRISON STREET		
13+32 TO 14+22		90
13+90 TO 14+05		15
14+05 TO 14+37	50.5	
TOTAL	50.5	315

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
HOME AVE PEDESTRIAN BRIDGE IMPROVEMENT
SCHEDULE OF QUANTITIES 2 OF 2
SCALE: NOT TO SCALE
DATE: 09/06/05
DRAWN BY FG
CHECKED BY SC

PLT DATE = 09/06/05
FILE NAME = MTRLEA
PLOT SCALE = AS CALLED
REFERENCE = RHEP