

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2533	05-00036-00-R5	KANE	15	3
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT - LAPP		
CONTRACT NO. 83826				

			CONST. CODE
			1000
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	3216
40600300	AGGREGATE (PRIME COAT)	TON	67
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	4
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3026
42400800	DETECTABLE WARNINGS	SQ FT	192
44000009	BITUMINOUS SURFACE REMOVAL 3"	SQ YD	16078
44000600	SIDEWALK REMOVAL	SQ FT	3026
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1276
* 44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	16078
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	70
60255500	MANHOLES TO BE ADJUSTED	EACH	9
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	6
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	400
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1838
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	135
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1295
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	853
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	171
X0301059	BLOCK RETAINING WALL	SQ FT	14
X0321558	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	7
X0321690	BRICK WALL REMOVAL	FOOT	7
X0322464	ABANDON AND FILL EXISTING SANITARY MANHOLE	EACH	4
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	2265
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	675
* XX000475	RESTORATION	SQ YD	938
XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	298
XX004917	CLASS D PATCHES, SUPERPAVE, TYPE III, 10"	SQ YD	127
XX004918	CLASS D PATCHES, SUPERPAVE, TYPE IV, 10"	SQ YD	245

* SPECIALTY ITEMS

COPYRIGHT © 2005 ENGINEERING ENTERPRISES, INC.

Engineering Enterprises, Inc.
 Consulting Engineers
 52 Wheeler Road
 Sugar Grove, Illinois 60554 630/466-9350

VILLAGE OF MONTGOMERY
 1300 SOUTH BROADWAY
 MONTGOMERY, ILLINOIS 60538

1	10/17/05	PER IDOT REVIEW
2	10/31/05	PER IDOT REVIEW
NO.	DATE	REVISIONS

DESIGNED BY: ---/---
 DRAWN BY: ---/---
 CHECKED BY: ---/---

MAIN STREET LAPP IMPROVEMENTS

SUMMARY OF QUANTITIES

DATE FEBRUARY 2005
 PROJ. NO. M00091
 FILE NO. M00091A10
 SHEET **3** OF **15**