

| | | | | |
|---------------------|----------------|---------------------------|--------------|-----------|
| FAU RTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 7000 | 02-00212-00-BR | VERMILION | 59 | 5 |
| FROM STA. 96+00.00 | | TO STA. 103+10.10 | | |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |

CONTRACT NO. 91285

| CODE NUMBER | ITEM | UNIT | TOTAL | STEEL ARCH BRIDGE OVER WATERWAY | BITUMINOUS CONCRETE ROADWAY |
|-------------|---|-------|--------|---------------------------------------|-----------------------------------|
| | | | | X044-2A | I000-2A |
| 50800105 | REINFORCEMENT BARS | POUND | 20320 | 20320 | |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 133980 | 133980 | |
| 51201600 | FURNISHING STEEL PILES HP12X53 | FOOT | 192 | 192 | |
| 51202700 | DRIVING STEEL PILES | FOOT | 192 | 192 | |
| 51203600 | TEST PILE STEEL HP12X53 | EACH | 2 | 2 | |
| 51204600 | METAL SHOES | EACH | 8 | 8 | |
| 51500100 | NAME PLATES | EACH | 1 | 1 | |
| 54200427 | PIPE CULVERTS, TYPE 1 RCCP 12" | FOOT | 193 | | 193 |
| 54213447 | END SECTIONS 12" | EACH | 4 | | 4 |
| 58700200 | BRIDGE SEAT SEALER | SQ FT | 46 | 46 | |
| 59100100 | GEOCOMPOSITE WALL DRAIN | SQ YD | 94 | 94 | |
| 60107600 | PIPE UNDERDRAINS 4" | FOOT | 164 | 164 | |
| 60201340 | CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE | EACH | 4 | | 4 |
| 60240328 | INLETS, TYPE B, TYPE 24 FRAME AND GRATE | EACH | 4 | | 4 |
| 60500050 | REMOVING CATCH BASINS | EACH | 1 | | 1 |
| 60500060 | REMOVING INLETS | EACH | 6 | | 6 |
| 60602200 | CONCRETE GUTTER | FOOT | 22 | | 22 |
| 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 | FOOT | 652 | | 652 |
| * 63000000 | STEEL PLATE BEAM GUARD RAIL, TYPE A | FOOT | 325 | | 325 |
| * 63100085 | TRAFFIC BARRIER TERMINAL, TYPE 6 | EACH | 4 | | 4 |
| * 63100167 | TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT) | EACH | 4 | | 4 |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 118 | | 118 |
| 67100100 | MOBILIZATION | L SUM | 1 | | 1 |
| 70102550 | TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR | EACH | 1 | | 1 |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 886 | | 886 |
| * 78005110 | EPOXY PAVEMENT MARKING - LINE 4" | FOOT | 534 | | 534 |
| 78200405 | GUARDRAIL MARKERS | EACH | 16 | | 16 |
| 78200500 | BARRIER WALL MARKERS | EACH | 12 | | 12 |
| 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 4 | | 4 |
| X0321501 | WEED BARRIER FABRIC | SQ YD | 165 | | 165 |
| X0323341 | BRIDGE EXPANSION JOINT SYSTEM | FOOT | 80 | 80 | |
| X4066414 | BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50 | TON | 89 | | 89 |
| X4066614 | BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50 | TON | 179 | | 179 |
| XX006426 | FLOATING BEARINGS, FIXED - 550K | EACH | 1 | 1 | |
| XX006427 | FLOATING BEARINGS, GUIDED EXPANSION, 550K | EACH | 2 | 2 | |
| XX006428 | FLOATING BEARINGS, NON-GUIDED EXPANSION (550 KIP) | EACH | 1 | 1 | |
| XX003503 | FLARED END SECTION REMOVAL | EACH | 5 | | 5 |

*SPECIALTY ITEM

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

CITY OF DANVILLE, ILLINOIS
HUNGRY HOLLOW ROAD BRIDGE

SUMMARY OF QUANTITIES II

SCALE: NTS
DATE: >DATE

DRAWN BY PFR
CHECKED BY JRH

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
302 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: (312) 944-4000

ROSSFF

ATTENTION: \S:\SUBDIR\W.DCN \S:\SUBDIR\W.DCN
P-03-2005-865508 SA DOCUMENT\02336902\CIVIL\DCN\SU000PHO.DGN