



**BEGIN PROJECT
BEGIN IMPROVEMENTS
CURTIS RD.
STA. 31+00.00
(END PROJECT
IDOT STA. 51+03.29)**

**REMOVE EXISTING CULVERT = 117 FT.
TRENCH BACKFILL (SPECIAL) = 0.9 CU. YD.
LT. STA. 32+11 TO LT. STA. 33+28
PLACE CLSM FROM STA. 32+11 TO STA. 32+40
97' OF PIPE AND END SECTIONS TO BE
SALVAGED AND INSTALLED AT BARKSTALL ENTRANCE, LT. 72+24**

**REMOVE EXISTING CULVERT = 61 FT.
(NO TRENCH BACKFILL REQUIRED)
RT. STA. 127+77 TO RT. STA. 128+37**

MAILBOXES SHALL BE TEMPORARILY RELOCATED AS DIRECTED BY THE ENGINEER IN ACCORDANCE WITH THE SPECIAL PROVISIONS.

SEE PLAN AND PROFILE SHEETS FOR STORM SEWER REMOVAL AND STRUCTURE REMOVAL AND ADJUSTMENT SCHEDULES.

ALL VARIOUS SIGNS WHICH INTERFERE WITH CONSTRUCTION OPERATIONS SHALL BE REMOVED AND RELOCATED AS DIRECTED BY THE ENGINEER. SEE SPECIAL PROVISIONS.

LEGEND

- (A) STRUCTURE TO BE ADJUSTED
- (R) STRUCTURE TO BE REMOVED
- (F) STRUCTURE TO BE FILLED
- (TM) TELEPHONE MANHOLE TO BE ADJUSTED BY OTHERS
- U.P.TBRBO UTILITY POLE - TO BE RELOCATED BY OTHERS
- U.P.DND UTILITY POLE - DO NOT DISTURB
- 15" TREE REMOVAL
- DRIVEWAY PAVEMENT REMOVAL
- PAVEMENT REMOVAL
- SIDEWALK REMOVAL
- CULVERT TO BE REMOVED

**TREE REMOVAL
(6 TO 15 UNITS DIAMETER)**

STATION	OFFSET	UNIT
30+73.4	45.6' RT.	6
30+87.0	42.9' RT.	8
32+20.2	47.6' RT.	8
32+50.2	35.9' RT.	10" STUMP
37+47.4	47.3' RT.	12

**TREE REMOVAL
(OVER 15 UNITS DIAMETER)**

STATION	OFFSET	UNIT
30+48.3	32.3' RT.	20
30+61.6	33.2' RT.	18
31+18.9	33.8' RT.	18
31+92.3	42.6' RT.	16
34+91.0	50.1' RT.	16
35+56.4	44.4' RT.	16
36+60.7	48.3' RT.	24
37+67.6	47.8' RT.	18

PAVING REMOVAL SCHEDULE

LOCATION	PAVEMENT REM (SQ YD)	DRIVEWAY PAVEMENT REM (SQ YD)	SIDEWALK REM (SQ FT)
32+67.6 C to 33+90.0 C	951.7		
127+15.0 C to 129+35.0 C			
33+90.0 C to 37+90.0 C	1,014.7		
34+23.3 RT. - P.I.		97.8	
36+33.0 RT. - P.I.		66.8	
37+56.8 RT. - P.I.		51.0	
37+25.2 LT. to 37+90.0 LT.			256.9

NOTE:
THE PAVEMENT REMOVAL AND/OR DRIVEWAY PAVEMENT REMOVAL SHALL INCLUDE ANY CURBS THAT HAVE BEEN CONSTRUCTED MONOLITHIC WITH THE PAVEMENT. THE COST OF REMOVING THE CURBS SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR "PAVEMENT REMOVAL" AND/OR "DRIVEWAY PAVEMENT REMOVAL".

ILLINOIS DEPARTMENT OF TRANSPORTATION

REMOVALS/RELOCATIONS PLAN

DATE : 8-05
DRAWN BY : S.M.W.
CHECKED BY : R.L.H.

SCALE : 1"=20'