

SUMMARY OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	99-00124-02-PV	COLES	229	16 A
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	BRIDGE		TRAFFIC SIGNS	HIGHWAY LIGHTING	IMPACT ATTENUATORS
				STA. 247+85.29 TO STA. 250+65.29	80% FEDERAL 10% STATE 10% LOCAL J000-2A			
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	2			2		
73700200	REMOVE CONCRETE FOUNDATION-GROUND MOUNT	EACH	2			2		
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14864	14,864				
78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	320	320				
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	40709	40,709				
78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	1594	1,594				
78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	951	951				
78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	72	72				
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	123	123				
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	32	32				
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	5	5				
78300400	THERMOPLASTIC PAVEMENT MARKING REMOVAL	SQ FT	1039	1,039				
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1				1	
81014600	CONDUIT TRENCHED 2" DIA. INTERMEDIATE METAL	FOOT	193				193	
81014800	CONDUIT TRENCHED 3" DIA. INTERMEDIATE METAL	FOOT	80				80	
81020500	CONDUIT PUSHED, 2" DIA., INTERMEDIATE METAL	FOOT	150				150	
81500200	TRENCH AND BACKFILL FOR ELECTRIC WORK	FOOT	5600				5,600	
81600315	UNIT DUCT, 2 #6 XLP, 1 #6 XLP GROUND 1" POLYETHYLENE	FOOT	5992				5,992	
82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	10				10	
82500520	LIGHT CONTROLLER PEDESTAL MOUNT CB-RCS 60 AMP-480 VOLT	EACH	1				1	
* 83052600	LIGHT POLE, FIBERGLASS ANCHOR BASE, 45 FT. M.H., TENON MOUNT	EACH	6				6	
* 83052800	LIGHT POLE, FIBERGLASS ANCHOR BASE, 45 FT. M.H., TENON MOUNT, TWIN	EACH	2				2	
83600355	LIGHT POLE FOUNDATION METAL, 15 BOLT CIRCLE, 8" X 6'	EACH	6				6	
83600357	LIGHT POLE FOUNDATION METAL, 15 BOLT CIRCLE, 8" X 8'	EACH	2				2	
83800650	BREAKAWAY DEVICE COUPLING, WITH STAINLESS STEEL SCREEN	EACH	32				32	
F30180Y2	SEEDLING - TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 2 YEAR-OLD, BARE ROOT	UNIT	1.1	1.1				
G20050Y2	SEEDLING - CORNUS SERICEA (RED-OSIER DOGWOOD), 2 YEAR-OLD, BARE ROOT	UNIT	202	202				
* XZ193300	SURVEY MARKER, TYPE 1 (SPECIAL)	EACH	6	6				
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	194	194				

- * SEE SPECIAL PROVISIONS
- ** QUANTITY PARTIALLY OR WHOLLY ASSUMED FOR ESTABLISHMENT OF UNIT PRICE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAI-57, FAS 642
 SEC NO. 15-23K, 99-00124-02-PV
 COLES COUNTY, ILLINOIS

SCALE: NOT TO SCALE
 DATE 11/10/2005

DRAWN BY KET
 CHECKED BY SKM



11/10/2005 11:57:00 AM C:\WMS\WMS\11-10-05\11-10-05.dwg
 6