

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	99-00124-02-PV	COLES	229	14 A
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		BRIDGE		TRAFFIC SIGNS	HIGHWAY LIGHTING	IMPACT ATTENUATORS
				80% FEDERAL 10% STATE 10% LOCAL J000-2A	80% FEDERAL 10% STATE 10% LOCAL X281-2A	80% FEDERAL 10% STATE 10% LOCAL Y002-1C	80% FEDERAL 10% STATE 10% LOCAL Y030-1E			
30201500	LIME	TON	1754.9	1,754.9						
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	46912	46,912						
35100400	AGGREGATE BASE COURSE, TYPE A 5"	SQ YD	113	113						
35100900	AGGREGATE BASE COURSE, TYPE A 10"	SQ YD	3146	3,146						
35101400	AGGREGATE BASE COURSE, TYPE B	TON	1750	1,750						
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	178	178						
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3971	3,971						
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	56.3	56.3						
40800030	AGGREGATE (PRIME COAT)	TON	1	1						
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	19	19						
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	20636	20,636						
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SQ YD	20745	20,745						
42001300	PROTECTIVE COAT	SQ YD	55461	55,461						
* 42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	416		416					
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	60		60					
* 44005000	STABILIZED SHOULDER REMOVAL	SQ YD	4254	4,254						
48100100	AGGREGATE SHOULDERS, TYPE A	TON	1245	1,245						
* 48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	8606	8,606						
* 48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	10726	10,726						
* 48202800	BITUMINOUS SHOULDERS SUPERPAVE 10"	SQ YD	344	344						
48300300	PORTLAND CEMENT CONCRETE SHOULDERS 8"	SQ YD	78	78						
48300410	PORTLAND CEMENT CONCRETE SHOULDERS 9 1/2"	SQ YD	10104	10,104						
* 50105220	PIPE CULVERT REMOVAL	FOOT	270	270						
50200100	STRUCTURE EXCAVATION	CU YD	613		613					
50300225	CONCRETE STRUCTURES	CU YD	198.4		198.4					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	578.3		578.3					
50300260	BRIDGE DECK GROOVING	SQ YD	1002		1,002					
50300300	PROTECTIVE COAT	SQ YD	1628		1,628					

- * SEE SPECIAL PROVISIONS
- ** QUANTITY PARTIALLY OR WHOLLY ASSUMED FOR ESTABLISHMENT OF UNIT PRICE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAI-57, FAS 642
 SEC NO. 15-23K, 99-00124-02-PV
 COLES COUNTY, ILLINOIS

SCALE: NOT TO SCALE
 DATE 11/10/2005
 Revised 1-13-06
 DRAWN BY KET
 CHECKED BY SKM



11/10/2005
 I:\ST-0055\97-020280\DW\Sheet-C-602_02sum.dgn
 LAYOUT: 11/10/2005
 PREPARED: J.P. 10/27/05
 REVIEWED: SKM 10/27/05