

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	99-00124-02-PV	COLES	229	16
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		BRIDGE		TRAFFIC SIGNS	HIGHWAY LIGHTING	IMPACT ATTENUATORS
				80% FEDERAL 10% STATE 10% LOCAL J000-2A		STA. 247+85.29 TO STA. 250+65.29	80% FEDERAL 10% STATE 10% LOCAL X281-2A			
•• 61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	5		5					
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1387.5		1,387.5					
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2		2					
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4			4				
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	EACH	5		5					
63200310	GUARDRAIL REMOVAL	FOOT	404		404					
63500105	DELINEATORS	EACH	101		101					
• 63500310	REMOVE AND REINSTALL DELINEATORS	EACH	10		10					
66101120	BITUMINOUS SHOULDER CURB	FOOT	1224		1,224					
66201120	CONCRETE SHOULDER CURB	FOOT	90		90					
66500105	WOVEN WIRE FENCE 4'	FOOT	10759		10,759					
• 66502300	WOVEN WIRE FENCE REMOVAL	FOOT	7693		7,693					
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	96		96					
• 67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24		24					
• 67000600	ENGINEER'S FIELD LABORATORY	CAL MO	16		16					
• 67100100	MOBILIZATION	L SUM	1		1					
• 70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1		1					
• 70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1		1					
• 70103800	TRAFFIC CONTROL (SPECIAL)	L SUM	1		1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	200		200					
△ 72000100	SIGN PANEL - TYPE 1	SQ FT	379.9				379.9			
△ 72000200	SIGN PANEL - TYPE 2	SQ FT	262.8				262.8			
△ 72000300	SIGN PANEL - TYPE 3	SQ FT	1007.0				1,007.0			
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	96				96			
△ 72700100	STRUCTURAL STEEL SIGN SUPPORT- BREAKAWAY	POUND	8394				8,394			
△ 72900100	METAL POST - TYPE A	FOOT	26				26			
△ 72900200	METAL POST - TYPE B	FOOT	56				56			
△ 73000100	WOOD SIGN SUPPORT	FOOT	1415				1,415			
△ 73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	17.8				17.8			

- SEE SPECIAL PROVISIONS
- QUANTITY PARTIALLY OR WHOLLY ASSUMED FOR ESTABLISHMENT OF UNIT PRICE
- △ SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 FAI-57, FAS 642  
 SEC NO. 15-23K, 99-00124-02-PV  
 COLES COUNTY, ILLINOIS

SCALE: NOT TO SCALE  
 DATE 11/10/2005  
 DRAWN BY KET  
 CHECKED BY SKM



11/10/2005  
 LAYOUT: KET 10/27/05  
 DRAWN: D.P. 10/27/05  
 REVIEWED: SKM 10/27/05  
 I:\ST\JOSS\97\202020\CVT\Sheet\c-605\_02a.mxd