

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	99-00124-02-PV	COLES	229	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		BRIDGE		TRAFFIC SIGNS	HIGHWAY LIGHTING	IMPACT ATTENUATORS
				80% FEDERAL 10% STATE 10% LOCAL J000-2A		STA. 247+85.29 TO STA. 250+65.29				
20100110	TREE REMOVAL ( 6 TO 15 UNITS DIAMETER)	UNIT	183	183						
20100210	TREE REMOVAL ( OVER 15 UNITS DIAMTER)	UNIT	329	329						
20100500	TREE REMOVAL, ACRES	ACRE	1.4	1						
• 20200100	EARTH EXCAVATION	CU YD	66772	66,772						
• 20400800	FURNISHED EXCAVATION	CU YD	440170	440,170						
• 20700400	POROUS GRANULAR EMBANKMENT (SPECIAL)	CU YD	415		415					
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	23163	23,163						
△ 25000200	SEEDING, CLASS 2	ACRE	22.0	22.0						
△ 25000210	SEEDING, CLASS 2A	ACRE	61.5	61.5						
△ 25000300	SEEDING, CLASS 3	ACRE	1.0	1.0						
△ 25000314	SEEDING, CLASS 4B	ACRE	2.1	2.1						
△ 25000320	SEEDING, CLASS 5	ACRE	10.7	10.7						
△ 25000350	SEEDING, CLASS 7	ACRE	100.9	100.9						
△ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	8758	8,758						
△ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	8758	8,758						
△ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	8758	8,758						
△ 25000700	AGRICULTURAL GROUND LIMESTONE	TON	194.6	194.6						
25000750	MOWING	ACRE	100.9	100.9						
△ 25100115	MULCH, METHOD 2	ACRE	84.5	84.5						
△ 25100125	MULCH, METHOD 3	ACRE	12.8	12.8						
△ 25100630	EROSION CONTROL BLANKET	SQ YD	8903	8,903						
28000300	TEMPORARY DITCH CHECKS	EACH	96	96						
28000400	PERIMETER EROSION BARRIER	FOOT	19091	19,091						
28000500	INLET AND PIPE PROTECTION	EACH	28	28						
28100103	STONE RIPRAP, CLASS A3	SQ YD	327	327						
28100107	STONE RIPRAP, CLASS A4	SQ YD	714	714						
28100109	STONE RIPRAP, CLASS A5	SQ YD	76	76						
28100149	STONE RIPRAP, CLASS C5	SQ YD	22	22						
28200200	FILTER FABRIC	SQ YD	1117	1,117						

- SEE SPECIAL PROVISIONS
- QUANTITY PARTIALLY OR WHOLLY ASSUMED FOR ESTABLISHMENT OF UNIT PRICE
- △ SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 FAI-57, FAS 642  
 SEC NO. 15-23K, 99-00124-02-PV  
 COLES COUNTY, ILLINOIS

SCALE: NOT TO SCALE  
 DATE 08/08/2005  
 DRAWN BY KET  
 CHECKED BY SKM



08/08/2005  
 1997.0655.97.620200/Civil/Sheet-601\_02sum.qgn  
 LAYOUT MET 05/24/05  
 DRAWN LJP 05/27/05  
 REVIEWED SKM 06/01/05