

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	99-00124-02-PV	COLES	229	15
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		BRIDGE		TRAFFIC SIGNS		HIGHWAY LIGHTING		IMPACT ATTENUATORS							
				80% FEDERAL	10% STATE	10% LOCAL	J000-2A	80% FEDERAL	10% STATE	10% LOCAL	X281-2A	80% FEDERAL	10% STATE	10% LOCAL	Y002-1C	80% FEDERAL	10% STATE	10% LOCAL	Y030-1E
50300260	BRIDGE DECK GROOVING	SQ YD	1002																
50300300	PROTECTIVE COAT	SQ YD	1628																
50400735	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 63"	FOOT	2178.5																
50800105	REINFORCEMENT BARS	POUND	5420		5,420														
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	151240																
51100100	SLOPE WALL 4 INCH	SQ YD	690																
51201600	FURNISHING STEEL PILES HP12X53	FOOT	3574																
51202700	DRIVING STEEL PILES	FOOT	3574																
51203600	TEST PILE STEEL HP12X53	EACH	3																
51500100	NAME PLATES	EACH	1																
54003000	CONCRETE BOX CULVERTS	CU YD	31.8		31.8														
54010603	PRECAST CONCRETE BOX CULVERT 6' x 3'	FOOT	357		357														
54020603	PRECAST CONCRETE BOX CULVERT 6' x 3' (M273)	FOOT	76		76														
54020804	PRECAST CONCRETE BOX CULVERT 8' x 4' (M273)	FOOT	270		270														
54200427	PIPE CULVERT, TYPE 1, RCCP 12"	FOOT	191		191														
54200430	PIPE CULVERT, TYPE 1, RCCP 15"	FOOT	234		234														
54200439	PIPE CULVERT, TYPE 1, RCCP 24"	FOOT	8		8														
54200451	PIPE CULVERT, TYPE 1, RCCP 36"	FOOT	925		925														
54207789	PIPE CULVERTS, TYPE 1, CORR. STEEL OR ALUMINUM, EQUIVALENT ROUND-SIZE 24"	FOOT	421		421														
54207801	PIPE CULVERTS, TYPE 1, CORR. STEEL OR ALUMINUM, EQUIVALENT ROUND-SIZE 36"	FOOT	183		183														
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2		2														
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	6		6														
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1		1														
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	23		23														
*54215547	METAL END SECTIONS, 12"	EACH	18		18														
*54215769	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	22		22														
*54215781	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 36"	EACH	8		8														
54247170	GRATING FOR CONCRETE FLARED END SECTIONS 36"	EACH	3		3														
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	392		392														

- SEE SPECIAL PROVISIONS
- QUANTITY PARTIALLY OR WHOLLY ASSUMED FOR ESTABLISHMENT OF UNIT PRICE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAI-57, FAS 642
 SEC NO. 15-23K, 99-00124-02-PV
 COLES COUNTY, ILLINOIS

SCALE: NOT TO SCALE
 DATE 07/13/2005
 DRAWN BY KET
 CHECKED BY SKM

