CONTRACT # 91353

| F.A.S. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 642 | 99-00124-02-PV | COLES | 229 | 16 A |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

# SUMMARY OF QUANTITIES

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | ROADWAY 80% FEDERAL 10% STATE 10% LOCAL J000-2A | BRIDGE STA. 247+85.29 TO STA. 250+65.29 80% FEDERAL 10% STATE 10% LOCAL X281-2A | TRAFFIC SIGNS 80% FEDERAL 10% STATE 10% LOCAL Y002-1C | HIGHWAY LIGHTING 80% FEDERAL 10% STATE 10% LOCAL Y030-1E | IMPACT ATTENUATORS 80% FEDERAL 10% STATE 10% LOCAL SFTY-3N |
|---|---|---|---|---|---|---|---|---|
| △ 72900200 | METAL POST - TYPE B | FOOT | 56 | | | 56 | | |
| △ 73000100 | WOOD SIGN SUPPORT | FOOT | 1415 | | | 1,415 | | |
| △ 73400200 | DRILLED SHAFT CONCRETE FOUNDATIONS | CU YD | 17.8 | | | 17.8 | | |
| 73700100 | REMOVE GROUND-MOUNTED SIGN SUPPORT | EACH | 2 | | | 2 | | |
| 73700200 | REMOVE CONCRETE FOUNDATION-GROUND MOUNT | EACH | 2 | | | 2 | | |
| △ 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 14864 | 14,864 | | | | |
| △ 78005100 | EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 320 | 320 | | | | |
| △ 78005110 | EPOXY PAVEMENT MARKING - LINE 4" | FOOT | 40709 | 40,709 | | | | |
| △ 78005140 | EPOXY PAVEMENT MARKING - LINE 8" | FOOT | 1594 | 1,594 | | | | |
| △ 78005150 | EPOXY PAVEMENT MARKING - LINE 12" | FOOT | 951 | 951 | | | | |
| △ 78005180 | EPOXY PAVEMENT MARKING - LINE 24" | FOOT | 72 | 72 | | | | |
| △ 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 123 | 123 | | | | |
| 78200100 | MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR | EACH | 32 | 32 | | | | |
| • 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 5 | 5 | | | | |
| 78300400 | THERMOPLASTIC PAVEMENT MARKING REMOVAL | SQ FT | 1039 | 1,039 | | | | |
| △ 80400100 | ELECTRIC SERVICE INSTALLATION | EACH | 1 | | | | 1 | |
| △ 81014600 | CONDUIT TRENCHED 2" DIA. INTERMEDIATE METAL | FOOT | 193 | | | | 193 | |
| △ 81014800 | CONDUIT TRENCHED 3" DIA. INTERMEDIATE METAL | FOOT | 80 | | | | 80 | |
| △ 81020500 | CONDUIT PUSHED, 2" DIA., INTERMEDIATE METAL | FOOT | 150 | | | | 150 | |
| △ 81500200 | TRENCH AND BACKFILL FOR ELECTRIC WORK | FOOT | 5600 | | | | 5,600 | |
| △ 81600315 | UNIT DUCT, 2 #6 XLP, 1 #6 XLP GROUND 1" POLYETHYLENE | FOOT | 5992 | | | | 5,992 | |
| △ 82103900 | LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT | EACH | 10 | | | | 10 | |
| △ 82500520 | LIGHT CONTROLLER PEDESTAL MOUNT CB-RCS 60 AMP-480 VOLT | EACH | 1 | | | | 1 | |
| △ • 83052600 | LIGHT POLE, FIBERGLASS ANCHOR BASE, 45 FT. M.H., TENON MOUNT | EACH | 6 | | | | 6 | |
| △ • 83052800 | LIGHT POLE, FIBERGLASS ANCHOR BASE, 45 FT. M.H., TENON MOUNT, TWIN | EACH | 2 | | | | 2 | |
| △ 83600355 | LIGHT POLE FOUNDATION METAL, 15 BOLT CIRCLE, 8" X 6' | EACH | 6 | | | | 6 | |
| △ 83600357 | LIGHT POLE FOUNDATION METAL, 15 BOLT CIRCLE, 8" X 8' | EACH | 2 | | | | 2 | |
| △ 83800650 | BREAKAWAY DEVICE COUPLING, WITH STAINLESS STEEL SCREEN | EACH | 32 | | | | 32 | |
| △ F30180Y2 | SEEDLING - TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 2 YEAR-OLD, BARE ROOT | UNIT | 109 | 109 | | | | |

• SEE SPECIAL PROVISIONS

•• QUANTITY PARTIALLY OR WHOLLY ASSUMED FOR ESTABLISHMENT OF UNIT PRICE

△ SPECIALITY ITEMS

| REVISIONS | |
|---|---|
| NAME | DATE |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
FAI-57, FAS 642
SEC NO. 15-23K, 99-00124-02-PV
COLES COUNTY, ILLINOIS

SCALE: NOT TO SCALE — DRAWN BY KET

DATE 10/05/2005 — CHECKED BY SKM

© Copyright Hanson Professional Services Inc. 2005

HANSON

10/05/2005
I:\57_IDOT\SYS\fa2028\CIVIL\Sheets\c-606_02sum.dgn

| | | |
|---|---|---|
| LAYOUT | KET | 05/24/05 |
| DRAWN | KET | 05/25/05 |
| REVIEWED | SKM | 09/01/05 |