CONTRACT # 91353

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	99-00124-02-PV	COLES	229	17
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 80% FEDERAL 10% STATE 10% LOCAL J000-2A	BRIDGE STA. 247+85.29 TO STA. 250+65.29 80% FEDERAL 10% STATE 10% LOCAL X281-2A	TRAFFIC SIGNS 80% FEDERAL 10% STATE 10% LOCAL Y002-1C	HIGHWAY LIGHTING 80% FEDERAL 10% STATE 10% LOCAL Y030-1E	IMPACT ATTENUATORS 80% FEDERAL 10% STATE 10% LOCAL SFTY-3N
* X0301766	DRILL AND GROUT #6 TIE BARS	EACH	1915	1,915				
* X0322903	SAW CUTTING, (FULL DEPTH)	FOOT	3868	3,868				
* X0728700	GRATING FOR BOX CULVERT 6' X 3'	EACH	4	4				
* X4066490	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, IL 9.5L (LOW ESAL)	TON	529	529				
* X4073041	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 8"	SQ YD	3751	3,751				
* X4073101	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 11"	SQ YD	16305	16,305				
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	104	104				
X6064201	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06	FOOT	4763	4,763				
* X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1				
* XX002162	PARTIAL REMOVAL OF EXISTING STRUCTURES	EACH	2	2				
* XX003503	FLARED END SECTION REMOVAL	EACH	4	4				
XX004350	TRANSVERSE DRAINS COMPLETE	EACH	4	4				
*, **Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	50	50				
Z0002600	BAR SPLICERS	EACH	122		122			
* Z0002750	BARRICADES, TYPE III	EACH	4	4				
* Z0030090	IMPACT ATTENUATORS (SEVERE USE, WIDE) TEST LEVEL 3	EACH	2					2
*, **Z0030900	INSPECTION WELLS	EACH	140	140				
* Z0038700	PERMANENT BENCH MARKS	EACH	1		1			
* Z0054500	ROCK FILL	TON	29689	29,689				
* Z0065100	SETTLEMENT PLATFORMS	EACH	1	1				
X0356910	PRECAST CONCRETE BOX CULVERT END SECTION 8' X 4'	EACH	6	6				
X0324548	PRECAST CONCRETE BOX CULVERT END SECTION 6' X 3'	EACH	6	6				
XX004418	GRATING FOR PRECAST CONCRETE BOX CULVERT END SECTION 8' X 4'	EACH	6	6				

* SEE SPECIAL PROVISIONS

** QUANTITY PARTIALLY OR WHOLLY ASSUMED FOR ESTABLISHMENT OF UNIT PRICE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
FAI-57, FAS 642
SEC NO. 15-23K, 99-00124-02-PV
COLES COUNTY, ILLINOIS

SCALE: NOT TO SCALE — DRAWN BY KET

DATE 12/01/2005 — CHECKED BY SKM

HANSON

12/01/2005
I:\ST_IDBS\Sft_s2028\Ch1\Sheets-607_02sum.dgn

LAYOUT	KET	05/24/05
DRAWN	D.P.	05/26/05
REVIEWED	SKM	06/01/05