CONTRACT # 91353

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	99-00124-02-PV	COLES	**229**	**20**
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)

ROADWAY	BEG STATION	END STATION	QUANTITY
CH18	244+06.84	244+56.84	1
CH18	247+12.44	247+62.44	1
CH18	252+88.14	253+38.14	1
CH18	255+93.74	256+43.74	1
RAMP B	38+08.00	38+58.00	1
	CONTRACT TOTAL		5

GUARDRAIL REMOVAL

ROADWAY	BEG STA	END STA	LENGTH (FT)
I-57	878+25.34	880+02.57	177
RAMP B	37+79.00	40+06.00	227
	CONTRACT TOTAL		404

DELINEATORS

ROADWAY	QUANTITY (EA)
RAMP A	26
RAMP B	23
RAMP C	28
RAMP D	24
CONTRACT TOTAL	101

REMOVE AND REINSTALL DELINEATORS

ROADWAY	BEG STA	END STA	QUANTITY (EA)
RAMP A	916+00.00	920+00.00	2
RAMP B	872+00.00	880+00.00	3
RAMP C	880+00.00	884+00.00	2
RAMP D	916+00.00	924+00.00	3
	TOTAL		10

WOVEN WIRE FENCE REMOVAL

BEG STA	ROADWAY	END STA	ROADWAY	LENGTH (FT)
33+48.09	RAMP C	63+00.00	RAMP D	3890
39+00.00	RAMP B	14+34.31	RAMP A	3803
		CONTRACT TOTAL		7693

WOVEN WIRE FENCE, 4'

BEG STA	ROADWAY	END STA	ROADWAY	LENGTH (FT)
33+48.09	RAMP C	264+60.00	CH 18	2803
233+85.00	CH 18	39+00.00	RAMP B	2432
264+60.00	CH 18	63+00.00	RAMP D	2792
14+34.31	RAMP A	233+85.00	CH 18	2732
		CONTRACT TOTAL		10,759

EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS

ROADWAY	STATION	TYPE	DESCRIPTION	AREA (SQ FT)
CH18	168+17.40	SYMBOL	LEFT ARROW	16
CH18	168+17.40	SYMBOL	RIGHT ARROW	16
CH18	168+97.40	SYMBOL	LEFT ARROW	16
CH18	168+97.40	SYMBOL	RIGHT ARROW	16
CH18	169+76.91	SYMBOL	LEFT ARROW	16
CH18	169+76.91	SYMBOL	RIGHT ARROW	16
CH18	171+72.00	SYMBOL	LEFT ARROW	16
CH18	171+72.00	SYMBOL	RIGHT ARROW	16
CH18	172+51.42	SYMBOL	LEFT ARROW	16
CH18	172+51.42	SYMBOL	RIGHT ARROW	16
CH18	173+31.42	SYMBOL	LEFT ARROW	16
CH18	173+31.42	SYMBOL	RIGHT ARROW	16
CH18	242+55.24	SYMBOL	LEFT ARROW	16
CH18	243+35.24	SYMBOL	LEFT ARROW	16
CH18	244+15.24	SYMBOL	LEFT ARROW	16
CH18	244+45.24	SYMBOL	LEFT ARROW	16
CH18	253+55.24	SYMBOL	LEFT ARROW	16
CH18	254+35.24	SYMBOL	LEFT ARROW	16
CH18	255+15.24	SYMBOL	LEFT ARROW	16
CH18	255+95.24	SYMBOL	LEFT ARROW	16
		CONTRACT TOTAL		320

FURNISHING AND ERECTING RIGHT OF WAY MARKERS

ROADWAY	STATION	OFFSET	EACH
CH18	166+00.00	RT 70.0	1
CH18	169+75.00	RT 70.0	1
CH18	170+30.12	RT 119.35	1
CH18	171+75.00	RT 60.0	1
CH18	180+56.22	RT 60.0	1
CH18	194+00.00	RT 60.0	1
CH18	195+00.00	RT 55.0	1
CH18	198+30.89	RT 55.0	1
CH18	206+00.00	RT 65.0	1
CH18	208+00.00	RT 65.0	1
CH18	211+00.00	RT 65.0	1
CH18	211+22.00	RT 75.0	1
CH18	211+77.00	RT 75.0	1
CH18	212+00.00	RT 60.0	1
CH18	218+00.00	RT 60.0	1
CH18	224+00.00	RT 60.0	1
CH18	225+00.00	RT 65.0	1
CH18	233+85.00	RT 65.0	1
CH18	238+00.00	RT 65.0	1
CH18	240+00.00	RT 75.0	1
CH18	240+51.02	RT 150.0	1
CH18	258+34.33	RT 213.93	1
CH18	259+00.00	RT 135.0	1
CH18	264+02.00	RT 103.63	1
CH18	264+60.00	RT 100.0	1
CH18	264+88.24	RT 134.59	1
CH18	266+09.97	RT 100.56	1
CH18	266+50.00	RT 75.0	1
CH18	275+00.00	RT 75.0	1
CH18	276+00.00	RT 70.0	1
CH18	169+25.00	LT 60.0	1
CH18	170+23.59	LT 120.61	1
CH18	171+13.49	LT 124.93	1
CH18	171+50.00	LT 70.0	1
CH18	176+00.00	LT 70.0	1
CH18	178+00.00	LT 60.0	1
CH18	186+00.00	LT 60.0	1
CH18	194+00.00	LT 60.0	1
CH18	195+00.00	LT 55.0	1
CH18	198+31.98	LT 55.0	1
CH18	206+00.00	LT 55.0	1
CH18	208+00.00	LT 65.0	1
CH18	211+50.00	LT 65.0	1
CH18	217+00.00	LT 65.0	1
CH18	223+75.00	LT 65.0	1
CH18	224+20.50	LT 100.0	1
CH18	224+70.00	LT 105.0	1
CH18	225+25.00	LT 60.23	1
CH18	233+85.00	LT 59.94	1
CH18	235+33.00	LT 59.89	1
CH18	238+00.00	LT 59.80	1
CH18	240+00.00	LT 80.0	1
CH18	240+61.02	LT 116.10	1
CH18	258+49.33	LT 175.0	1
CH18	259+50.00	LT 140.0	1
CH18	262+00.00	LT 120.0	1
CH18	267+00.00	LT 70.0	1
CH18	275+65.00	LT 70.0	1
CH18	275+95.06	LT 147.76	1
CH18	276+38.97	LT 175.0	1
CH18	276+70.00	LT 70.0	1
700E	60+00.00	RT 27.50	1
700E	61+00.00	RT 40.0	1
700E	67+00.00	RT 40.0	1
700E	68+00.00	RT 45.0	1
700E	75+00.00	RT 45.0	1
700E	76+00.00	RT 25.0	1
700E	60+00.00	LT 27.50	1
700E	61+00.00	LT 40.0	1
700E	67+00.00	LT 40.0	1
700E	68+00.00	LT 50.0	1
700E	75+00.00	LT 45.0	1
700E	76+00.00	LT 30.0	1
RAMP A	14+34.33	RT 45.0	1
RAMP A	16+50.00	RT 45.0	1
RAMP A	17+50.00	RT 60.0	1
RAMP A	26+00.00	RT 60.0	1

ROADWAY	STATION	OFFSET	EACH
RAMP B	31+00.00	RT 70.0	1
RAMP B	38+00.00	RT 70.0	1
RAMP B	39+00.00	RT 48.54	1
RAMP C	33+48.07	RT 50.0	1
RAMP C	44+00.00	RT 50.0	1
RAMP C	46+00.00	RT 105.0	1
RAMP D	49+00.00	RT 120.0	1
RAMP D	51+00.00	RT 70.0	1
RAMP D	62+00.00	RT 70.0	1
RAMP D	63+00.00	RT 55.38	1
870E	1+50.00	RT 22.0	1
870E	2+50.00	RT 40.0	1
870E	5+27.37	RT 40.0	1
870E	6+75.00	RT 60.0	1
870E	1+50.00	LT 22.0	1
870E	2+50.00	LT 35.0	1
870E	4+13.00	LT 35.0	1
870E	5+35.00	LT 40.0	1
870E	6+75.00	LT 60.0	1
		CONTRACT TOTAL	96

EPOXY PAVEMENT MARKING - LINE 4"

ROADWAY	BEG STA	END STA	OFFSET	LENGTH (FOOT)
CH18	166+00.00	179+46.78	LT,EOP	1472
CH18	166+00.00	179+46.78	RT,EOP	1472
CH18	230+00.00	270+00.00	LT,EOP	3676
CH18	230+00.00	270+00.00	RT,EOP	3718
CH18	166+00.00	179+46.78	TURNLANE @ 700E	3047
CH18	232+43.56	264+89.80	MEDIANS/TURNLANES/ISLANDS	7231
CH18	230+00.00	270+00.00	℄	795
RAMP A	9+85.13	35+68.10	LT,RT	4595
RAMP B	20+23.00	49+15.50	LT,RT	4954
RAMP C	29+80.77	55+90.93	LT,RT	4644
RAMP D	40+23.00	69+90.22	LT,RT	5105
		CONTRACT TOTAL		40,709

EPOXY PAVEMENT MARKING - LINE 8"

ROADWAY	BEG STA	END STA	OFFSET	LENGTH (FOOT)
RAMP A	12+62.09	16+60.09	LT	796
RAMP C	32+62.03	36+60.96	LT	798
		CONTRACT TOTAL		1594

RAISED REFLECTIVE PAVEMENT MARKERS

ROADWAY	STATION	OFFSET	EACH
RAMP A	9+85.93 TO 18+00.09	0.50' LT	41
RAMP A	12+62.09 TO 16+60.09	LT	20
RAMP C	29+80.77 TO 38+00.96	0.50' LT	42
RAMP C	32+62.03 TO 36+60.96	LT	20
CONTRACT TOTAL			123

EPOXY PAVEMENT MARKING - LINE 24"

ROADWAY	STATION	LENGTH (FOOT)
CH18	240+61+54, LT	18
CH18	241+50.92, LT	18
CH18	256+99.43, RT	18
CH18	257+88.80, RT	18
CONTRACT TOTAL		72

EPOXY PAVEMENT MARKING - LINE 12"

ROADWAY	LOCATION	LENGTH (FOOT)
RAMP A	ISLAND	133
RAMP C	ISLAND	130
RAMP A	12+62.09 TO 16+60.09 LT	181
RAMP C	32+62.03 TO 36+60.96 LT	193
CH18	166+00.00 TO 167+82.05, LT & RT	47
CH18	173+66.78 TO 179+46.78, LT & RT	241
CH18	MEDIAN	23
CH18	MEDIAN	3
	CONTRACT TOTAL	951

CONCRETE SHOULDER CURB

ROADWAY	BEG STA	END STA	OFFSET	LENGTH (FOOT)
CH18	244+04.97	244+19.97	RT	15
CH18	245+99.97	246+14.97	RT	15
CH18	247+04.97	247+19.97	LT	15
CH18	253+25.37	253+40.37	RT	15
CH18	253+40.37	253+55.37	LT	15
CH18	256+25.37	256+40.37	LT	15
		CONTRACT TOTAL		90

REMOVE CONCRETE FOUNDATION - GROUND MOUNTED

ROADWAY	STATION	OFFSET	QUANTITY (EA.)
RAMP B	43+06.00	RT	2
		CONTRACT TOTAL	2

BITUMINOUS SHOULDER CURB

ROADWAY	BEG STA	END STA	OFFSET	LENGTH (FOOT)
CH18	244+19.97	245+99.97	RT	180
CH18	246+14.97	247+82.49	RT	168
CH18	250+62.49	253+25.37	RT	263
CH18	247+19.97	247+88.09	LT	68
CH18	250+68.09	253+40.37	LT	272
CH18	253+55.37	256+25.37	LT	270
CH18	256+40.37	256+43.74	LT	3
		CONTRACT TOTAL		1224

MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR

ROADWAY	BEG. STATION	END STATION	QUANTITY (EA)
CH18	244+06.84	253+38.14	12
CH18	247+12.44	256+43.74	12
RAMP B	38+08.00	39+95.50	4
I-57	878+25.34	880+00.29	4
CONTRACT TOTAL			32

REMOVE SIGN PANEL - TYPE 3

ROADWAY	STATION	OFFSET	QUANTITY (SQ. FT.)
RAMP B	43+06.00	RT	96
		CONTRACT TOTAL	96

REMOVE GROUND MOUNTED SIGN SUPPORT

ROADWAY	STATION	OFFSET	QUANTITY (EA.)
RAMP B	43+06.00	RT	2
		CONTRACT TOTAL	2

THERMOPLASTIC PAVEMENT MARKING-LINE, 4"

ROADWAY	BEG STA	END STA	OFFSET	LENGTH (FOOT)
CH18	179+46.78	230+00.00	LT, EOP	5094
CH18	179+46.78	230+00.00	RT, EOP	5091
CH18	270+00.00	278+00.00	LT, EOP	837
CH18	270+00.00	278+00.00	RT, EOP	800
CH18	179+46.78	230+00.00	℄	2127
CH18	270+00.00	278+00.00	℄	915
		CONTRACT TOTAL		14,864

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES-3
FAI-57, FAS 642
SEC NO. 15-23K, 99-00124-02-PV
COLES COUNTY, ILLINOIS

SCALE: NOT TO SCALE DRAWN BY JAP
DATE 07/13/2005 CHECKED BY SKM

© Copyright Hanson Professional Services Inc. 2005
HANSON

07/13/2005
I:\97JOBS\97s2028b\Civil\Sheet\C-631-SCH-02.dgn

LAYOUT	JAP	12/26/03
DRAWN	JAP	12/26/03
REVIEWED	SKM	01/29/04