

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	99-00124-02-PV	COLES	228	21
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

TERMINAL MARKER-DIRECT APPLIED

ROADWAY	STATION	QUANTITY (EA)
CH18	244+06.84	1
CH18	247+12.44	1
CH18	253+38.14	1
CH18	256+43.74	1
RAMP B	38+08.00	1
CONTRACT TOTAL		5

THERMOPLASTIC PAVMENT MARKING REMOVAL

ROADWAY	STATION	STATION	SQ.FT.
RAMP A	9+85.93	TO 16+60.09	225
RAMP B	40+33.34	TO 49+15.50	294
RAMP C	29+80.77	TO 36+60.96	227
RAMP D	61+10.12	TO 69+90.22	293
CONTRACT TOTAL			1039

SURVEY MARKER, TYPE 1 (SPECIAL)

ROADWAY	STATION	OFFSET	EACH
C.H. 18	170+82.70	75.65' RT	1
C.H. 18	171+81.22	85.43' RT	1
C.H. 18	224+68.09	60.25' LT	1
C.H. 18	250+84.26	59.36' LT	1
C.H. 18	276+33.67	54.45' LT	1
C.H. 18	277+21.57	54.28' LT	1
CONTRACT TOTAL			6

SAW CUTTING, (FULL DEPTH)

ROADWAY	BEG STA	END STA	LENGTH (FT)
RAMP A	10+00.00	16+60.09	670
RAMP B	36+24.31	48+83.34	1269
RAMP C	30+00.00	36+60.96	670
RAMP D	57+10.91	69+60.12	1259
CONTRACT TOTAL			3868

BARRICADES, TYPE III

ROADWAY	STA	QUANTITY (EACH)
CH18	278+00.00	4
CONTRACT TOTAL		4

PARTIAL REMOVAL OF EXISTING STRUCTURES

ROADWAY	STATION	QUANTITY (EA)
RAMP B	39+81.61, RT	1
RAMP C	31+36.72, RT	1
CONTRACT TOTAL		2

DRILL AND GROUT #6 TIE BARS

ROADWAY	BEG STA	END STA	QUANTITY (EACH)
RAMP A	10+00.00	16+60.09	330
RAMP B	36+24.31	48+83.34	630
RAMP C	30+00.00	36+60.96	330
RAMP D	57+10.91	69+60.12	625
CONTRACT TOTAL			1915

IMPACT ATTENUATORS (SEVERE USE, WIDE), TEST LEVEL 3

ROADWAY	LOCATION	QUANTITY (EACH)
I-57	EITHER SIDE OF BRIDGE PIER	2
CONTRACT TOTAL		2

GUARDRAIL AGGREGATE EROSION CONTROL

ROADWAY	BEG STA	END STA	OFFSET	TONS
C.H. 18	242+72.84	248+14.99	RT	55
C.H. 18	246+78.44	248+20.59	LT	18
C.H. 18	250+29.99	253+72.14	RT	42
C.H. 18	250+35.59	256+71.94	LT	79
CONTRACT TOTAL				3868
				194

PAVING SCHEDULE

STA. TO STA.	PROCESSING LIME MODIFIED SOILS 12"	AGGREGATE BASE COURSE, TYPE A 4"	AGGREGATE BASE COURSE, TYPE A 10"	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	BIT. CONCRETE SURFACE COURSE, SUPERPAVE, IL 9.5L (LOW ESAL)	BIT. CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 8"	BIT. CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 11"
	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	SQ YD	SQ YD
COUNTY HIGHWAY 18								
166+00.00 TO 179+46.78	7935	7935		7445				
179+46.78 TO 230+00.00	16201							13941
230+00.00 TO 248+15.29		7265		6285				
250+35.29 TO 270+00.00		7942		6906				
270+00.00 TO 278+00.00	3650							2364
RAMP A								
10+00.00 TO 35+68.10	5898	5898			5124			
RAMP B								
20+23.00 TO 48+83.34	5880	5880			5150			
RAMP C								
30+00.00 TO 55+90.93	5967	5967			5202			
RAMP D								
40+23.00 TO 69+60.12	6025	6025			5269			
TOWNSHIP ROAD 700								
60+00.00 TO 69+21.20	2850						2441	
71+82.95 TO 76+78.60	1530						1310	
TOWNSHIP ROAD 780								
6+00.00 TO 9+36.91	957		808			136		
TOWNSHIP ROAD 800								
10+62.90 TO 12+35.00	418		341			57		
TOWNSHIP ROAD 870								
1+50.00 TO 9+32.69	1918		1570			264		
TOWNSHIP ROAD 900								
10+62.20 TO 12+53.54	512		427			72		
CONTRACT TOTAL	77995	46912	3146	20636	20745	529	3751	16305

• FURNISHED EXCAVATION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES-4
 FAI-57, FAS 642
 SEC NO. 15-23K, 99-00124-02-PV
 COLES COUNTY, ILLINOIS

SCALE: NOT TO SCALE
 DATE: 08/11/2005
 DRAWN BY: JAP
 CHECKED BY: SKM



08/11/2005
 I:\ST\1085\ST_620289\CH18\Map\6-31-SCH-02.dgn

LAYOUT	JAP	12/26/03
DRAWN	JAP	12/26/03
REVISIONS	SKM	01/29/04